



STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION

ROY COOPER  
GOVERNOR

J. ERIC BOYETTE  
SECRETARY

August 17, 2020

**NOTICE TO PROSPECTIVE BIDDERS**

**Contract Number:** DH00312  
**WBS Number:** 15408.1019012  
**County:** Chatham  
**Description:** Emergency Pipe Replacement on NC 42 Between SR 1918 (Dickens Rd.) and SR 1912 (Christians Chapel Rd.)

**Subject:** Addendum #1

The following revisions have been made to the project proposal associated with the above referenced project:

- Bidders shall replace the original Itemized Proposal List for Contract No. DH00312 bid form with the attached correct Itemized Proposal List for Contract No. DH00312 bid form.
- Bidders shall apply Addendum files that are available on the Bidding & Letting website.

Proposal packages may be obtained from the Division 8 website at:

<https://connect.ncdot.gov/letting/Pages/Division8Letting.aspx>

For questions, please contact me at (910) 773-8034 or [cgbrown1@ncdot.gov](mailto:cgbrown1@ncdot.gov).

Sincerely,

DocuSigned by:  
*Chad G. Brown*  
15C686F6ED674C5...

Chad G. Brown  
Division Proposal Engineer

cc: File  
ec: Mr. D. R. Garner    Prospective Bidders,    Plan Rooms

County : Chatham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0043000000-N	226	GRADING	Lump Sum	L.S.	
0003	0320000000-E	300	FOUNDATION CONDITIONING GEO-TEXTILE	200 SY		
0004	0987000000-E	310	GENERIC PIPE ITEM Corrugated Aluminum Pipe Arch (73" X 55" 12 Gauge, 3 x 1 Co rrugation)	60 LF		
0005	1077000000-E	SP	#57 STONE	315 TON		
0006	1121000000-E	520	AGGREGATE BASE COURSE	400 TON		
0007	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	50 TON		
0008	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	16 TON		
0009	3635000000-E	876	RIP RAP, CLASS II	70 TON		
0010	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	100 SY		
0011	3691000000-N	SP	GENERIC EROSION CONTROL ITEM DIVERSION PUMPPING	1 EA		
0012	4457000000-N	SP	TEMPORARY TRAFFIC CONTROL	Lump Sum	L.S.	
0013	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	200 LF		
0014	6000000000-E	1605	TEMPORARY SILT FENCE	200 LF		
0015	6036000000-E	1631	MATTING FOR EROSION CONTROL	200 SY		
0016	6070000000-N	1639	SPECIAL STILLING BASINS	1 EA		
0017	6071010000-E	SP	WATTLE	80 LF		

County : Chatham

---

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	6084000000-E	1660	SEEDING & MULCHING	0.2		
				ACR		

---

---

1228/Aug17/Q1896.2/D57068110000/E18

Total Amount Of Bid For Entire Project :

---