



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

ROY COOPER
GOVERNOR

J. ERIC BOYETTE
SECRETARY

February 6, 2023

TO: Prospective Bidders
FROM: Jeff Turner, Division Proposals Engineer
SUBJECT: **Addendum #1**
Contract: DI00314
17BP.9.R.80 – Rowan County
Bridge No. 790155 over Unnamed Creek on SR 2136 (Agner Road)
Grading, Drainage, Paving, and Structure

The subject contract proposal contains the following addendum:

1. Revised Bid Form – Line 20 “Frame with Grate (840.35)” has been removed.

This addendum officially becomes part of the contract.

County: ROWAN

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|------------------------|--------------|-------|---|------------|-----------|--------|
| STRUCTURE ITEMS | | | | | | |
| 0001 | 0000100000-N | 800 | MOBILIZATION | Lump Sum | L.S. | |
| 0002 | 0000400000-N | 801 | CONSTRUCTION SURVEYING | Lump Sum | L.S. | |
| 0003 | 0030000000-N | SP | TYPE II MODIFIED APPROACH FILL, STATION ***** (STA 13+82.5) | Lump Sum | L.S. | |
| 0004 | 0043000000-N | 226 | GRADING | Lump Sum | L.S. | |
| 0005 | 0050000000-E | 226 | SUPPLEMENTARY CLEARING & GRUBBING | 1 ACR | | |
| 0006 | 0318000000-E | 300 | FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES | 10 TON | | |
| 0007 | 0320000000-E | 300 | FOUNDATION CONDITIONING GEOTEXTILE | 20 SY | | |
| 0008 | 0366000000-E | 310 | 15" RC PIPE CULVERTS, CLASS III | 40 LF | | |
| 0009 | 0582000000-E | 310 | 15" CS PIPE CULVERTS, 0.064" THICK | 20 LF | | |
| 0010 | 1099500000-E | 505 | SHALLOW UNDERCUT | 100 CY | | |
| 0011 | 1099700000-E | 505 | CLASS IV SUBGRADE STABILIZATION | 100 TON | | |
| 0012 | 1220000000-E | 545 | INCIDENTAL STONE BASE | 20 TON | | |
| 0013 | 1330000000-E | 607 | INCIDENTAL MILLING | 140 SY | | |
| 0014 | 1491000000-E | 610 | ASPHALT CONC BASE COURSE, TYPE B25.0C | 320 TON | | |
| 0015 | 1503000000-E | 610 | ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C | 320 TON | | |
| 0016 | 1519000000-E | 610 | ASPHALT CONC SURFACE COURSE, TYPE S9.5B | 300 TON | | |
| 0017 | 1575000000-E | 620 | ASPHALT BINDER FOR PLANT MIX | 50 TON | | |

County: ROWAN

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--|-------------|-----------|--------|
| 0018 | 2000000000-N | 806 | RIGHT-OF-WAY MARKERS | 10 EA | | |
| 0019 | 2286000000-N | 840 | MASONRY DRAINAGE STRUCTURES | 2 EA | | |
| 0021 | 2367000000-N | 840 | FRAME WITH TWO GRATES, STD 840.29 | 2 EA | | |
| 0022 | 2556000000-E | 846 | SHOULDER BERM GUTTER | 60 LF | | |
| 0023 | 3030000000-E | 862 | STEEL BEAM GUARDRAIL | 112.5 LF | | |
| 0024 | 3150000000-N | 862 | ADDITIONAL GUARDRAIL POSTS | 5 EA | | |
| 0025 | 3215000000-N | SP | GUARDRAIL ANCHOR UNITS, TYPE III | 4 EA | | |
| 0026 | 3287000000-N | SP | GUARDRAIL END UNITS, TYPE TL-3 | 4 EA | | |
| 0027 | 3649000000-E | 876 | RIP RAP, CLASS B | 3 TON | | |
| 0028 | 3656000000-E | 876 | GEOTEXTILE FOR DRAINAGE | 230 SY | | |
| 0029 | 4155000000-N | 907 | DISPOSAL OF SIGN SYSTEM, U- CHANNEL | 4 EA | | |
| 0030 | 4400000000-E | 1110 | WORK ZONE SIGNS (STATIONARY) | 373 SF | | |
| 0031 | 4410000000-E | 1110 | WORK ZONE SIGNS (BARRICADE MOUNTED) | 94 SF | | |
| 0032 | 4445000000-E | 1145 | BARRICADES (TYPE III) | 64 LF | | |
| 0033 | 4810000000-E | 1205 | PAINT PAVEMENT MARKING LINES (4") | 4,960 LF | | |
| 0034 | 6000000000-E | 1605 | TEMPORARY SILT FENCE | 1,405 LF | | |
| 0035 | 6006000000-E | 1610 | STONE FOR EROSION CONTROL, CLASS A | 105 TON | | |

County: ROWAN

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---------------------------------------|-------------|-----------|--------|
| 0036 | 6009000000-E | 1610 | STONE FOR EROSION CONTROL, CLASS B | 25 TON | | |
| 0037 | 6012000000-E | 1610 | SEDIMENT CONTROL STONE | 200 TON | | |
| 0038 | 6015000000-E | 1615 | TEMPORARY MULCHING | 0.5 ACR | | |
| 0039 | 6018000000-E | 1620 | SEED FOR TEMPORARY SEEDING | 100 LB | | |
| 0040 | 6021000000-E | 1620 | FERTILIZER FOR TEMPORARY SEEDING | 0.5 TON | | |
| 0041 | 6024000000-E | 1622 | TEMPORARY SLOPE DRAINS | 200 LF | | |
| 0042 | 6029000000-E | SP | SAFETY FENCE | 200 LF | | |
| 0043 | 6030000000-E | 1630 | SILT EXCAVATION | 70 CY | | |
| 0044 | 6036000000-E | 1631 | MATTING FOR EROSION CONTROL | 7,500 SY | | |
| 0045 | 6037000000-E | SP | COIR FIBER MAT | 100 SY | | |
| 0046 | 6042000000-E | 1632 | 1/4" HARDWARE CLOTH | 895 LF | | |
| 0047 | 6048000000-E | SP | FLOATING TURBIDITY CURTAIN | 140 SY | | |
| 0048 | 6071012000-E | SP | COIR FIBER WATTLE | 90 LF | | |
| 0049 | 6071020000-E | SP | POLYACRYLAMIDE (PAM) | 85 LB | | |
| 0050 | 6084000000-E | 1660 | SEEDING & MULCHING | 0.5 ACR | | |
| 0051 | 6087000000-E | 1660 | MOWING | 0.5 ACR | | |
| 0052 | 6090000000-E | 1661 | SEED FOR REPAIR SEEDING | 50 LB | | |

County: ROWAN

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---|-------------|-----------|--------|
| 0053 | 6093000000-E | 1661 | FERTILIZER FOR REPAIR SEEDING | 0.25 TON | | |
| 0054 | 6096000000-E | 1662 | SEED FOR SUPPLEMENTAL SEEDING | 50 LB | | |
| 0055 | 6108000000-E | 1665 | FERTILIZER TOPDRESSING | 0.25 TON | | |
| 0056 | 6114500000-N | 1667 | SPECIALIZED HAND MOWING | 10 MHR | | |
| 0057 | 6117000000-N | SP | RESPONSE FOR EROSION CONTROL | 15 EA | | |
| 0058 | 6117500000-N | SP | CONCRETE WASHOUT STRUCTURE | 2 EA | | |
| 0059 | 8035000000-N | 402 | REMOVAL OF EXISTING STRUCTURE AT STATION ***** (STA 13+82.50) | Lump Sum | L.S. | |
| 0060 | 8065000000-N | SP | ASBESTOS ASSESSMENT | Lump Sum | L.S. | |
| 0061 | 8096000000-E | 450 | PILE EXCAVATION IN SOIL | 221 LF | | |
| 0062 | 8097000000-E | 450 | PILE EXCAVATION NOT IN SOIL | 112 LF | | |
| 0063 | 8121000000-N | 412 | UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (STA 13+82.50) | Lump Sum | L.S. | |
| 0064 | 8182000000-E | 420 | CLASS A CONCRETE (BRIDGE) | 43.2 CY | | |
| 0065 | 8210000000-N | 422 | BRIDGE APPROACH SLABS, STATION ***** (STA 13+43) | Lump Sum | L.S. | |
| 0066 | 8217000000-E | 425 | REINFORCING STEEL (BRIDGE) | 5,272 LB | | |
| 0067 | 8328200000-E | 450 | PILE DRIVING EQUIPMENT SETUP FOR *** STEEL PILES (HP 12X53) | 14 EA | | |
| 0068 | 8364000000-E | 450 | HP 12 X 53 STEEL PILES | 385 LF | | |

County: ROWAN

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---|--------------|-----------|--------|
| 0069 | 8505000000-E | 460 | VERTICAL CONCRETE BARRIER RAIL | 110.25 LF | | |
| 0070 | 8590000000-E | 876 | RIP RAP, CLASS ** (CLASS II) | 250 TON | | |
| 0071 | 8622000000-E | 876 | GEOTEXTILE FOR DRAINAGE | 275 SY | | |
| 0072 | 8657000000-N | 430 | ELASTOMERIC BEARINGS | Lump Sum | L.S. | |
| 0073 | 8762000000-E | 430 | 3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS | 605 LF | | |

1323/Feb06/Q25909.45/D340189932000/E72

Total Amount Of Bid For Entire Project :