




STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

ROY COOPER
GOVERNOR

J. ERIC BOYETTE
SECRETARY

February 14, 2022

TO: Prospective Bidders

FROM: Jeff Turner,  Division Proposals Engineer

SUBJECT: **Addendum #1**
Contract: DI00228
R- 5828; WBS 47100.3.1
Grading, Drainage, Paving, Roundabout
US 311 (North Main Street) @ SR 1918 (First Street) in Walnut Cove in Stokes
County

The subject contract proposal contains the following addendum:

1. Plans have been revised.
 - Updated Index of Sheets.
 - Removed Duplicate Plan Sheet W1.
 - Added X-Section plan sheets.
 - Revised pavement schedule on Plan Sheet 2A-1 and 2A-2.
2. Add 7" Concrete Truck Apron Special Provision.
3. The bid form has been revised.
 - Bid Form Page 2 – Line # 31 has been deleted.
 - Bid Form Page 8 – Line # 135 has been deleted;
 - Line #680 & #685 have been added.

This addendum officially becomes part of the contract.

Mailing Address:
NC DEPARTMENT OF TRANSPORTATION
DIVISION 9 – PROJECT DEVELOPMENT
375 SILAS CREEK PARKWAY
WINSTON-SALEM, NC 27127

Telephone: (336) 747-7800
Fax: (336) 761-2004
Website: www.ncdot.gov

Location:
375 SILAS CREEK PARKWAY
WINSTON-SALEM, NC 27127

7" CONCRETE TRUCK APRON:

Description

Construct 7" Concrete Truck Apron in accordance with Section 848 of the *Standard Specifications* as modified by the typical section in the plans and this provision.

Materials

Concrete shall be Class A Concrete meeting the requirements of Section 1000 of the *Standard Specifications*.

Wire mesh reinforcement shall be 4x4 - W3.5 x W3.5 or 6x6 - W5 x W5 wire mesh meeting the requirements of Section 1070 of the *Standard Specifications*.

Joints, aligned radially, shall be placed in the concrete. The spacing of these joints shall be 15' or less on top of variable depth of aggregate base course.

County : Stokes

Addendum #1 - 02-14-2022

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0004	0036000000-E	225	UNDERCUT EXCAVATION	450 CY		
0005	0043000000-N	226	GRADING	Lump Sum	L.S.	
0006	0134000000-E	240	DRAINAGE DITCH EXCAVATION	20 CY		
0007	0192000000-N	260	PROOF ROLLING	5 HR		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	200 CY		
0009	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA-TION	500 SY		
0010	0245000000-E	SP	GENERIC GRADING ITEM (FOAM INSTALLATION SOIL STABILIZATION)	300 GAL		
0011	0255000000-E	SP	GENERIC GRADING ITEM (HAUL & DISP OF PETRO CONTAMINATED SOIL)	50 TON		
0012	0318000000-E	300	FOUNDATION CONDITIONING MATE-RIAL, MINOR STRUCTURES	435 TON		
0013	0320000000-E	300	FOUNDATION CONDITIONING GEO-TEXTILE	138 SY		
0014	0335200000-E	305	15" DRAINAGE PIPE	260 LF		
0015	0335400000-E	305	24" DRAINAGE PIPE	56 LF		
0016	0343000000-E	310	15" SIDE DRAIN PIPE	44 LF		
0017	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	664 LF		
0018	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	72 LF		

County : Stokes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	218 LF		
0020	0453000000-E	310	*** PIPE END SECTION (18")	1 EA		
0021	0636000000-E	310	*** CS PIPE ELBOWS, ***** THICK (15", 0.064")	6 EA		
0022	0995000000-E	340	PIPE REMOVAL	250 LF		
0023	1099500000-E	505	SHALLOW UNDERCUT	100 CY		
0024	1099700000-E	505	CLASS IV SUBGRADE STABILIZATION	190 TON		
0025	1330000000-E	607	INCIDENTAL MILLING	230 SY		
0026	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	1,480 TON		
0027	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	730 TON		
0028	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	100 TON		
0029	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	880 TON		
0030	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	165 TON		
0032	2000000000-N	806	RIGHT-OF-WAY MARKERS	25 EA		
0033	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		
0034	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	23 EA		
0035	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	23 LF		
0036	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	1 EA		
0037	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	1 EA		

County : Stokes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (TYPE E)	2 EA		
0039	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (TYPE F)	4 EA		
0040	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (TYPE G)	9 EA		
0041	2396000000-N	840	FRAME WITH COVER, STD 840.54	1 EA		
0042	2407000000-N	840	STEEL FRAME WITH TWO GRATES, STD 840.37	5 EA		
0043	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	1,640 LF		
0044	2591000000-E	848	4" CONCRETE SIDEWALK	360 SY		
0045	2605000000-N	848	CONCRETE CURB RAMPS	2 EA		
0046	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	410 SY		
0047	2752000000-E	SP	GENERIC PAVING ITEM (2' MODIFIED VALLEY CURB)	360 LF		
0048	2762000000-E	SP	GENERIC PAVING ITEM (SLAB LEVELING, UNDERLNG & VOI D FILL)	450 LB		
0049	3030000000-E	862	STEEL BEAM GUARDRAIL	87.5 LF		
0050	3045000000-E	862	STEEL BEAM GUARDRAIL, SHOP CURVED	50 LF		
0051	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0052	3195000000-N	862	GUARDRAIL END UNITS, TYPE AT-1	1 EA		
0053	3210000000-N	862	GUARDRAIL END UNITS, TYPE CAT-1	1 EA		
0054	3287000000-N	SP	GUARDRAIL END UNITS, TYPE TL-3	1 EA		
0055	3288000000-N	SP	GUARDRAIL END UNITS, TYPE TL-2	1 EA		

County : Stokes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	3360000000-E	863	REMOVE EXISTING GUARDRAIL	360		LF
0057	3536000000-E	866	CHAIN LINK FENCE, 48" FABRIC	77		LF
0058	3542000000-E	866	METAL LINE POSTS FOR 48" CHAIN LINK FENCE	7		EA
0059	3548000000-E	866	METAL TERMINAL POSTS FOR 48" CHAIN LINK FENCE	4		EA
0060	3649000000-E	876	RIP RAP, CLASS B	217		TON
0061	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	690		SY
0062	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	148		SF
0063	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (F)	14		SF
0064	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	359		LF
0065	4102000000-N	904	SIGN ERECTION, TYPE E	25		EA
0066	4108000000-N	904	SIGN ERECTION, TYPE F	2		EA
0067	4116100000-N	904	SIGN ERECTION, RELOCATE TYPE **** (GROUND MOUNTED) (TYPE D)	1		EA
0068	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	11		EA
0069	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	1		EA
0070	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	397		SF
0071	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96		SF
0072	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	80		SF
0073	4420000000-N	1120	PORTABLE CHANGEABLE MESSAGE SIGN	2		EA

County : Stokes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	4430000000-N	1130	DRUMS	50	EA	
0075	4435000000-N	1135	CONES	35	EA	
0076	4445000000-E	1145	BARRICADES (TYPE III)	108	LF	
0077	4455000000-N	1150	FLAGGER	360	DAY	
0078	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	2	EA	
0079	4470000000-N	1160	REMOVE & RESET TEMPORARY CRASH CUSHION	2	EA	
0080	4485000000-E	1170	PORTABLE CONCRETE BARRIER	500	LF	
0081	4510000000-N	1190	LAW ENFORCEMENT	240	HR	
0082	4516000000-N	1180	SKINNY DRUM	50	EA	
0083	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	37	EA	
0084	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	5,121	LF	
0085	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	275	LF	
0086	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	24	EA	
0087	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	20,986	LF	
0088	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	432	LF	
0089	4825000000-E	1205	PAINT PAVEMENT MARKING LINES (12")	161	LF	
0090	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	200	LF	
0091	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	44	EA	
0092	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	2,759	LF	

County : Stokes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0093	4860000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (8")	120	LF	
0094	4891000000-E	1205	GENERIC PAVEMENT MARKING ITEM (24" THERMOPLASTIC MARKING LINE S 90 MILS)	100	LF	
0095	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	22	EA	
0096	5325200000-E	1510	2" WATER LINE (SDR21)	288	LF	
0097	5325600000-E	1510	6" WATER LINE (PC350)	350	LF	
0098	5325800000-E	1510	8" WATER LINE (PC350)	757	LF	
0099	5329000000-E	1510	DUCTILE IRON WATER PIPE FITTINGS	1,845	LB	
0100	5536000000-E	1515	2" VALVE	1	EA	
0101	5540000000-E	1515	6" VALVE	2	EA	
0102	5546000000-E	1515	8" VALVE	4	EA	
0103	5649000000-N	1515	RECONNECT WATER METER	4	EA	
0104	5686500000-E	1515	WATER SERVICE LINE	75	LF	
0105	5691400000-E	1520	10" SANITARY GRAVITY SEWER (SDR 35)	186	LF	
0106	5775000000-E	1525	4' DIA UTILITY MANHOLE	2	EA	
0107	5781000000-E	1525	UTILITY MANHOLE WALL 4' DIA	1	LF	
0108	5798000000-E	1530	ABANDON *** UTILITY PIPE (2")	440	LF	
0109	5800000000-E	1530	ABANDON 6" UTILITY PIPE	332	LF	
0110	5801000000-E	1530	ABANDON 8" UTILITY PIPE	660	LF	
0111	5802000000-E	1530	ABANDON 10" UTILITY PIPE	260	LF	

County : Stokes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0112	6000000000-E	1605	TEMPORARY SILT FENCE	2,110 LF		
0113	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	100 TON		
0114	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	310 TON		
0115	6012000000-E	1610	SEDIMENT CONTROL STONE	265 TON		
0116	6015000000-E	1615	TEMPORARY MULCHING	3.5 ACR		
0117	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	300 LB		
0118	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.5 TON		
0119	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0120	6030000000-E	1630	SILT EXCAVATION	250 CY		
0121	6036000000-E	1631	MATTING FOR EROSION CONTROL	7,675 SY		
0122	6042000000-E	1632	1/4" HARDWARE CLOTH	630 LF		
0123	6071010000-E	SP	WATTLE	50 LF		
0124	6071012000-E	SP	COIR FIBER WATTLE	150 LF		
0125	6071020000-E	SP	POLYACRYLAMIDE (PAM)	75 LB		
0126	6084000000-E	1660	SEEDING & MULCHING	3 ACR		
0127	6087000000-E	1660	MOWING	3 ACR		
0128	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0129	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0130	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75 LB		
0131	6108000000-E	1665	FERTILIZER TOPDRESSING	2.25 TON		

County : Stokes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0132	6114500000-N	1667	SPECIALIZED HAND MOWING	10	MHR	
0133	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	25	EA	
0134	6117500000-N	SP	CONCRETE WASHOUT STRUCTURE	1	EA	
0680	1891000000-E	SP	GENERIC PAVING ITEM 7" CONCRETE TRUCK APRON	510	SY	
0685	8801000000-E	SP	MSE RETAINING WALL NO **** ONE(1)	550	SF	

1240/Feb11/Q63886.0/D494767942000/E135

Total Amount Of Bid For Entire Project :