



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

PAT MCCRORY
GOVERNOR

ANTHONY J. TATA
SECRETARY

April 22, 2013

TO: Prospective Bidders

FROM: ^{WJT} W. Jeff Turner, Division Proposals Engineer

SUBJECT: Contract DI00029
Addendum #2 -
Grading, Drainage, Widening and Paving to Realign the Intersection of SR 1002 (Bringle Ferry Road) and SR 2144 (Surratt Road) in Rowan County.

The subject contract proposal contains the following addendum:

1. Replacement of Bid form. Line Item 19 – the description was changed from Surface Course, SF9.5A to Surface Course, S9.5B.

This addendum officially becomes part of the contract.

**North Carolina Department of Transportation
BID FORM**

Revised

CONTRACT: DI00029

**DESCRIPTION: GRADING, DRAINAGE, WIDENING, AND PAVING TO REALIGN THE INTERSECTION OF SR
1002 (Bringle Ferry Road) AND SR 2144 (Surratt Road) IN ROWAN COUNTY**

LINE #	ITEM #	SECT	ITEM DESCRIPTION	QTY*	UNIT	UNIT PRICE	PRICE
1	0000100000-N	800	MOBILIZATION	1	LS		
2	0005000000-E	200	SUPPLEMENTARY CLEARING & GRUBBING	1	ACR		
3	0057000000-E	226	UNDERCUT EXCAVATION	500	CY		
4	0063000000-N	226	GRADING	1	LS		
5	0195000000-E	265	SELECT GRANULAR MATERIAL	250	CY		
6	0196000000-E	270	GEOTEXTILE FOR SOIL STABILICATION	1800	SY		
7	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	25	TON		
8	0320000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	70	SY		
9	0343000000-E	310	15" SIDE DRAIN PIPE	24	LF		
10	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	6	LF		
11	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	156	LF		
12	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	8	LF		
13	0995000000-E	340	PIPE REMOVAL	216	LF		
14	1099700000-E	505	CLASS IV SUBGRADE STABILIZATION	500	TON		
15	1220000000-E	545	INCIDENTAL STONE BASE	100	TON		
16	1330000000-E	607	INCIDENTAL MILLING	1000	SY		
17	1489000000-E	610	BASE COURSE, B25.0B	2401	TON		
18	1498000000-E	610	INTERMEDIATE COURSE, I19.0B	891	TON		
19	1525000000-E	610	SURFACE COURSE, S9.5B	480	TON		
20	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	181	TON		
21	2000000000-N	806	RIGHT OF WAY MARKERS	20	EA		
22	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	500	LF		
23	2070000000-N	815	SUBDRAIN PIPE OUTLET	1	EA		
24	2077000000-E	815	6" OUTLET PIPE	6	LF		
25	2253000000-E	840	PIPE COLLARS	3	CY		
26	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3	EA		
27	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	2	EA		
28	2472000000-N	840	JUNCTION BOX 840.31	1	EA		
29	3030000000-E	862	STEEL BM GUARDRAIL	366	LF		
30	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	2	EA		
31	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	420	SY		
32	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	44	LF		
33	4102000000-N	904	SIGN ERECTION, TYPE E	5	EA		
34	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	15	EA		
35	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	536	SF		
36	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	154	SF		
37	4430000000-N	1130	DRUMS	50	EA		
38	4445000000-E	1145	BARRICADES (TYPE III)	112	LF		
39	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	6464	LF		

North Carolina Department of Transportation BID FORM

CONTRACT: DI00029

**DESCRIPTION: GRADING, DRAINAGE, WIDENING, AND PAVING TO REALIGN THE INTERSECTION OF SR
1002 (Bringle Ferry Road) AND SR 2144 (Surratt Road) IN ROWAN COUNTY**

LINE #	ITEM #	SECT	ITEM DESCRIPTION	QTY*	UNIT	UNIT PRICE	PRICE
40	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MIL)	53	LF		
41	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	50	EA		
42	6000000000-E	1605	TEMPORARY SILT FENCE	3095	LF		
43	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	285	TON		
44	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	320	TON		
45	6012000000-E	1610	SEDIMENT CONTROL STONE	170	TON		
46	6015000000-E	1615	TEMPORARY MULCHING	3	ACR		
47	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	200	LB		
48	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	2	TON		
49	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200	LF		
50	6030000000-E	1630	SILT EXCAVATION	720	CY		
51	6036000000-E	1631	MATTING FOR EROSION CONTROL	3500	SY		
52	6037000000-E	SP	COIR FIBER MAT	45	SY		
53	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	430	SY		
54	6042000000-E	1632	¼" HARDWARE CLOTH	250	LF		
55	6071020000-E	SP	POLYACRYLAMIDE (PAM)	40	LB		
56	6071030000-E	1640	COIR FIBER BAFFLES	285	LF		
57	6071050000-E	SP	1.5" SKIMMER	5	EA		
58	6084000000-E	1660	SEEDING & MULCHING	7	ACR		
59	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB		
60	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	.25	TON		
61	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	125	LB		
62	6108000000-E	1665	FERTILIZER TOPDRESSING	3	TON		
63	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	18	EA		
64	8594000000-E	876	RIP RAP, CLASS B	6	TON		

*The Contractor shall note that all quantities are used only for figuring the lowest responsible bidder. The quantities may vary based on the amount of work needed during the year as directed by the Engineer.

TOTAL BID FOR PROJECT: _____

CONTRACTOR _____
ADDRESS _____

Federal Identification Number _____	Contractor's License Number _____
Authorized Agent _____	Title _____
Signature _____	Date _____
Witness _____	Title _____
Signature _____	Date _____

THIS SECTION TO BE COMPLETED BY NORTH CAROLINA DEPARTMENT OF TRANSPORTATION
This bid has been reviewed in accordance with Article 103-1 of the Standard Specifications for Roads and Structures 2012.

Reviewed by _____ (date) _____
Accepted by NCDOT _____ Engineer _____ (date)