



STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION


ROY COOPER  
GOVERNOR

J. ERIC BOYETTE  
SECRETARY

July 18, 2023

TO: Prospective Bidders

FROM: Jeff Turner, Division Proposals Engineer

DocuSigned by:  
  
B47701BDF119489...

SUBJECT: **Addendum #1**  
Contract: DI00331  
49321.3.3 – Davidson County  
Grading, Paving, Drainage - US 64 from 1000 Feet West of SR 2782 (Bowers Road) to 1100 Feet East of SR 2012/SR 2227 (Heath Church/New Bowers Road)

The subject contract proposal contains the following addendum:

1. Revised Bid Sheet.  
Line #26 – Item 2655000000-E: Qty changed from 410 SY to 2,800 SY.

This addendum officially becomes part of the contract.

Jul 18, 2023 8:02 AM

## ITEMIZED PROPOSAL FOR CONTRACT NO. DI00331

Page 1 of 6

County: DAVIDSON

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	500 SY		
0005	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	135 TON		
0006	0320000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	518 SY		
0007	0448000000-E	310	***** RC PIPE CULVERTS, CLASS IV (12")	64 LF		
0008	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	68 LF		
0009	0448300000-E	310	18" RC PIPE CULVERTS, CLASS IV	476 LF		
0010	0448400000-E	310	24" RC PIPE CULVERTS, CLASS IV	268 LF		
0011	0995000000-E	340	PIPE REMOVAL	53 LF		
0012	1099500000-E	505	SHALLOW UNDERCUT	50 CY		
0013	1220000000-E	545	INCIDENTAL STONE BASE	500 TON		
0014	1330000000-E	607	INCIDENTAL MILLING	11,515 SY		
0015	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	1,850 TON		
0016	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	1,500 TON		
0017	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	1,710 TON		

County: DAVIDSON

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	255 TON		
0019	1704000000-E	SP	PATCHING EXISTING PAVEMENT	20 TON		
0020	2275000000-E	SP	FLOWABLE FILL	15 CY		
0021	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	14 EA		
0022	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	11 EA		
0023	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	3 EA		
0024	2396000000-N	840	FRAME WITH COVER, STD 840.54	2 EA		
0025	2451000000-N	852	CONCRETE TRANSITIONAL SECTION FOR DROP INLET	12 EA		
0026	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	2,800 SY		
0027	2815000000-N	858	ADJUSTMENT OF DROP INLETS	1 EA		
0028	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	1 EA		
0029	2938000000-N	859	CONVERT EXISTING DROP INLET TO JUNCTION BOX WITH MANHOLE	2 EA		
0030	3649000000-E	876	RIP RAP, CLASS B	14 TON		
0031	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	269 SY		
0032	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	1,234 LF		
0033	4102000000-N	904	SIGN ERECTION, TYPE E	66 EA		
0034	4108000000-N	904	SIGN ERECTION, TYPE F	10 EA		

County: DAVIDSON

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	66 EA		
0036	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	160 SF		
0037	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	256 SF		
0038	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	80 SF		
0039	4415000000-N	1115	FLASHING ARROW BOARD	2 EA		
0040	4420000000-N	1120	PORTABLE CHANGEABLE MESSAGE SIGN	2 EA		
0041	4430000000-N	1130	DRUMS	131 EA		
0042	4445000000-E	1145	BARRICADES (TYPE III)	80 LF		
0043	4455000000-N	1150	FLAGGER	45 DAY		
0044	4480000000-N	1165	TMA	2 EA		
0045	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	13 EA		
0046	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	12,360 LF		
0047	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	4,437 LF		
0048	4700000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (12", 90 MILS)	809 LF		
0049	4709000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 90 MILS)	150 LF		
0050	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	29 EA		
0051	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	4,000 LF		

County: DAVIDSON

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0052	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	115 LF		
0053	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	2 EA		
0054	4905100000-N	SP	NON-CAST IRON SNOWPLOWABLE PAVEMENT MARKER	406 EA		
0055	5325800000-E	1510	8" WATER LINE	689 LF		
0056	5329000000-E	1510	DUCTILE IRON WATER PIPE FITTINGS	2,040 LB		
0057	5546000000-E	1515	8" VALVE	2 EA		
0058	5649000000-N	1515	RECONNECT WATER METER	1 EA		
0059	5686500000-E	1515	WATER SERVICE LINE	15 LF		
0060	5835700000-E	1540	16" ENCASEMENT PIPE	70 LF		
0061	5872500000-E	1550	BORE AND JACK OF *** (16")	70 LF		
0062	6000000000-E	1605	TEMPORARY SILT FENCE	1,145 LF		
0063	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	120 TON		
0064	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	85 TON		
0065	6012000000-E	1610	SEDIMENT CONTROL STONE	100 TON		
0066	6015000000-E	1615	TEMPORARY MULCHING	1 ACR		
0067	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0068	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.5 TON		

County: DAVIDSON

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0069	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0070	6030000000-E	1630	SILT EXCAVATION	130 CY		
0071	6036000000-E	1631	MATTING FOR EROSION CONTROL	19,500 SY		
0072	6042000000-E	1632	1/4" HARDWARE CLOTH	270 LF		
0073	6071010000-E	SP	WATTLE	170 LF		
0074	6071012000-E	SP	COIR FIBER WATTLE	90 LF		
0075	6071020000-E	SP	POLYACRYLAMIDE (PAM)	45 LB		
0076	6071030000-E	1640	COIR FIBER BAFFLE	25 LF		
0077	6084000000-E	1660	SEEDING & MULCHING	3 ACR		
0078	6087000000-E	1660	MOWING	3 ACR		
0079	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0080	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0081	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0082	6108000000-E	1665	FERTILIZER TOPDRESSING	0.75 TON		
0083	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0084	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	25 EA		
0085	6117500000-N	SP	CONCRETE WASHOUT STRUCTURE	2 EA		

County: DAVIDSON

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0086	6132000000-N	SP	GENERIC EROSION CONTROL ITEM (FABRIC INSERT INLET PROTECTION DEVICE CLEANOUT)	9 EA		
-----						
0087	6132000000-N	SP	GENERIC EROSION CONTROL ITEM (FABRIC INSERT INLET PROTECTION DEVICE)	9 EA		
-----						

0802/Jul18/Q72114.5/D348619572000/E87

Total Amount Of Bid For Entire Project :

