



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

ROY COOPER
GOVERNOR

JAMES H. TROGDON, III
SECRETARY

March 20, 2017

Addendum No. 1

Contract No.: DA00336

WBS Element: 17BP.1.R.68

Replacement of Bridge #7 on SR 1200 over Sawyers Creek in Camden County

To Whom It May Concern:

Reference is made to the proposal and plans previously furnished for this project.

The following revision has been made to the proposal:

Pages No.131-134 "Bid Form" have been revised to adjust quantities and include a line item for "Geotextile for Soil Stabilization". Please void existing Pages No. 131-134 and replace with revised Pages No. 131-134.

If you choose the "Electronic Bid Preparation with Manual Delivery Method" or "Traditional Paper Bid Method," please acknowledge receipt of Addendum #1 in the space provided on the Addendum Acknowledgement Form.

If you choose the "Electronic Bid Preparation with Manual Delivery Method," place DA00336.001 in the same folder with DA00336.EBS, so that Expedite Bid will properly apply the addendum.

Sincerely,

DocuSigned by:

A handwritten signature in black ink that reads "W. B. Hobbs".

99A5A272ED6A447...

W. B. Hobbs, PE

Division Project Manager

WBH

Attachment

cc: C. W. Bridgers, Jr, PE
C. S. Mebane, PE
J. S. Abel, Jr.
D. B. Otts, PE

Mailing Address:
NC DEPARTMENT OF TRANSPORTATION
DIVISION ONE
113 AIRPORT DRIVE, SUITE 100
EDENTON, NC 27932

Telephone: (252) 482-1850
Fax: (252) 482-8722
Customer Service: 1-877-368-4968

Location:
113 AIRPORT DRIVE, SUITE 100
EDENTON, NC 27932

Website: www.ncdot.gov

County : Camden

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0022000000-E	225	UNCLASSIFIED EXCAVATION (SURCHARGE)	10 CY		
0003	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (13+30.50)	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	50 CY		
0006	0106000000-E	230	BORROW EXCAVATION (SURCHARGE)	1,200 CY		
0007	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	1,975 SY		
0008	0248000000-N	SP	GENERIC GRADING ITEM (EXCAVATION & EMBANKMENT)	Lump Sum	L.S.	
0009	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	10 TON		
0010	0320000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	30 SY		
0011	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	16 LF		
0012	1220000000-E	545	INCIDENTAL STONE BASE	10 TON		
0013	1330000000-E	607	INCIDENTAL MILLING (0" TO 3")	450 SY		
0014	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	240 TON		
0015	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	130 TON		
0016	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	235 TON		
0017	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	31 TON		

County : Camden

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	2022000000-E	815	SUBDRAIN EXCAVATION	23 CY		
0019	2033000000-E	815	SUBDRAIN FINE AGGREGATE	17 CY		
0020	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0021	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		
0022	2077000000-E	815	6" OUTLET PIPE	6 LF		
0023	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1 EA		
0024	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		
0025	2556000000-E	846	SHOULDER BERM GUTTER	25 LF		
0026	3030000000-E	862	STEEL BM GUARDRAIL	50 LF		
0027	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0028	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0029	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0030	3649000000-E	876	RIP RAP, CLASS B	1 TON		
0031	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	175 SY		
0032	4457000000-N	SP	TEMPORARY TRAFFIC CONTROL	Lump Sum	L.S.	
0033	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	1,020 LF		
0034	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	1,020 LF		
0035	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	2,040 LF		
0036	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	7 EA		

County : Camden

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	6000000000-E	1605	TEMPORARY SILT FENCE	860		LF
0038	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75		TON
0039	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	15		TON
0040	6012000000-E	1610	SEDIMENT CONTROL STONE	15		TON
0041	6015000000-E	1615	TEMPORARY MULCHING	0.5		ACR
0042	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100		LB
0043	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.5		TON
0044	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200		LF
0045	6029000000-E	SP	SAFETY FENCE	200		LF
0046	6030000000-E	1630	SILT EXCAVATION	20		CY
0047	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,285		SY
0048	6037000000-E	SP	COIR FIBER MAT	100		SY
0049	6042000000-E	1632	1/4" HARDWARE CLOTH	25		LF
0050	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	160		SY
0051	6071012000-E	SP	COIR FIBER WATTLE	115		LF
0052	6084000000-E	1660	SEEDING & MULCHING	3		ACR
0053	6087000000-E	1660	MOWING	0.5		ACR
0054	6090000000-E	1661	SEED FOR REPAIR SEEDING	50		LB
0055	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25		TON
0056	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50		LB

County : Camden

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	6108000000-E	1665	FERTILIZER TOPDRESSING	0.5 TON		
0058	6111000000-E	SP	IMPERVIOUS DIKE	153 LF		
0059	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0060	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	7 EA		
0061	6132000000-N	SP	GENERIC EROSION CONTROL ITEM (CONC WASHOUT STR))	2 EA		

STRUCTURE ITEMS

0062	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (13+30.50)	Lump Sum	L.S.	
0063	8112730000-N	450	PDA TESTING	1 EA		
0064	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (13+30.50)	Lump Sum	L.S.	
0065	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (13+30.50)	Lump Sum	L.S.	
0066	8365000000-E	450	HP12X53 GALVANIZED STEEL PILES	1,000 LF		
0067	8393000000-N	450	PILE REDRIVES	10 EA		
0068	8765000000-N	SP	CONSTRUCTION OF SUBSTRUCTURE	Lump Sum	L.S.	
0069	8766000000-N	SP	CONSTRUCTION OF SUPERSTRUCTURE	Lump Sum	L.S.	
0070	8860000000-N	SP	GENERIC STRUCTURE ITEM (ASBESTOS ASSESSMENT)	Lump Sum	L.S.	

County : Camden

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0071	8892000000-E	SP	GENERIC STRUCTURE ITEM (GALVENIZED STEEL SHEET PILE)	7,022 SF		

1123/Mar20/Q20378.25/D307243342000/E71

Total Amount Of Bid For Entire Project :
