

NOTES:

BENT DIAPHRAGMS AND OTHER CONCRETE COMPONENTS MY BE REPAIRED UNDER SHOTCRETE REPAIRS OR CONCRETE REPAIRS WITH THE APPROVAL OF THE ENGINEER.


CONTRACTOR SHALL SAW CUT TO A NOMINAL DEPTH OF 1/2" BUT REINFORCING STEEL SHALL NOT BE DAMAGED.

CONTRACTOR SHALL REMOVE SURFACE CONCRETE TO VERIFY THAT SAWCUT DEPTH WILL NOT BE DAMAGE EXISTING REINFORCING STEEL.

SHOTCRETE REPAIRS MAY BE REPLACED WITH CONCRETE REPAIRS WITH THE APPROVAL OF THE ENGINEER.

FOR SHOTCRETE REPAIRS,SEE SPECIAL PROVISIONS.

FOR EPOXY RESIN INJECTION,SEE SPECIAL PROVISIONS.



SUBSTRUCTURE REPAIR DETAIL

PROJECT NO. B-5942
HYDE COUNTY
BRIDGE NO. 20
SHEET 15 OF 15



DRAWN BY : B. L. GREEN DATE : 10/15
CHECKED BY : R. W. WRIGHT DATE : 11/15

DOCUMENT NOT CONSIDERED
FINAL UNLESS ALL
SIGNATURES COMPLETED

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	S-30
1			3			TOTAL SHEETS 30
2			4			