


## LEGEND- ACCENT 1, ACCENT 2:

ACCENT 1 (1"X 1"):
AMERICAN OLEAN, UNGLAZED COLORBODY- PORCELAIN MOSAIKS- DILL PICKLE A83 (2).

ACCENT 2 (1"X 1"):
AMERICAN OLEAN, UNGLAZED COLORBODY- PORCELAIN MOSAIKS- ICE WHITE A25 (2).

1 A2.3 ENLARGED PLAN- ACCENT 1, ACCENT 2
SCALE: 1/4" = 1'-0"

## LEGEND- WALL:

ACCENT 1 (1"X 1")- SEE 1/A2.3:
AMERICAN OLEAN, UNGLAZED COLORBODY- PORCELAIN MOSAIKS- DILL PICKLE A83 (2).

ACCENT 2 (1"X 1")- SEE 1/A2.3:
AMERICAN OLEAN, UNGLAZED COLORBODY- PORCELAIN MOSAIKS- ICE WHITE A25 (2).

ACCENT 3 (12"X 24" VERTICAL STACKED):
DALTILE, SHOWSCAPE, CRISP BLUE BRUSHSTROKE SH16 (2).

ACCENT 4 (12"X 24" - POLISHED- HORIZONTAL STACKED):
DALTILE, UNITY SERIES- P400 AVORIO.

ACCENT 5 (12"X 24" HORIZONTAL STACKED):
DALTILE, SHOWSCAPE, STYLISH WHITE BRUSHSTROKE SH09 (1).

FIELD (12"X 24"- UNPOLISHED- HORIZONTAL STACKED):
DALTILE, UNITY SERIES- P400 AVORIO.

COVE BASE (6"X 12"- UNPOLISHED):
DALTILE, UNITY SERIES- P400 AVORIO.

## GROUT:

TILE GROUT: QUARTZ LOCK , 145 BONE.
COVE BASE GROUT: TILE GROUT: QUARTZ LOCK , 145 BONE.

2 A2.3 LEGEND- WALL
SCALE: 1/4" = 1'-0"

## ROOM FINISH

| NO. | ROOM | FLOOR | | BASE | | NORTH WALL | | EAST WALL | | SOUTH WALL | | WEST WALL | | CEILING | | | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | MAT. | COLOR | MAT. | COLOR | MATERIAL | COLOR | MATERIAL | COLOR | MATERIAL | COLOR | MATERIAL | COLOR | MAT. | COLOR | HEIGHT | |
| 101 | CORRIDOR | CT | SEE SPEC. | CT | SEE SPEC. | SEE 12/A2.2 | SEE SPEC. | SEE 1/A2.2 | SEE SPEC. | SEE 11/A2.2 | SEE SPEC. | SEE 2/A2.2 | SEE SPEC. | GWB | SEE SPEC. | 8'-8" | |
| 102 | FAMILY RESTROOM | CT | ↓ | CT | ↓ | SEE 4/A2.2 | ↓ | SEE 10/A2.2 | ↓ | SEE 7/A2.2 | ↓ | SEE 2/A2.2 | ↓ | ↓ | ↓ | 8'-7" | |
| 103 | JANITOR CLOSET | * *** | N/A | *** | N/A | *** | N/A | N/A | N/A | N/A | N/A | N/A | N/A | ** | N/A | N/A | * FLOOR: EXISTING CONCRETE TO REMAIN. ** CEILING: EXISTING GWB TO REMAIN. |
| 104 | MECHANICAL | * | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A | ** | N/A | N/A | * FLOOR: EXISTING CONCRETE TO REMAIN. ** CEILING: EXISTING GWB TO REMAIN. |
| 105 | ALTERNATE TOILET | CT | SEE SPEC. | CT | SEE SPEC. | SEE 4/A2.2, 5/A2.2 | SEE SPEC. | SEE 1/A2.2 | SEE SPEC. | SEE 7/A2.2 | SEE SPEC. | SEE 9/A2.2 | SEE SPEC. | GWB | SEE SPEC. | 8'-7" | |
| 106 | MEN | CT | ↓ | CT | | SEE 8/A2.2 | ↓ | SEE 1/A2.2 | ↓ | SEE 3/A2.2, 6/A2.2 | ↓ | SEE 9/A2.2 | ↓ | ↓ | ↓ | 8'-7" | |
| 107 | PIPE CHASE | * | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A | ** | N/A | N/A | * FLOOR: EXISTING CONCRETE TO REMAIN. ** CEILING: EXISTING GWB TO REMAIN. |
| 108 | ELECTRICAL | * | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A | ** | N/A | N/A | * FLOOR: EXISTING CONCRETE TO REMAIN. ** CEILING: EXISTING GWB TO REMAIN. |
| 109 | WOMEN | CT | SEE SPEC. | CT | SEE SPEC. | SEE 8/A2.2 | SEE SPEC. | SEE 10/A2.2 | SEE SPEC. | SEE 3/A2.2, 6/A2.2 | SEE SPEC. | SEE 2/A2.2 | SEE SPEC. | GWB | SEE SPEC. | 8'-7" | |

## GENERAL NOTE:

FOR ROOM FINISH, REFER TO WALL/ FLOOR LEGENDS SHEET A2.1, A2.3.

*** JANITOR SINK IN 103 JANITOR CLOSET TO RECEIVE 4'-0" HIGH FRP ON 3 SURROUNDING WALLS-SEE A1.1. NEW JANITOR SINK SURROUND TO RECEIVE 6"X6" QUARRY TILE FLOOR AND QUARRY TILE BASE TO MATCH EXISTING TILE IN ROOM.

BID DOCUMENTS

LISA LARKIN KEEL
REGISTERED ARCHITECT
6195
NORTH CAROLINA
RALEIGH, N.C.
SEAL:
SEAL NOT VALID UNLESS SIGNED AND DATED

DESIGNED BY:
FACILITIES DESIGN
ARCHITECTS & ENGINEERS
FACILITIES MANAGEMENT DIVISION, NCDOT
1 SOUTH WILMINGTON STREET
RALEIGH, NORTH CAROLINA 27601
PH:919/707-4640 FAX:919/715-0369

CONSULTANT:

DRAWING TITLE / DESCRIPTION:
ENLARGED PLAN, WALL LEGEND
FINISH SCHEDULE

PROJECT TITLE:
CAMDEN COUNTY REST AREA REFURBISHMENT
2356 HWY 117 NORTH, SOUTH MILLS NC 27976
CAMDEN COUNTY, NORTH CAROLINA

| | |
|---|---|
| SCO ID NO. | 14-11342-01A |
| - | - |
| WBS NO. | 36059.27 |
| - | - |

ASSET NUMBER:
CO.# SITE.# BLDG.#
15 - 04 - 02

REVISIONS
NO. DATE

DATE ISSUED: 4/17/15
DRAWN BY:
CHECKED BY: -
SHEET NO.
A2.3