

LEGEND- ACCENT 1, ACCENT 2:

ACCENT 1 (1"X 1"):
AMERICAN OLEAN, UNGLAZED COLORBODY- PORCELAIN MOSAIKS- DILL PICKLE A83 (2).

ACCENT 2 (1"X 1"):
AMERICAN OLEAN, UNGLAZED COLORBODY- PORCELAIN MOSAIKS- ICE WHITE A25 (2).

1 / A2.3 ENLARGED PLAN- ACCENT 1, ACCENT 2
SCALE: 1/4" = 1'-0"

LEGEND- WALL:

ACCENT 1 (1"X 1")- SEE 1/A2.3:
AMERICAN OLEAN, UNGLAZED COLORBODY- PORCELAIN MOSAIKS- DILL PICKLE A83 (2).

ACCENT 2 (1"X 1")- SEE 1/A2.3:
AMERICAN OLEAN, UNGLAZED COLORBODY- PORCELAIN MOSAIKS- ICE WHITE A25 (2).

ACCENT 3 (12"X 24" VERTICAL STACKED):
DALTILE, SHOWSCAPE, CRISP BLUE BRUSHSTROKE SH16 (2).

ACCENT 4 (12"X 24" - POLISHED- HORIZONTAL STACKED):
DALTILE, UNITY SERIES- P400 AVORIO.

ACCENT 5 (12"X 24" HORIZONTAL STACKED):
DALTILE, SHOWSCAPE, STYLISH WHITE BRUSHSTROKE SH09 (1).

FIELD (12"X 24"- UNPOLISHED- HORIZONTAL STACKED):
DALTILE, UNITY SERIES- P400 AVORIO.

COVE BASE (6"X 12"- UNPOLISHED):
DALTILE, UNITY SERIES- P400 AVORIO.

GROUT:

TILE GROUT: QUARTZ LOCK , 145 BONE.
COVE BASE GROUT: TILE GROUT: QUARTZ LOCK , 145 BONE.

2 / A2.3 LEGEND- WALL
SCALE: 1/4" = 1'-0"

ROOM FINISH

NO.	ROOM	FLOOR		BASE		NORTH WALL		EAST WALL		SOUTH WALL		WEST WALL		CEILING			REMARKS
		MAT.	COLOR	MAT.	COLOR	MATERIAL	COLOR	MATERIAL	COLOR	MATERIAL	COLOR	MATERIAL	COLOR	MAT.	COLOR	HEIGHT	
101	CORRIDOR	CT	SEE SPEC.	CT	SEE SPEC.	SEE 12/A2.2	SEE SPEC.	SEE 1/A2.2	SEE SPEC.	SEE 11/A2.2	SEE SPEC.	SEE 2/A2.2	SEE SPEC.	GWB	SEE SPEC.	8'-8"	
102	FAMILY RESTROOM	CT	↓	CT	↓	SEE 4/A2.2	↓	SEE 10/A2.2	↓	SEE 7/A2.2	↓	SEE 2/A2.2	↓	↓	↓	8'-7"	
103	JANITOR CLOSET	* ***	N/A	***	N/A	***	N/A	N/A	N/A	N/A	N/A	N/A	N/A	**	N/A	N/A	* FLOOR: EXISTING CONCRETE TO REMAIN. ** CEILING: EXISTING GWB TO REMAIN.
104	MECHANICAL	*	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	**	N/A	N/A	* FLOOR: EXISTING CONCRETE TO REMAIN. ** CEILING: EXISTING GWB TO REMAIN.
105	ALTERNATE TOILET	CT	SEE SPEC.	CT	SEE SPEC.	SEE 4/A2.2, 5/A2.2	SEE SPEC.	SEE 1/A2.2	SEE SPEC.	SEE 7/A2.2	SEE SPEC.	SEE 9/A2.2	SEE SPEC.	GWB	SEE SPEC.	8'-7"	
106	MEN	CT	↓	CT		SEE 8/A2.2	↓	SEE 1/A2.2	↓	SEE 3/A2.2, 6/A2.2	↓	SEE 9/A2.2	↓	↓	↓	8'-7"	
107	PIPE CHASE	*	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	**	N/A	N/A	* FLOOR: EXISTING CONCRETE TO REMAIN. ** CEILING: EXISTING GWB TO REMAIN.
108	ELECTRICAL	*	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	**	N/A	N/A	* FLOOR: EXISTING CONCRETE TO REMAIN. ** CEILING: EXISTING GWB TO REMAIN.
109	WOMEN	CT	SEE SPEC.	CT	SEE SPEC.	SEE 8/A2.2	SEE SPEC.	SEE 10/A2.2	SEE SPEC.	SEE 3/A2.2, 6/A2.2	SEE SPEC.	SEE 2/A2.2	SEE SPEC.	GWB	SEE SPEC.	8'-7"	

GENERAL NOTE:

FOR ROOM FINISH, REFER TO WALL/ FLOOR LEGENDS SHEET A2.1, A2.3.

*** JANITOR SINK IN 103 JANITOR CLOSET TO RECEIVE 4'-0" HIGH FRP ON 3 SURROUNDING WALLS-SEE A1.1. NEW JANITOR SINK SURROUND TO RECEIVE 6"X6" QUARRY TILE FLOOR AND QUARRY TILE BASE TO MATCH EXISTING TILE IN ROOM.

BID DOCUMENTS

LISA LARKIN KEEL
REGISTERED ARCHITECT
NORTH CAROLINA
RALEIGH, N.C.
DocuSigned by: Lisa Keel 6/12/2025
SEAL:
SEAL NOT VALID UNLESS SIGNED AND DATED

DESIGNED BY:
FACILITIES DESIGN
ARCHITECTS & ENGINEERS
FACILITIES MANAGEMENT DIVISION, NCDOT
1 SOUTH WILMINGTON STREET
RALEIGH, NORTH CAROLINA 27601
PH:919/707-4640 FAX:919/715-0369

CONSULTANT:

DRAWING TITLE / DESCRIPTION:
ENLARGED PLAN, WALL LEGEND
FINISH SCHEDULE

PROJECT TITLE:
CAMDEN COUNTY REST AREA REFURBISHMENT
2356 HWY 117 NORTH, SOUTH MILLS NC 27976
CAMDEN COUNTY, NORTH CAROLINA

SCO ID NO.	14-11342-01A
-	-
WBS NO.	36059.27
-	-

ASSET NUMBER:
CO.# SITE.# BLDG.#
15 - 04 - 02

REVISIONS
NO. DATE

DATE ISSUED: 4/17/15
DRAWN BY:
CHECKED BY: -
SHEET NO.
A2.3