



STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION

ROY COOPER  
GOVERNOR

JAMES H. TROGDON, III  
SECRETARY

July 13, 2018

**Addendum No. 3**

Contract No.: DA00333

WBS Element: 50196.3.1

TIP Number: R-5738

*Grading, Drainage, Paving and Structure Improvements on SR1208 "Kitty Hawk Road," in Dare County*

To Whom It May Concern:

Reference is made to the proposal and plans previously furnished for this project.


The following revision has been made to the proposal:

Page 6, "Intermediate Contract Time Number 1 and Liquidated Damages" has been revised to update the completion date. Please void existing Page 6 and replace with the revised Page 6.

Pages 110 - 114, "Bid Form" has been revised to change Line Item #7 from " 18" Drainage Pipe to 18" RC Pipe Culverts, Class III" and to add a Line Item for "Foundation Conditioning Material" & "Foundation Conditioning Geotextile". Please void existing Pages 110 - 114 and replace with the revised Pages 110 - 114.

The amended EBS File (DA00333.003) has been uploaded to Bid Express. We apologize for any inconvenience.

Sincerely,

DocuSigned by:  
  
CDAEAC77A6394FB...

C. E. Slachta  
Division Proposals Engineer

cc: J. D. Jennings, PE  
C. W. Bridgers, Jr, PE  
G. A. Byrum, PE  
R. W. Midgett, PE.

Mailing Address:  
NC DEPARTMENT OF TRANSPORTATION  
DIVISION ONE  
113 AIRPORT DRIVE, SUITE 100  
EDENTON, NC 27932

Telephone: (252) 482-1850  
Fax: (252) 482-8722  
Customer Service: 1-877-368-4968

Location:  
113 AIRPORT DRIVE, SUITE 100  
EDENTON, NC 27932

Website: [www.ncdot.gov](http://www.ncdot.gov)

**INTERMEDIATE CONTRACT TIME NUMBER 1 AND LIQUIDATED DAMAGES:**

Except for that work required of final establishment of erosion control measures contained in the contract and removal of temporary erosion control measures, the Contractor will be required to complete all work included in this contract and shall place and maintain traffic on same.

The date of availability for this intermediate contract time is the date of availability of the contract.

**The completion date for this intermediate contract time is the date of acceptance of all roadway and structure items in the contract. Liquidated Damages will begin if roadway and structure items in the contract are not completed within 210 days from the date construction begins but must be complete no later than June 28, 2019.**

The liquidated damages for this intermediate contract time are **Seven Hundred Fifty Dollars (\$ 750.00)** per calendar day.

Upon apparent completion of all the work required to be completed by this intermediate date, a final inspection will be held in accordance with Article 105-17 and upon acceptance, the Department will assume responsibility for the maintenance of all work except for the final establishment of erosion control measures and removal of temporary erosion control measures. The Contractor will be responsible for and shall make corrections of all damages to the completed roadway and/or bridge caused by operations performed in final establishment of erosion control measures and removal of temporary erosion control measures, whether occurring prior to or after placing traffic on the project.

Payment for maintenance and removal of temporary erosion control measures is incidental to the various pay items in the contract. No additional compensation will be made for maintenance and removal of temporary erosion control items.

**PROSECUTION OF WORK:**

(7-1-95) (Rev. 8-21-12)

108

SP1 G15R

The Contractor will be required to prosecute the work in a continuous and uninterrupted manner from the time he begins the work until completion and final acceptance of the project. The Contractor will not be permitted to suspend his operations except for reasons beyond his control or except where the Engineer has authorized a suspension of the Contractor's operations in writing.

In the event that the Contractor's operations are suspended in violation of the above provisions, the sum of **\$ 250.00** will be charged the Contractor for each and every calendar day that such suspension takes place. The said amount is hereby agreed upon as liquidated damages due to extra engineering and maintenance costs and due to increased public hazard resulting from a suspension of the work. Liquidated damages chargeable due to suspension of the work will be additional to any liquidated damages that may become chargeable due to failure to complete the work on time.

County : Dare

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0030000000-N	SP	TYPE II MODIFIED APPROACH FILL, STATION ***** (42+68.00)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0199000000-E	SP	TEMPORARY SHORING	200 SF		
0007	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	80 TON		
0008	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	460 SY		
0009	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	16 LF		
0010	0448300000-E	310	18" RC PIPE CULVERTS, CLASS IV	72 LF		
0011	0448600000-E	310	36" RC PIPE CULVERTS, CLASS IV	140 LF		
0012	0995000000-E	340	PIPE REMOVAL	81 LF		
0013	1121000000-E	520	AGGREGATE BASE COURSE	30 TON		
0014	1220000000-E	545	INCIDENTAL STONE BASE	130 TON		
0015	1330000000-E	607	INCIDENTAL MILLING	333 SY		
0016	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	1,700 TON		
0017	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	150 TON		
0018	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	2,225 TON		

County : Dare

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	235		TON
0020	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	40		TON
0021	2209000000-E	838	ENDWALLS	7		CY
0022	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3		EA
0023	2352000000-N	840	FRAME WITH GRATE, STD 840.**** (18 OR 27)	1		EA
0024	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E, F OR G)	2		EA
0025	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	220		LF
0026	2556000000-E	846	SHOULDER BERM GUTTER	21		LF
0027	2591000000-E	848	4" CONCRETE SIDEWALK	260		SY
0028	3030000000-E	862	STEEL BEAM GUARDRAIL	25		LF
0029	3215000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE III	2		EA
0030	3288000000-N	SP	GUARDRAIL END UNITS, TYPE TL-2	2		EA
0031	3420000000-E	SP	GENERIC GUARDRAIL ITEM (WOODEN PEDESTRIAN RAILING)	200		LF
0032	3628000000-E	876	RIP RAP, CLASS I	4		TON
0033	3635000000-E	876	RIP RAP, CLASS II	100		TON
0034	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	190		SY
0035	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	248		SF
0036	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	81		SF
0037	4430000000-N	1130	DRUMS	35		EA

County : Dare

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	4435000000-N	1135	CONES	20	EA	
0039	4445000000-E	1145	BARRICADES (TYPE III)	96	LF	
0040	4455000000-N	1150	FLAGGER	6	DAY	
0041	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	2	EA	
0042	4490000000-E	1170	PORTABLE CONCRETE BARRIER (ANCHORED)	405	LF	
0043	4500000000-E	1170	REMOVE & RESET PORTABLE CONC- RETE BARRIER	770	LF	
0044	4600000000-N	SP	GENERIC TRAFFIC CONTROL ITEM (TEMPORARY PORTABLE TRAFFIC SI GNAL SYSTE M)	1	EA	
0045	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	12,000	LF	
0046	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	400	LF	
0047	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	12,000	LF	
0048	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	100	LF	
0049	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	12,000	LF	
0050	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	18	LF	
0051	6000000000-E	1605	TEMPORARY SILT FENCE	15,120	LF	
0052	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75	TON	
0053	6012000000-E	1610	SEDIMENT CONTROL STONE	70	TON	
0054	6015000000-E	1615	TEMPORARY MULCHING	1.5	ACR	
0055	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100	LB	

County : Dare

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.5 TON		
0057	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0058	6029000000-E	SP	SAFETY FENCE	200 LF		
0059	6036000000-E	1631	MATTING FOR EROSION CONTROL	3,000 SY		
0060	6037000000-E	SP	COIR FIBER MAT	100 SY		
0061	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	285 SY		
0062	6070000000-N	1639	SPECIAL STILLING BASINS	3 EA		
0063	6071012000-E	SP	COIR FIBER WATTLE	540 LF		
0064	6084000000-E	1660	SEEDING & MULCHING	1.2 ACR		
0065	6087000000-E	1660	MOWING	1.2 ACR		
0066	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0067	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0068	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0069	6108000000-E	1665	FERTILIZER TOPDRESSING	0.75 TON		
0070	6111000000-E	SP	IMPERVIOUS DIKE	360 LF		
0071	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0072	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	25 EA		
0073	6117500000-N	SP	CONCRETE WASHOUT STRUCTURE	1 EA		
0074	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (42+68.00)	Lump Sum	L.S.	
0075	8065000000-N	SP	ASBESTOS ASSESSMENT	Lump Sum	L.S.	

County : Dare

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0076	8112730000-N	450	PDA TESTING	2 EA		
0077	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (42+68.00)	Lump Sum	L.S.	
0078	8175000000-E	420	CLASS AA CONCRETE (BRIDGE)	97 CY		
0079	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (42+68.00)	Lump Sum	L.S.	
0080	8224000000-E	425	EPOXY COATED REINFORCING STEEL (BRIDGE)	9,465 LB		
0081	8328000000-E	450	PILE DRIVING EQUIPMENT SETUP FOR *** PRESTRESSED CONCRETE PILES (12")	16 EA		
0082	8329000000-E	450	12" PRESTRESSED CONCRETE PILES	640 LF		
0083	8393000000-N	450	PILE REDRIVES	8 EA		
0084	8430000000-E	452	SHEET PILE RETAINING WALLS	930 SF		
0085	8475000000-E	460	TWO BAR METAL RAIL	55.25 LF		
0086	8505000000-E	460	VERTICAL CONCRETE BARRIER RAIL	62.75 LF		
0087	8517000000-E	460	1'-***X ***** CONCRETE PARAPET (2", 3'-6")	62.75 LF		
0088	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	117 TON		
0089	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	99 SY		
0090	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0091	8763000000-E	430	3'-0" X 2'-0" PRESTRESSED CONC CORED SLABS	879 LF		