

FED AID NO STATE FUNDED  
CONSTRUCT OPEN-AIR PASSENGER SHELTERS  
HATTERAS FERRY TERMINAL OCRACOCKE SOUTH FERRY TERMINAL

A R CHESSON CONSTRUCTION CO  
INC  
WILLIAMSTON, NC

**ROADWAY ITEMS**

0001	0000100000-N	800	MOBILIZATION	Lump Sum		26460.61
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum		18975.00
0003	0043000000-N	226	GRADING	Lump Sum		58650.00
0004	0050000000-E	226	SUPP CLEARING & GRUBBING	0.25 ACR	7187.00	1796.75
0005	0057000000-E	226	UNDERCUT EXCAVATION	150 CY	112.00	16800.00
0006	0255000000-E	SP	GENERIC GRADING ITEM (TON) (WASHED #57 STONE)	33 TON	92.00	3036.00
0007	0331000000-E	SP	GENERIC DRAINAGE ITEM (CY) (CONCRETE SPILLWAY LIP)	1.25 CY	2265.00	2831.25
0008	0542000000-E	310	*** PVC PIPE CULVERTS (8")	18 LF	45.54	819.72
0009	0986000000-E	SP	GENERIC PIPE ITEM (LF) (8" PREFORATED PVC PIPE)	182 LF	52.90	9627.80
0010	1121000000-E	520	AGGREGATE BASE COURSE	810 TON	85.80	69498.00
0011	1519000000-E	610	ASP CONC SURF CRS S9.5B	650 TON	132.25	85962.50
0012	1575000000-E	620	ASP FOR PLANT MIX	45 TON	479.00	21555.00
0013	1858000000-E	710	*****PCC PVMT RAMPS (6")	175 SY	256.00	44800.00
0014	2022000000-E	815	SUBDRAIN EXCAVATION	25 CY	71.30	1782.50
0015	2026000000-E	815	GEOTEXTILE FOR SUBSURF DRNS	122 SY	6.45	786.90
0016	2591000000-E	848	4" CONCRETE SIDEWALK	117 SY	150.00	17550.00
0017	2605000000-N	848	CONCRETE CURB RAMP	4 EA	1782.00	7128.00
0018	2759000000-N	SP	GENERIC PAVING ITEM (EA) (CONCRETE WHEEL STOPS)	46 EA	172.50	7935.00
0019	3533000000-E	866	CHN LK FENCE *** FABRIC (72")	431 LF	20.00	8620.00
0020	3539000000-E	866	MET LINE PST *** CL FEN (72")	40 EA	40.00	1600.00
0021	3545000000-E	866	MET TERM PST *** CL FEN (72")	11 EA	78.00	858.00
0022	3551000000-E	866	MET GATE PST *** CL FEN S (72")	2 EA	150.00	300.00
0023	3564000000-E	866	SGL GATE **HIGH, **WIDE, **OPEN (72" X 6' X 6')	1 EA	80.00	80.00
0024	3572000000-E	867	CHAIN LINK FENCE RESET	193 LF	10.00	1930.00
0025	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	75 SY	11.90	892.50
0026	4116100000-N	904	SIGN ERECT, RELOC ** GRD MTD (METAL)	3 EA	200.00	600.00
0027	4413000000-E	SP	WORK ZONE ADV/GEN WARN SIGN	192 SF	38.00	7296.00
0028	4457000000-N	SP	TEMP TRAFFIC CONTROL (SP)	Lump Sum		11270.00
0029	4600000000-N	SP	GENERIC TRAFFIC CONTROL ITEM (EA) (RELOCATE CONCRETE WHEEL STOPS)	8 EA	115.00	920.00
0030	4685000000-E	1205	THERMO PVT MKG LINES 4"90	4,695 LF	9.03	42395.85
0031	4686000000-E	1205	THERMO PVT MKG LINES 4"120	25 LF	11.00	275.00
0032	4695000000-E	1205	THERMO PVT MKG LINES 8"90 MILS	1,045 LF	11.00	11495.00
0033	4710000000-E	1205	24"WIDE THERMO 120 MILS	110 LF	74.75	8222.50

FED AID NO STATE FUNDED  
CONSTRUCT OPEN-AIR PASSENGER SHELTERS  
HATTERAS FERRY TERMINAL OCRACOCKE SOUTH FERRY TERMINAL

A R CHESSON CONSTRUCTION CO  
INC  
WILLIAMSTON, NC

0034	4721000000-E	1205 THERMO PVT MKG CHARACTER 120	7 EA	575.00	4025.00
0035	4725000000-E	1205 THERMO PVT SYMBOL 90MILS	23 EA	517.50	11902.50
0036	4850000000-E	1205 LINE REMOVAL 4" WIDE	360 LF	20.70	7452.00
0037	4860000000-E	1205 LINE REMOVAL 8" WIDE	175 LF	23.00	4025.00
0038	4870000000-E	1205 LINE REMOVAL 24" WIDE	70 LF	51.75	3622.50
0039	5709100000-E	1520 2" FORCE MAIN SEWER	250 LF	48.30	12075.00
0040	6000000000-E	1605 TEMPORARY SILT FENCE	1,273 LF	3.45	4391.85
0041	6006000000-E	1610 EROS CONTRL STONE CL A	37.5 TON	140.00	5250.00
0042	6015000000-E	1615 TEMPORARY MULCHING	0.35 ACR	2860.00	1001.00
0043	6018000000-E	1620 SEED FOR TEMP SEEDING	70 LB	5.00	350.00
0044	6021000000-E	1620 FERT FOR TEMP SEEDING	0.35 TON	1700.00	595.00
0045	6084000000-E	1660 SEEDING AND MULCHING	0.35 ACR	6600.00	2310.00
0046	6087000000-E	1660 MOWING	0.35 ACR	600.00	210.00
0047	6090000000-E	1661 SEED FOR REPAIR SEEDING	25 LB	18.00	450.00
0048	6093000000-E	1661 FERT FOR REPAIR SEEDING	0.18 TON	1700.00	306.00
0049	6096000000-E	1662 SEED FOR SUPP SEEDING	35 LB	18.00	630.00
0050	6102000000-E	1664 SODDING	165 SY	9.00	1485.00
0051	6108000000-E	1665 FERTILIZER TOPDRESSING	0.18 TON	1700.00	306.00
0052	6114500000-N	1667 SPECIALIZED HAND MOWING	7 MHR	70.00	490.00
0053	6132000000-N	SP GENERIC EROSION CONTROL ITEM (EA) (CONCRETE WASHOUT STRUCTURE)	2 EA	1023.00	2046.00

**STRUCTURE ITEMS**

0054	8000000000-N	800 MOBILIZATION (STRUCTURES)	Lump Sum		43783.00
0055	8860000000-N	SP GENERIC STRUCTURE ITEM (LS) (CORNER RAILS)	Lump Sum		18600.00
0056	8860000000-N	SP GENERIC STRUCTURE ITEM (LS) (REMOVE EXIST WD. RAMP & CONSTRUCT NEW)	Lump Sum		17040.00
0057	8860000000-N	SP GENERIC STRUCTURE ITEM (LS) (SITE CLEARING FOR SHELTER)	Lump Sum		39805.00
0058	8892000000-E	SP GENERIC STRUCTURE ITEM (SF) (2X6 T&G ROOF DECK)	4,200 SF	21.60	90720.00
0059	8892000000-E	SP GENERIC STRUCTURE ITEM (SF) (4" CONCRETE PAD OUTSIDE SHELTER)	3,575 SF	23.28	83226.00
0060	8892000000-E	SP GENERIC STRUCTURE ITEM (SF) (4" CONCRETE PAD WITHIN SHELTER)	3,000 SF	23.28	69840.00
0061	8892000000-E	SP GENERIC STRUCTURE ITEM (SF) (ROOF SHINGLES)	4,200 SF	5.58	23436.00
0062	8892000000-E	SP GENERIC STRUCTURE ITEM (SF) (TIMBER ROOF FRAMING/TRUSSES FOR COVERED SHELTER)	4,200 SF	68.53	287826.00
0063	8892000000-E	SP GENERIC STRUCTURE ITEM (SF) (UNDERLAYMENT)	4,200 SF	1.74	7308.00
0064	8897000000-N	SP GENERIC STRUCTURE ITEM (EA) (BENCHES)	48 EA	973.00	46704.00

DEC 07, 2017 08:00 AM

DARE, HYDE

TIP NO F-5702A, F-5702B

44973.3.1, 44973.3.2

2:00PM 3 / 3 001

DEC 06 2017 DA00388  
0.020 MI

FED AID NO STATE FUNDED

CONSTRUCT OPEN-AIR PASSENGER SHELTERS

HATTERAS FERRY TERMINAL OCRACOKE SOUTH FERRY TERMINAL

A R CHESSON CONSTRUCTION CO  
INC  
WILLIAMSTON, NC

0065	8897000000-N	SP	GENERIC STRUCTURE ITEM (EA) (ELECTRICAL LIGHT FIXTURES)	8 EA	3925.00	31400.00
0066	8897000000-N	SP	GENERIC STRUCTURE ITEM (EA) (TIMBER PILES FOR COVERED SHELTER)	32 EA	4150.00	132800.00
0067	8897000000-N	SP	GENERIC STRUCTURE ITEM (EA) (TRIANGULAR VENTS)	2 EA	960.00	1920.00

CONTRACT TOTAL TOTAL 1450080.73

ROADWAY ITEMS SUB-TOTAL 555672.73

STRUCTURE ITEMS SUB-TOTAL 894408.00

**BIDDERS IN ORDER CONTRACT TOTAL**

A R CHESSON CONSTRUCTION CO INC 1 1450080.73