



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

ROY COOPER
GOVERNOR

JAMES H. TROGDON, III
SECRETARY

January 10, 2019

WBS No: 50138.3.30
Contract No: DJ00309
County: Union
Description: Grading, Drainage, Paving, Concrete Monolithic Islands, Concrete Curb and Gutter, Erosion Control and Thermoplastic Pavement Markings for the Construction at the Intersections of Waxhaw Hwy (NC 75) and S. Rocky River Rd. (SR-1007) and Old Waxhaw Monroe Rd. (SR-1150).

Addendum No. 1
January 16, 2019 Letting

To: Prospective Bidders

Please note the following revision to the plans for the above referenced project.

- Summary of Earthwork Quantities Table in the plans has been revised. The quantities for Unclassified Excavation was changed from 850 CY to 880 CY and Borrow Excavation changed from 5590 CY to 3700 CY.

The changes and attachments included with this addendum will become part of contract DJ00309.

For Electronic Bid using Bid Express® please delete the EBS files you previously downloaded for DJ00309 for the January 16, 2019 letting and download the new EBS files (DJ00309.EBS and DJ00309.001) listed for DJ00309. Bid Express will not accept your bid unless the new EBS file associated with the January 16, 2019 letting is used.

If you have any questions, please contact me at (704) 983-4400.

Sincerely,

DocuSigned by:
Donald Harward
D47AFDC4A327453...
Donald Harward
Division/Design Construct Engineer

cc: Kellie Crump, Project Manager
File

STATE OF NORTH CAROLINA
 DIVISION OF HIGHWAYS

DOCUMENT NOT CONSIDERED FINAL
 UNLESS ALL SIGNATURES COMPLETED

RIGHT OF WAY AREA DATA

PARCEL NO.	PROPERTY OWNERS NAMES	TOTAL ACREAGE	TOTAL RIGHT OF WAY AREA TAKEN	AREA REMAINING RT.	AREA REMAINING LT.	TEMP. CONST. EASE.	PERM. DRAIN. EASE.	AERIAL UTL. EASE.	PERM. UTL. EASE.
1	KATHY H CLARK		129.20 SF			727.20 SF			336.92 SF
2	GERALD THOMAS		19106.09 SF			1118.91 SF			54.07 SF
3	DAVID & BARBARA C FAZELINA		7929.75 SF			3291.63 SF	397.33 SF		4150.31 SF
4	CARL & YVONNE M STACKS					312.23 SF	793.77 SF		
5	LINDA C YOW						126.28 SF		2376.11 SF
6	SHONE M HOUSTON		1493.90 SF			1382.13 SF			
7	LEE FARMS ROBERT BRADFORD LEE		4379.04 SF			1439.92 SF			1310.95 SF
8	UNKNOWN		1651.26 SF			1330.08 SF			6629.61 SF
9	SEABOARD COASTLINE RR							3645.71 SF	

SUMMARY OF EARTHWORK

LINE	STATION	STATION	UNCL. EXCAV. (CY)	EMBANK. + 20% (CY)	BORROW (CY)	WASTE (CY)
L1	14+40.00	17+66.59	113	180	67	
L2	10+00.00	15+28.83	355	180		175
Y1	10+00.00	14+54.58	79	920	841	
Y2	11+40.00	15+89.28	226	876	650	
Y3	10+40.00	11+38.50	68	2		66
RAB	-RAB1-10+00.00	-RAB1-13+64.42	30	2189	2159	
SUBTOTAL:			871	4347	3717	241
EARTH TO REPLACE BORROW					-241	-241
PROJECT TOTALS:			871	4347	3476	0
ESTIMATE 5% TOPSOIL FOR BORROW PITS:				218	218	
GRAND TOTALS:			871	4565	3694	
SAY:			880		3700	

CURB & GUTTER SUMMARY

CLASS AA CONCRETE 1'-6" CURB AND GUTTER				
LINE	STATION	STATION	LENGTH	REMARKS
L1/L2	17+15.00 (LT)	14+85.00 (RT)	226.20	
L1/Y1	16+95.00 (RT)	13+65.00 (LT)	207.50	
Y1/Y2	14+20.00 (RT)	15+02.00 (LT)	161.50	
Y2/L2	15+51.00 (RT)	14+25.00 (LT)	220.60	
RAB1	CENTRAL ISLAND		364.42	
TOTAL CLASS AA 1'-6" CURB & GUTTER:			1180.22	
SAY:			1190	
MODIFIED 2'-6" CURB AND GUTTER				
LINE	STATION	STATION	LENGTH	REMARKS
RAB1	CENTRAL ISLAND		267	
TOTAL MODIFIED 2'-6" CURB & GUTTER:			267	
SAY:			270	

PAVEMENT REMOVAL SUMMARY

LINE	STATION	STATION	LOCATION L/RT/CL	YD ²
-Y1/Y2-	11+97 +/-	11+40 +/-	RTL/L	1297.92 SY
-L2-	13+12 +/-	15+90 +/-	RT	469.67 SY
-L1/L2-	16+31 +/-	14+79 +/-	L/RT	381.53 SY
-Y3-	10+75 +/-	11+59 +/-	RTL/L	166.03 SY
TOTAL:				2,315.15 SY
SAY:				2,320 SY

NOTE:
 APPROXIMATE QUANTITIES ONLY. UNCLASSIFIED EXCAVATION, BORROW EXCAVATION, FINE GRADING, CLEARING AND GRUBBING, AND REMOVAL OF EXISTING PAVEMENT WILL BE PAID FOR AT THE CONTRACT LUMP SUM PRICE FOR "GRADING."