

ADDENDUM No. 3

TO: Prospective Bidders

FROM: Sadia Khan, Contracts Administrator

DATE: January 19, 2018

PROJECT: **Beam Road at Shopton Road (SR 1155) Roundabout**
 Project Number: 512-13-010
 TIP Number: C-5533
 Bid Number: HC2017-1042

The following items are being issued herein for modification and clarification to the Bid Requirements for the project referenced above. All Bidders shall acknowledge this Addendum within their submittal.

MODIFICATIONS

PROJECT MANUAL

- 1) Under Section 00 40 00 "ITEMIZED BID", following items have been *deleted* and *added*:

Item #	Section #	Description	Qty	Unit	Unit Price (\$)	Amount Bid (\$) (Qty x Unit Price)
63	SPU-03	Subdrain Clean Out	1	EA		

The Electronic Itemized Bid Form available at the City's website has been revised to reflect the above changes.

- 2) On page 00 75 00 – 25, insert the following **SPU-03, SUBDRAIN CLEAN OUT**:

SPU-03, SUBDRAIN CLEAN OUT

1.0 DESCRIPTION

The work covered by this special provision includes furnishing all materials, equipment, and labor required to install subdrain cleanouts to finished grade, as specified and as shown on the Plans and Standard Details.

2.0 MEASUREMENT AND PAYMENT

Measurement will be made on a per each basis for all materials and labor necessary for each "Subdrain Clean Out" that has been completed and accepted.

Payment will be made under:

SUBDRAIN CLEAN OUT..... EA

END OF ADDENDUM NO. 3

ITEMIZED BID

Project #: 512-13-010

Project Name: Beam Road at Shopton Road (SR 1155) Roundabout

SECTION 1: BID

ADDENDUM # 3

Item #	Section #	Description	Qty	Unit	Unit Price (\$)	Amount Bid (\$) (Qty x Unit Price)
1	800	Mobilization	1	LS		
2	226	Grading	1	LS		
3	SP-03	Select Material	300	TN		
4	226	Undercut Excavation	550	CY		
5	300	Foundation Conditioning Material, Minor Structures	100	TN		
6	310	15" R.C. Pipe Culverts, Class III	919	LF		
7	310	15" R.C. Pipe Culverts, Class IV	232	LF		
8	310	18" R.C. Pipe Culverts, Class III	256	LF		
9	310	18" R.C. Pipe Culverts, Class IV	144	LF		
10	340	Pipe Removal	380	LF		
11	SP-04	Wall, Precast Modular Block Retaining	280	SF		
12	545	Incidental Stone Base	100	TN		
13	607	Milling Asphalt Pavement, 0.0" to 3.0"	7,300	SY		
14	610	Asphalt Concrete Base Course, Type B 25.0 C	1,610	TN		
15	610	Asphalt Concrete Intermediate Course, Type I 19.0 C	1,070	TN		
16	610	Asphalt Concrete Surface Course, Type S 9.5 C	1,250	TN		

ADDENDUM # 3

Item #	Section #	Description	Qty	Unit	Unit Price (\$)	Amount Bid (\$) (Qty x Unit Price)
17	620	Asphalt Binder for Plant Mix	235	TN		
18	840	Masonry Drainage Structures	16	EA		
19	840	Masonry Drainage Structures, Extra Depth	10	LF		
20	858	Adjustment of Manholes	2	EA		
21	840	Frame with Grate (all types)	15	EA		
22	840	Manhole Frame and Cover, NCDOT Std 840.54	1	EA		
23	840	Pipe Collars	3	CY		
24	840	Pipe Plugs	1	CY		
25	846	6" x 12" Concrete Curb	130	LF		
26	SP-15	1' 6" Concrete Curb and Gutter with Black Tint, Class AA Concrete	695	LF		
27	846	2' 6" Concrete Curb and Gutter	2,635	LF		
28	848	4 " Concrete Sidewalk	1,755	SY		
29	SP-05	Truck Mountable Island	610	SY		
30	SP-06	Pedestrian Ramps at Truck Aprons	30	SY		
31	SP-07	Ramps, Wheelchair concrete	260	SY		
32	852	Monolithic Concrete Islands, 5"	520	SY		
33	867	Metal Fence Reset	540	LF		
34	SP-10	4" Perforated Subdrain Pipe w/Stone & Filter Fabric (CLDS 40.08A, B, C)	160	LF		
35	SP-11	4" Schedule 80 PVC	55	LF		
36	SP-12	CDOT 2.0" PVC Conduit, Schedule 80	200	LF		

ADDENDUM # 3

Item #	Section #	Description	Qty	Unit	Unit Price (\$)	Amount Bid (\$) (Qty x Unit Price)
37	901	Contractor Furnished, Type D Sign	1,165	SF		
38	903	Supports, 3-lb Steel U-Channel	215	LF		
39	904	Sign Erection, Type D	37	EA		
40	SP-08	Reflective Paddles	4	EA		
41	SP-09	Traffic Control	1	LS		
42	1205	Thermoplastic Pavement Marking Lines, 4", 90 mils	821	LF		
43	1205	Thermoplastic Pavement Marking Lines, 4", 120 mils	5,373	LF		
44	1205	Thermoplastic Pavement Marking Lines, 6", 90 mils	3,739	LF		
45	1205	Thermoplastic Pavement Marking Lines, 6", 120 mils	178	LF		
46	1205	Thermoplastic Pavement Marking Lines, 8", 90 mils	522	LF		
47	1205	Thermoplastic Pavement Marking Lines, 8", 120 mils	716	LF		
48	1205	Thermoplastic Pavement Marking Lines, 12", 90 mils	62	LF		
49	1205	Thermoplastic Pavement Marking Lines, 12", 120 mils	60	LF		
50	1205	Thermoplastic Pavement Marking Symbols	38	EA		
51	1251	Permanent Raised Pavement Markers	75	EA		
52	1605	Temporary Silt Fence	1,655	LF		
53	1610	Sediment Control Stone	170	TN		
54	1610	Stone for Erosion Control, Class B	50	TN		
55	1632	¼" Hardware Cloth	260	LF		
56	SP-13	Catch Basin Inlet Protection	17	EA		

ADDENDUM # 3

Item #	Section #	Description	Qty	Unit	Unit Price (\$)	Amount Bid (\$) (Qty x Unit Price)
57	1660	Seeding and Mulching	2	AC		
58	SP-14	Temporary Tree Protection Fence	60	LF		
59	SPU-01	Adjust Water Valve	1	EA		
60	SPU-02	Relocate Fire Hydrant	1	EA		
61	SP-16	Planting Mix	230	CY		
62	1120	Portable Changeable Message Sign	4	EA		
63	SPU-03	Subdrain Clean Out	1	EA		
Total Amount Bid						

Do **not** include any North Carolina Sales and Use Tax that qualifies as Eligible Taxes per Section 00 70 00, Subsection 2.17 "Sales and Use Tax".