



PAT McCRORY
Governor

NICHOLAS J. TENNYSON
Secretary

May 16, 2016

WBS No: 45340.3.12
County: Union
Location: US 74 from Fowler Secrest Rd. (SR-1510) to NC 200 (Morgan Mill Rd.)
Description: Grading, Paving, Milling, Drainage, Concrete Monolithic Islands, and Thermoplastic Pavement Markings

Addendum No. 1
May 25, 2016 Letting

To: Prospective Bidders

Please note the following revisions to the Bid Sheet for the above mentioned project.

- Revised Bid Sheet Quantity for Line Item 12, Master Item No. 1297000000-E, Milling Asphalt Pavement, 1.5" Depth. The revised Bid Sheet is attached to this letter.

The following revision shall be reviewed and the revised Bid Sheet shall be attached to the back of the contract when it is returned to be opened on Wednesday May 25, 2016 at 10:00 AM. The old bid sheet shall be removed and replaced with the revised bid sheet.

If you are submitting an electronic bid package you must go to the Division 10 Letting site and download and use the DJ00193.001 addendum file. The Division 10 Letting site can be accessed at the following link:

https://connect.ncdot.gov/letting/Pages/Letting-Details.aspx?let_type=10&let_date=2016-05-25

If you have any questions, please contact me at (704) 983-4400.

Sincerely,

A handwritten signature in black ink that reads "Randy Bowers". The signature is written in a cursive, flowing style.

Randy Bowers
DDC Engineer

cc: Kellie Crump
Scott Cole, P.E.



WBS : 45340.3.12

TIP: W-5210L

Type of Work: Grading, Paving, Milling, Drainage, Concrete Monolithic Islands, and Thermoplastic Pavement Markings

County: Union

Location: US 74 from Fowler Secrest Road (SR-1510) to NC 200 (Morgan Mill Road)

LINE NO.	DESC. NO.	MASTER ITEM NO.	SEC. NO.	ITEM DESCRIPTION	EST. QTY.	UNIT	UNIT PRICE	TOTAL AMOUNT
1	1	0000100000-N	800	MOBILIZATION	1	LS		
2	32	0043000000-N	226	GRADING	1	LS		
3	34	0057000000-E	226	UNDERCUT EXCAVATION	150	CY		
4	60	0234000000-E	SP	BORROW EXCAVATION (PIPE INSTALLATION)	100	CY		
5	71	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	150	TON		
6	72	0320000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	500	SY		
7	93	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	1424	LF		
8	94	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	672	LF		
9	115	0453000000-E	310	15" PIPE END SECTION	1	EA		
10	159	0995000000-E	340	PIPE REMOVAL	50	LF		
11	188	1220000000-E	545	INCIDENTAL STONE BASE	100	TON		
12	196	1297000000-E	607	MILLING ASPHALT PAVEMENT, 1.5" DEPTH	6100	SY		
13	204	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	2200	TON		
14	207	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	1550	TON		
15	211	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	1100	TON		
16	221	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	239	TON		
17	228	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	100	TON		
18	313	2253000000-E	840	PIPE COLLARS	1	CY		
19	314	2264000000-E	840	PIPE PLUGS	1	CY		
20	316	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	48	EA		
21	318	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	2	LF		
22	324	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	28	EA		
23	326	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	12	EA		
24	330	2396000000-N	840	FRAME WITH COVER, STD 840.54	5	EA		
25	337	2472000000-N	840	MODIFIED CONCRETE DROP INLET	1	EA		
26	367	2647000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED)	2280	SY		
27	388	2830000000-N	858	ADJUSTMENT OF MANHOLES	2	EA		
28	389	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	2	EA		

29	612	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	400	SF		
30	619	4430000000-N	1130	DRUMS	200	EA		
31	651	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	8300	LF		
32	652	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	2000	LF		
33	656	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	3500	LF		
34	658	4700000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (12", 90 MILS)	1200	LF		
35	663	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	19	EA		
36	684	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	8000	LF		
37	698	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	200	LF		
38	1010	6012000000-E	1610	SEDIMENT CONTROL STONE	60	TON		
39	1017	6036000000-E	1631	MATTING FOR EROSION CONTROL	200	SY		
40	1021	6042000000-E	1632	1/4" HARDWARE CLOTH	700	LF		
41	1034	6071010000-E	SP	WATTLE	200	LF		
42	1038	6071020000-E	SP	POLYACRYLAMIDE (PAM)	2	LB		
43	1045	6084000000-E	1660	SEEDING & MULCHING	2	ACR		

Total Bid for Project

CONTRACTOR _____

ADDRESS _____

Federal ID No. _____

Contr. License No. _____

Telephone No. _____

Vendor No. _____

Authorized Agent _____

Signature _____

Witness _____

Signature _____



Title _____

Date _____

Title _____

Date _____