WBS : 44720.3.1 TIP: SS-4910CC

Type of Work: Grading, Paving, Drainage, and Thermoplastic Pavement Markings

County: Union

Location: New Town Road (SR-1315) and Cuthbertson Road (SR-1321)

LINE NO.	DESC. NO.	MASTER ITEM NO.	SEC. NO.	ITEM DESCRIPTION	EST. QTY.	UNIT	UNIT PRICE	TOTAL AMOUNT
1	1	0000100000-N	800	MOBILIZATION	1	LS		
2	33	0043000000-N	226	GRADING	1	LS		
3	35	0057000000-E	226	UNDERCUT EXCAVATION	100	CY		
4	61	0234000000-E	SP	BORROW EXCAVATION (PIPE INSTALLATION)	50	CY		
5	72	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	20	TON		
6	73	0320000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	60	SY		
7	77	0335100000-E	305	12" DRAINAGE PIPE	116	LF		
8	93	0360000000-E	310	12" RC PIPE CULVERTS, CLASS III	48	LF		
9	156	0995000000-E	340	PIPE REMOVAL	62	LF		
10	185	1220000000-E	545	INCIDENTAL STONE BASE	60	TON		
11	196	1330000000-E	607	INCIDENTAL MILLING	180	SY		
12	202	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	510	TON		
13	205	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	375	TON		
14	209	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	500	TON		
15	216	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	71	TON		
16	221	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	50	TON		
17	372	2830000000-N	858	ADJUSTMENT OF MANHOLES	1	EA		
18	373	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	2	EA		
19	595	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	72	SF		
20	607	4430000000-N	1130	DRUMS	50	EA		
21	648	4700000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (12", 90 MILS)	105	LF		
22	651	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	55	LF		
23	653	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	3	EA		
24	704	4891000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS) (HIGHLY REFLECTIVE)	5110	LF		
25	705	4891000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS) (HIGHLY REFLECTIVE)	2900	LF		
26	710	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	40	EA		
27	985	6000000000-E	1605	TEMPORARY SILT FENCE	300	LF		
28	986	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	28	TON		

29	988	6012000000-E	1610	SEDIMENT CONTROL STONE	10	TON		
30	995	6036000000-E	1631	MATTING FOR EROSION CONTROL	7500	SY		
31	1012	6071010000-E	SP	WATTLE	180	LF		
32	1016	6071020000-E	SP	POLYACRYLAMIDE (PAM)	2	LB		
33	1023	6084000000-E	1660	SEEDING & MULCHING	2	ACR		
34	1189	7060000000-E	1705	SIGNAL CABLE	300	LF		
35	1194	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	4	EA		
36	1195	7132000000-E	1705	VEHICLE SIGNAL HEAD (12", 4 SECTION)	1	EA		
37	1207	7264000000-E	1710	MESSENGER CABLE (3/8")	150	LF		
38	1211	7300000000-E	1715	UNPAVED TRENCHING (1 CONDUIT, 2 INCH)	700	LF		
39	1216	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	7	EA		
40	1218	7360000000-N	1720	WOOD POLE	1	EA		
41	1219	7372000000-N	1721	GUY ASSEMBLY	2	EA		
42	1223	7420000000-E	1722	2" RISER WITH WEATHERHEAD	1	EA		
43	1226	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	350	LF		
44	1227	7456000000-E	1726	LEAD-IN CABLE (14-2)	1100	LF		
Total Bid for Project								