



STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION

ROY COOPER  
GOVERNOR

JAMES H. TROGDON, III  
SECRETARY

August 1, 2018

WBS No: 45773.3.1  
Contract No: DJ00296  
County: Stanly  
Description: Remove and Replace Bridge #221 over Curl Tail Creek on SR 1507 (Gold Branch Rd) with a Precast Three Sided Culvert.

**Addendum No. 1**  
**August 15, 2018 Letting**

To: Prospective Bidders

Please note the following revision to the proposal for the above referenced project.


- A Special Provision was added for "Response for Erosion Control". Special provision is attached.
- Response for Erosion Control pay item (Line No. 51) was added to the bid sheet. A revised bid sheet is attached.

The changes and attachments included with this addendum will become part of contract DJ00296.

For Electronic Bid using Bid Express® please delete the EBS files you previously downloaded for DJ00296 for the August 15, 2018 letting and download the new EBS files (DJ00296.EBS and DJ00296.001) listed for DJ00296. Bid Express will not accept your bid unless the new EBS files associated with the August 15, 2018 letting are used.

If you have any questions, please contact me at (704) 983-4400.

Sincerely,

DocuSigned by:  
  
5169D778708C4B7...

Terry Burleson  
Contracts Engineer

cc: Kellie Crump, Project Manager  
File

Mailing Address:  
NC DEPARTMENT OF TRANSPORTATION  
HIGHWAY DIVISION 10  
716 WEST MAIN ST.  
ALBEMARLE, NC 28001

Telephone: (704) 983-4400  
Fax: (704) 982-3146  
Customer Service: 1-877-368-4968

Location:  
716 WEST MAIN ST.  
ALBEMARLE, NC 28001

Website: [www.ncdot.gov](http://www.ncdot.gov)

## **RESPONSE FOR EROSION CONTROL:**

### **Description**

Furnish the labor, materials, tools and equipment necessary to move personnel, equipment, and supplies to the project necessary for the pursuit of any or all of the following work as shown herein, by an approved subcontractor.

<b>Section</b>	<b>Erosion Control Item</b>	<b>Unit</b>
1605	Temporary Silt Fence	LF
1606	Special Sediment Control Fence	LF/TON
1615	Temporary Mulching	ACR
1620	Seed - Temporary Seeding	LB
1620	Fertilizer - Temporary Seeding	TN
1631	Matting for Erosion Control	SY
SP	Coir Fiber Mat	SY
1640	Coir Fiber Baffles	LF
SP	Permanent Soil Reinforcement Mat	SY
1660	Seeding and Mulching	ACR
1661	Seed - Repair Seeding	LB
1661	Fertilizer - Repair Seeding	TON
1662	Seed - Supplemental Seeding	LB
1665	Fertilizer Topdressing	TON
SP	Safety/Highly Visible Fencing	LF
SP	Response for Erosion Control	EA

### **Construction Methods**

Provide an approved subcontractor who performs an erosion control action as described in the NPDES Inspection Form SPPP30. Each erosion control action may include one or more of the above work items.

### **Measurement and Payment**

*Response for Erosion Control* will be measured and paid for by counting the actual number of times the subcontractor moves onto the project, including borrow and waste sites, and satisfactorily completes an erosion control action described in Form 1675. The provisions of Article 104-5 of the *Standard Specifications* will not apply to this item of work.

Payment will be made under:

**Pay Item**

Response for Erosion Control

**Pay Unit**

Each

Work Order No. <u>B-5820</u>							
7/31/2018 <u>Remove and Replace Bridge # 221 Over Curl Tail Creek on SR 1507 (Gold Branch Rd.)</u>							
County <u>Stanly</u>							
LINE NO.	MASTER ITEM NO.	SEC. NO.	ITEM DESCRIPTION	ESTIMATED QUANTITY	UNIT	UNIT PRICE	TOTAL AMOUNT
1	0000100000-N	800	MOBILIZATION	1	LS		
2	0000400000-N	801	CONSTRUCTION SURVEYING	1	LS		
3	0063000000-N	SP	GRADING	1	LS		
4	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	600	SY		
5	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	20	TON		
6	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	50	SY		
7	0448300000-E	310	18" RC PIPE CULVERTS, CLASS IV	144	LF		
8	1099500000-E	505	SHALLOW UNDERCUT	100	CY		
9	1099700000-E	505	CLASS IV SUBGRADE STABILIZATION	200	TON		
10	1121000000-E	520	AGGREGATE BASE COURSE	15	TON		
11	1220000000-E	545	INCIDENTAL STONE BASE	50	TON		
12	1330000000-E	607	INCIDENTAL MILLING	210	SY		
13	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	270	TON		
14	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	300	TON		
15	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	440	TON		
16	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	55	TON		
17	3635000000-E	876	RIP RAP, CLASS II	140	TON		
18	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	505	SY		
19	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	412	SF		
20	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	216	SF		
21	4445000000-E	1145	BARRICADES (TYPE III)	128	LF		
22	5325800000-E	1510	8" WATER LINE	136	LF		
23	5329000000-E	1510	DUCTILE IRON WATER PIPE FITTINGS	575	LB		
24	5546000000-E	1515	8" VALVE	1	EA		
25	5709200000-E	1520	4" FORCE MAIN SEWER	117	LF		
26	5769000000-E	1520	DUCTILE IRON SEWER PIPE FITTINGS	400	LB		
27	5798000000-E	1530	ABANDON 4" UTILITY PIPE	139	LF		

28	5801000000-E	1530	ABANDON 8" UTILITY PIPE	116	LF		
29	5912000000-N	SP	TEMPORARY STREAM BYPASS PUMPING	1	LS		
30	6000000000-E	1605	TEMPORARY SILT FENCE	670	LF		
31	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	80	TON		
32	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	165	TON		
33	6012000000-E	1610	SEDIMENT CONTROL STONE	155	TON		
34	6029000000-E	SP	SAFETY FENCE	200	LF		
35	6030000000-E	1630	SILT EXCAVATION	90	CY		
36	6036000000-E	1631	MATTING FOR EROSION CONTROL	900	SY		
37	6037000000-E	SP	COIR FIBER MAT	100	SY		
38	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	100	SY		
39	6042000000-E	1632	1/4" HARDWARE CLOTH	210	LF		
40	6045000000-E	SP	36" TEMPORARY PIPE	135	LF		
41	6070000000-N	1639	SPECIAL STILLING BASINS	4	EA		
42	6071020000-E	SP	POLYACRYLAMIDE (PAM)	45	LB		
43	6084000000-E	1660	SEEDING & MULCHING	3.00	ACR		
44	6087000000-E	1660	MOWING	0.50	ACR		
45	6111000000-E	SP	IMPERVIOUS DIKE	271	LF		
46	6117500000-N	SP	CONCRETE WASHOUT STRUCTURE	2	EA		
51	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	10	EA		
<b>CULVERT ITEMS</b>							
47	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STA. 14+47.00 -L-	1	LS		
48	8065000000-N	SP	ASBESTOS ASSESSMENT	1	LS		
49	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION 14+47.00 -L-	1	LS		
50	8804000000-N	SP	PRECAST REINFORCED CONCRETE THREE-SIDED CULVERT AT STA. 14+47.00 -L-	1	LS		

Total Bid For Project \$ \_\_\_\_\_