

# SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP	FINAL SURFACE TESTING REQUIRED	LENGTH MI	WIDTH FT	CLEARING & GRUBBING ..0.19 ACRE(S) LS	CLEARING & GRUBBING ..0.15 ACRE(S) LS	BORROW CY	GEOTEXTILE FOR SOIL STABILIZATION SY	SELECT MATERIAL, CLASS *****VI TON	FOUNDATION CONDITIONING GEOTEXTILE SY	24" RCP, CLASS III LF	
10.106011B-74	Mecklenburg	1	US74/29	SLOPE REPAIR	1	NO	0.5	36	1.00		1,500	550	500	100	32	
<b>TOTAL FOR MAP NO. 1</b>							<b>0.5</b>		<b>1.00</b>		<b>1,500</b>	<b>550</b>	<b>500</b>	<b>100</b>	<b>32</b>	
<b>TOTAL FOR PROJ NO. 10.106011B-74</b>							<b>0.5</b>		<b>1.00</b>		<b>1,500</b>	<b>550</b>	<b>500</b>	<b>100</b>	<b>32</b>	
10.106011B-49	Mecklenburg	2	NC49	SLOPE REPAIR	2	NO	0.5	24		1.00	250	350	300	100	8	
<b>TOTAL FOR MAP NO. 2</b>							<b>0.5</b>			<b>1.00</b>	<b>250</b>	<b>350</b>	<b>300</b>	<b>100</b>	<b>8</b>	
<b>TOTAL FOR PROJ NO. 10.106011B-49</b>							<b>0.5</b>			<b>1.00</b>	<b>250</b>	<b>350</b>	<b>300</b>	<b>100</b>	<b>8</b>	
<b>GRAND TOTAL</b>							<b>1</b>			<b>1.00</b>	<b>1.00</b>	<b>1,750</b>	<b>900</b>	<b>800</b>	<b>200</b>	<b>40</b>

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP	FINAL SURFACE TESTING REQUIRED	LENGTH MI	WIDTH FT	RIP RAP, CLASS A TON	TEMPORARY SILT FENCE LF	SAFETY FENCE LF	MATTING FOR EROSION CONTROL SY	WATTLE LF	SEED & MULCHING AC
10.106011B-74	Mecklenburg	1	US74/29	SLOPE REPAIR	1	NO	0.5	36	80	100	100	933	30	0.19
<b>TOTAL FOR MAP NO. 1</b>							<b>0.5</b>		<b>80</b>	<b>100</b>	<b>100</b>	<b>933</b>	<b>30</b>	<b>0.19</b>
<b>TOTAL FOR PROJ NO. 10.106011B-74</b>							<b>0.5</b>		<b>80</b>	<b>100</b>	<b>100</b>	<b>933</b>	<b>30</b>	<b>0.19</b>
10.106011B-49	Mecklenburg	2	NC49	SLOPE REPAIR	2	NO	0.5	24	60	100	100	726	30	0.15
<b>TOTAL FOR MAP NO. 2</b>							<b>0.5</b>		<b>60</b>	<b>100</b>	<b>100</b>	<b>726</b>	<b>30</b>	<b>0.15</b>
<b>TOTAL FOR PROJ NO. 10.106011B-49</b>							<b>0.5</b>		<b>60</b>	<b>100</b>	<b>100</b>	<b>726</b>	<b>30</b>	<b>0.15</b>
<b>GRAND TOTAL</b>							<b>1</b>		<b>140</b>	<b>200</b>	<b>200</b>	<b>1,659</b>	<b>60</b>	<b>0.34</b>

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	LENGTH	WIDTH	4589000000-N	4589000000-N
							GENERIC TRAFFIC CONTROL ITEM LS	TRAFFIC CONTROL LS
10.106011B-74	Mecklenburg	1	US74/29	SLOPE REPAIR	0.5	36	1.00	
<b>TOTAL FOR MAP NO. 1</b>					<b>0.5</b>		<b>1</b>	
<b>TOTAL FOR PROJ NO. 10.106011B-74</b>					<b>0.5</b>		<b>1</b>	
10.106011B-49	Mecklenburg	2	NC49	SLOPE REPAIR	0.5	24		1
<b>TOTAL FOR MAP NO. 2</b>					<b>0.5</b>			<b>1</b>
<b>TOTAL FOR PROJ NO. 10.106011B-49</b>					<b>0.5</b>			<b>1</b>

