



STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION

ROY COOPER  
GOVERNOR

JAMES H. TROGDON, III  
SECRETARY

August 29, 2017

WBS No: 44856.3.13 & 44856.3.14  
County: Cabarrus and Stanly  
TIP No: W-5710M & W-5710N  
Description: Milled Rumble Strips and Thermoplastic Pavement Markings on NC 3 from SR 2635 (Old Airport Rd) to NC 73 (2.3 Miles) & NC 49 from 0.2 Miles West of N. Main St. (SR 1006) to the Rowan County Line (16.1 Miles)

**Addendum No. 1**  
**September 06, 2017 Letting**

To: Prospective Bidders

We are providing clarification concerning ICT #1 in the advertised proposal. ICT#1 states that the milled rumble strips shall be constructed within 24 hrs. of the removal of the centerline markings. This will only apply if the contractor totally removes the existing centerline markings. The proposed thermoplastic markings cannot be applied directly to the existing thermoplastic marking material. In accordance with Section 1205(I) of the 2012 Standard Specifications, only 25% of the existing thermoplastic markings must be removed for proper bonding of the new markings. This removal is not considered total removal and therefore ICT#1 will not apply.

If you have any questions, please contact me at (704) 983-4400.

Sincerely,

Terry Burleson  
Proposals Engineer

cc: Kellie Crump, Division Project Manager  
Sean Epperson, PE, Division Project Team Lead