

VICINITY MAP

### STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS

PLAN FOR PROPOSED HIGHWAY EROSION CONTROL

### CALDWELL COUNTY

LOCATION: SR 1562 McMILLIAN PLACE FROM SR 1550 BLUE CREEK ROAD 1380FT TO POINT TYPE OF WORK: GRADING, DRAINAGE, BASE AND PAVING - 0.26 MILES

SEEST TOTAL NO. SHEETS STATE **EC-1** 5 11C.014084 EROSION AND SEDIMENT CONTROL MEASURES

1630.05 Temporary Silt Ditch 1630.05 Temporary Diversion \_ \_ \_ \_ \_ \_ 1606.01 Temperary Silt Fence 1606.01 Special Sediment Centrel Fence \_ \_ . 1622.01 Temperary Berms and Slope Drains \_ \_ \_ \_ \_ 1630.02 Silt Basin Type B \_ \_ \_ \_ \_ \_ \_ 1633.01 Temperary Reck Silt Check Type A\_ \_ \_ \_ . Temperary Rock Silt Check Type"A with Matting and Polyacrylamide (PAM) Temperary Reck Silt Check Type B\_\_\_\_ 1633.02 Wattle / Coir Fiber Wattle\_\_\_\_\_ --) Wattle / Cair Fiber Wattle with Polyacrylamide (PAM)\_\_\_\_\_\_ -( **)** Temperary Rock Sediment Dam Type-A\_\_\_ 1634.02 Temperary Reck Sediment Dam Type-B.
Rock Pipe Inlet Sediment Trap Type-A. 1635.01 Rock Pipe Inlet Sediment Trap Type-B\_ \_\_ 1635.09 1630.04 Stilling Basin \_ \_ \_ \_ \_ \_ \_ 1630.06 Special Stilling Basin\_\_\_\_\_\_ Rock Inlet Sediment Trap: A 1632,02 вП C

> THIS PROJECT CONTAINS EROSION CONTROL PLANS FOR CLEARING AND GRUBBING PHASE OF CONSTRUCTION.

Porous Baffle Spacing \*Baffles in Silt Basins at drainage turnouts and all other temporary rock sediment dams-Type B: -If basin length = 10' or less;1 baffle -If basin length=11' to 20';2 baffles -If basin length = 20' or more; 3 baffles equally spaced in basin

PERIMETER EROSION CONTROL MEASURES SHALL BE INSTALLED DURING CLEARING AND GRUBBING PHASE.

Level III-A Cert # 391 Level III-B Cert# 382



ROADSIDE ENVIRONMENTAL UNIT DIVISION OF HIGHWAYS STATE OF NORTH CAROLINA

> THESE EROSION AND SEDIMENT CONTROL PLANS COMPLY WITH THE REGULATIONS SET FORTH BY THE
>
> NCG-010000 GENERAL CONSTRUCTION PERMIT EFFECTIVE AUGUST 3, 2011
> ISSUED BY THE NORTH CAROLINA DEPARTMENT OF ENVIRONMENT AND NATURAL RESOURCES DIVISION OF WATER QUALITY.

Prepared in the Office of:

#### **DIVISION OF HIGHWAYS**

DIVISION 11 DISTRICT 2 ROOME

P.O. BOX 1460, BOONE, N.C. 28607

2012 STANDARD SPECIFICATIONS

Roadway Standard Drawings

The following roadway english standards as appear in "Roadway Standard Drawings"- Roadway Design Unit - N.C. Department of Transportation - Raleigh, N.C., dated January 2012 and the latest revision thereto are applicable to this project and by reference hereby are considered a part of these plans.

1604.01 Railroad Erosion Control Detail 1605.01 Temporary Silt Fence 1606.01 Special Sediment Control Fence 1607.01 Gravel Construction Entrance

| 1607-01 | Gravel Construction Entrance |
1622-01 | Temporary Berms and Slope Drains |
1630-01 | Riser Basin |
1630-02 | Silt Basin | Type B |
1630-03 | Temporary Silt Ditch |
1630-04 | Selling Basin |
1630-05 | Temporary Diversion |
1630-05 | Temporary Diversion |
1630-06 | Special Stilling Basin |
1631-01 | Matting Installation |

1632.01 Rock Inlet Sediment Trap Type A 1632.02 Rock Inlet Sediment Trap Type B 1632.03 Rock Inlet Sediment Trap Type C 1633.01 Temporary Rock Silt Check Type A 1633.02 Temporary Rock Silt Check Type A 1634.02 Temporary Rock Sediment Dam Type A 1634.02 Temporary Rock Sediment Dam Type A 1634.02 Temporary Rock Sediment Dam Type B 1635.01 Rock Type Inlet Sediment Trap Type A 1635.02 Rock Type Inlet Sediment Trap Type B 1645.01 Temporary Stream Crossing

# EROSION CONTROL & PIPE INSTALLATION SCHEDULE TROUT BUFFER ZONE SEQUENCE GENERAL E&SC NOTES GROUND STABILIZATION CHART

Erosion Control Schedule and Notes

- 1. Generally, the order of installation of the erosion control measures will be as follows:
  - A. Temporary silt basins shall be installed before clearing and grubbing begins.
  - B. Silt fences and temporary silt ditches shall be installed after clearing and before grading.
  - C. Temporary stone ditch checks with PAM or wattles with PAM shall be installed in all disturbed areas as soon as the disturbance begins.
  - D. Final stone ditch checks or wattles shall be installed as soon as ditch line is established.
  - E. Pipe outlet and inlet protection will be done as soon as the pipe is installed.
  - F. Other permanent erosion control measures are to be implemented as soon as practical.
- 2. Temporary rock silt checks, type B will be spaced by percent grade as shown in the erosion control plan.
- 3. No. 5 stone, or equivalent, will be used in conjunction with the temporary rock silt checks in locations where water is leaving the project or entering a pipe.
- 4. All devices are to be cleaned out when half full.
- 5. Establish permanent vegetation per ground stabilization chart.

#### Notes:

For silt basin size see the attached erosion control plans.

PAM is to be placed on all Type A checks and wattles in the erosion control chain except for the final device in HWQ and Trout projects.

Wet Pipe Installation Schedule and Notes

- 1. Prior to installing any E&SC measures identify permit conditions and impact area limits.
- 2. Install erosion control devices.
- 3. Manage the water course. The pipe must be placed in the dry. Install dewatering measures.
- 4. Remove material and existing pipe while limiting, material and sediment from entering stream and escaping the project.
- 5. Excavation of stream channel shall not exceed 10' on either side of new pipe or culvert unless indicated on permit.
- 6. Per permit conditions for Corps of Engineers and the Wildlife Resources Commission, all pipes in streams 48"or greater must be buried 12" below streambed elevation. Pipes less than 48"must be buried with 20% of the diameter below streambed elevation.
- 7. Place the new pipe and compact backfill.
- 8. Install slope protection on the outlet and inlet ends of the pipe. Also complete installation of erosion control measures and perform maintenance as needed on existing measures.
- 9. Establish permanent vegetation per ground stabilization chart.
- 10. More information on wet pipe installation can be found in the BMP manual section 4.2 "Pipe & Culvert installation"

General Erosion Control Sequence & Notes for NC DOT Projects in Trout Buffer Zones

- 1. Prior to installing any E&SC measures identify permit conditions and impact area limits. Review trout buffer variance approval conditions for any special provisions.
- 2. All materials should be on the hand before work is commenced.
- 3. Install EC devices
- 4. Work within the buffer zone should be sequenced to minimize the length of time that disturbed areas are exposed. Stream bank stabilization, which includes the area from the edge of water to the top of bank, should be phased so that each day's work is a completed work, including provision of adequate ground cover.
- 5. Graded slopes and fills within the trout buffer zone will within 7 calendar days of completion of any phase of grading be planted or otherwise provided with temporary or permanent ground cover, devices, or structures sufficient to restrain erosion.
- Graded slopes and fills within the trout buffer zone (excluding road shoulders) shall be protected with rolled erosion control product, bonded fiber matrix, or flexible growth medium after seeding.

#### Notes:

Silt fence backed by woven wire, with a post spacing of 6 feet, shall be used instead of standard silt fence in trout buffer zone. Special sediment control fence shall be used in areas where bedrock is encountered which prohibits the proper anchoring of fabric, and in low points of the silt fence in 3-foot sections to allow for concentrated flows.

The disturbed areas within the stream buffer shall be restored to native vegetation characteristic of an undisturbed buffer to the extent practical upon completion of construction.


Flyrock protection such as blast mats should be provided for blasting in close proximity to streams.

PAM is to be placed on all Type A checks and wattles in the erosion control chain except for the final device in HWQ and Trout projects.


#### GROUND STABILIZATION CHART

Site Area Description	Stabilization Time Frame	Stabilization Time Frame Exceptions
Perimeter dikes, swales, ditches and slopes	7 days	None
High Quality Water Zones	7 days	None
Slopes steeper than 3:1	7 days	If slopes are 10 ft. or less in length and are not steeper than 2:1, 14 days are allowed
Slopes 3:1 or flatter	14 days	7 days for slopes greater than 50' in lenght
All other areas flatter than 4:1	14 days	None (except for perimeters and HQW zones)

PROJECT REFERENCE NO	).	SHEET NO.
CA-1562		2
ROADWAY DESIGN ENGINEER	P	AVEMENT DESIGN ENGINEER



# 16'-18' EXISTING TYPICAL SECTION SR 1562



GRAPHIC SCALE

TYPICAL SECTION NO. 1

# STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS

PROJECT NO.	SHEET NO.
SR 1515A	3-C

## LIST OF PIPES, ENDWALLS, ETC. (FOR PIPES 48" & UNDER)

	N.													NEW PIPES EXISTING PIPES									
	Z,		BITUMINOUS COATED C.S. PIPE TYPE B (UNLESS NOTED OTHERWISE)									OR STD.	DJ. FRAME AND GRATE STD. 840.16	J.B. STD. 840.31 OR 840.32									
SIZE	LOCATION (LT, RT, OR CL)'	12"	15"	18"	24"	30"	36"	42"	48"		12"	15"	18"	24"	30"	36"	42"	48"	PIPE REMOVAL	D.I. STD. 840.14 OR STD. 840.15	AME AND	D. 840.31	
TYPE	SC.																		띪	I. ST	1. F.R.	3. ST	
STATION																			ᆸ	⊡ %	⊡ %	7	REMARKS
01+60	LT		20'									20'							20'				EX 15" RCP DRV PIPE
01+75	CL			50'									40'						40'				EX 18"CMP CROSSLINE
01+76	RT		20'									20'							20'				EX 15" CMP DRV PIPE
02+60	LT		35'									35'							35'				EX 15" CMP DRV PIPE
05+16	LT		20'									20'							20'				EX 15" PLASTIC DRV PIPE
07+22	RT			60'									60'						60'				EX 18" CMP DRV PIPE
09+45	CL			50'									40'						40'				EX 18"CMP CROSSLINE
10+15	LT		25'									25'							25'				EX 15' CMP DRV PIPE
10+80	LT		40'									40'							40'				EX 15' CMP DRV PIPE
11+55	RT		60'									60'							60'				EX 15"CMP DRV PIPE
																			0'				
																			0' 0'				
																			0'				
																			0' 0'				
																			0'				
																			0'				
																			0'				
																			0'				
																			0' 0'				
																			0'				
																			0'				
																			0'				
																			0'				
																			0' 0'				
					1	1		1											0'				
																			0'				
								1											0'	1	1		
								<del>                                     </del>											0'				
																			0'				
	1							1			-								0'	<b> </b>	1		<del>                                     </del>
								<del>                                     </del>											0'				
																			0'				
ET TOTALS		0	220	160	0	0	0	0	0	380	0	220	140	0	0	0	0	0	360			l	

