


# HIGHWAY LANDSCAPE DEVELOPMENT PROJECT



T.I.P. #	STATE PROJECT W.B.S. #	SHEET #	SHEET # TOTAL
E-2973K	3711.3.17	L1.0	4
FED. PROJ. #	DESCRIPTION		DIVISION
<ul> <li>ENHANCEMENT</li> </ul>		11	

CONVENTIONAL SYMBOLS



## CALDWELL COUNTY

LOCATION: S.R. 1160 (MT. HERMAN RD)

TYPE OF WORK: LANDSCAPE ENHANCEMENT



# Prop. Right of Way Line Marker (By Others) Prop Right of Way Line Marker (By Contract) Exist. Control of Access Line. Prop. Control of Access Line. Property Line Easement Line. Slope Stake Line. Exist. Fence. Prop. Woven Wire Fence. Prop. Chain Link Fence. Exist. Road Prop. Road Guardrail Survey Line.

City or Town Line\_\_\_\_\_ Exist. Right of Way Line Marker\_\_

County Line\_\_\_

Prop. Road
Guardrail
Survey Line
Denotes Line Equality
Bridge
Culvert
Railroad
Woods

Exist. Telephone Pole
Prop. Telephone Pole
Tower Pole and Line
Exist. Power Pole
Prop. Power Pole
Sanitary Sewer Line.

Gas Line\_\_\_\_\_\_ can
Picnic Shelter\_\_\_\_\_\_

Regeneration\_\_\_\_\_\_

Reforestation\_\_\_\_\_\_



### Summary of Quantities

DES	SEC	QTY	UNIT	KEY	BOTANICAL NAME	COMMAN NAME	SIZE	FURNISH	A.S.N.S.	REMARKS
L	1670	74	EA	HH	Hemerocallis 'Happy Returns'	Happy Returns Daylily		#1 cont	12.2.3	As Shown
L	1670	33	EA	IC	Ilex crenata 'Soft Touch'	Soft Touch Holly	18-24"	#3 cont	4.2.2	As Shown
L	1670	1	EA	LI	Lagerstroemia indica "Natchez'	Natchez Crape Myrtle	8-10'	B&B	1.3	3-4 stem
L	1670	42	EA	MC	Muhlenbergia capillaris	Pink Muhley Grass	18-24"	#3 cont	12.4	As Shown
L	1670	21	EA	ND	Nandina domestica 'Harbour Dwarf'	Harbour Dwarf Nandina	18-24"	#3 cont	4.2.2	As Shown
L	1670	21	EA	RK	Rosa x 'Double Knock Out'	Red Double Knock Out Rose	18-24"	#3 cont	5.2	As Shown
L	1670	13	CY		Mulch for Planting					
L	1670		M/G		Water for Planting					
L	1670	300	SY		Pre emergence treatment					
L	1670	300	SY		Post emergence treatment					
L	1670	146	SY		Landscape Filter Fabric					
L	1670	93	LF		Commercial Grade Steel Landscape					
					Metal Edging, 4" wide, 12 ga.					
					Brown powder coat finish					
L	1670	48	CY		Weed Free Topsoil					
L	1670	6	TONS		Washed River Rock					
L	1670	3			Boulders (2-5 tons each)					
L	1670	70	LF		Block Wall					
L	1670	1	CY		Crushed Stone 1" depth					



L 1.0  $\dots$  TITLE, DESCRIPTION, LOCATION

L 2.0 ... PLANTING DETAILS L 3.0 ... WALL LAYOUT PLAN

Water Line\_\_\_\_\_

L 4.0 ... PLANTING PLAN

PREPARED BY: BM date: 1/2014

REVISIONS

DATE	DESCRIPTION



# STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

LOCATION: Mt. Herman Rd

TYPE of WORK: Landscape Planting

County: Caldwell County

2004 American Standard for Nursery Stock

2012 NCDOT STANDARD SPECIFICATIONS

PREPARED IN THE OFFICE OF:

NCDOT- ROADSIDE ENVIRONMENTAL UNIT LANDSCAPE DESIGN & DEVELOPMENT SECTION 1557 MAIL SERVICE CENTER RALEIGH NC 27699 919-707-2920

06–FEB–2014 09:36 R:\U3437\Landscape\U-3437 Ladscap Plr \$\$\$\$USERNAME\$\$\$\$



Development Section

යු

Landscape Design


Roundabout RdHerman


BM AS NOTED

1 / 31 /2014

E-2973K

4" MULCH -NOTE: PLANTS MAY BE INSTALLED BEFORE OR AFTER MULCHING OPERATION FINISH GRADE BEFORE PLANTING, SCARIFY SOIL TO A MIN. DEPTH OF 6" OR 2" DEEPER THAN CONTAINER SIZE, WHICHEVER IS GROUND COVER/BEDDING PLANT DETAIL





# GUARDRAIL MULCHING DETAIL ...

4' MIN. TO 8' MAX. NATURAL WEATHERED STONE TO BE PROVIDED BY NCDOT. STONE TO BE BURIED 1/3 IN GROUND AND 2/3 EXPOSED

(LEVEL TO SLOPING)

**TYPICAL** 

SCALE: NTS

VARIABLE GRADE

**BOULDER PLACEMENT DETAIL** 

FLEXIBLE TIE MATERIAL RUBBER HOSE APPROVED BY ENGINEER. SECTION 14 GAUGE STEEL WIRE STRANDS TWISTED AROUND EACH OTHER UNTIL WIRES ARE TAUT. 1 3/4" x 1 3/4" WOODEN STAKE. 18-24" LG. STAKE TO BE 4-6" ABOVE GRADE 1 3/4" x 1 3/4" WOODEN STAKE 

(TREES 6'-10')

PLAN VIEW

**GUYING DETAIL** (TREES 10' OR LARGER)

(SLOPING GROUND)

SECTION OF RUBBER HOSE OR

MANUFACTURED TIES BETWEEN

TREE OR SHRUB PLANTING DETAIL SIZE OR CONTAINER DIAMETER. SHRUB BED PLANTING DETAIL EXTEND MULCH TO FRONT EDGE OF THE GUARDRAIL OR TO PAVEMENT EDGE OF TRAVELWAY.

USE AS DIRECTED BY FIELD ENGINEER

**ROADWAY** 

DITCH LINING DETAIL

Planting Details

WIRES AND TREE BARK 14 GUAGE STEEL WIRE \*EXACT LENGTH WITHIN INDICATED RANGE TO BE DETERMINED BY Guy tie detail ENGINEER IN FIELD RUBBER HOSE SECTION AND 14 GAUGE WIRE OR

PRUNE DAMAGED BRANCHES -

INSTALL TREE OR SHRUB

SO THAT 1/8 OF ROOT

WATER RETENTION RING -

COMPACT BACKFILL

PLANT HOLE WIDTH (X) TO BE TWICE

THE ROOT BALL SIZE OR CONTAINER

FINISH GRADE

BALL IS ABOVE GRADE

PLAN VIEW

TREE OR SHRUB PLANTING DETAIL

(LEVEL GROUND)

STAKING DETAIL

USE AS DIRECTED BY FIELD ENGINEER

DO NOT REMOVE LEADER

MULCH -

USE AS DIRECTED BY FIELD ENGINEER

MULCH

DIG TREE AND REPLANT TO UPRIGHT POSITION.

**ROADWAY** 

DO NOT PLACE MULCH WITHIN 2" -

MULCH DETAIL

SCHEDULE FOR PLANT HOLE SIZE:

PLANT HOLE WIDTH (X) TO BE TWICE THE ROOT BALL SIZE OR CONTAINER

SEE STANDARD SPECIFICATIONS FOR

APPLY FERTILIZER AT PLANTING TIME

IN THE FORM OF A SLOW RELEASE

PELLET OR TABLET. APPLY AT RATE

RECOMMENDED BY MANUFACTURER. BOTH RATE AND FORMULATION MUST BE APPROVED BY FIELD ENGINEER PRIOR

REMOVE WIRE BASKET AND FOLD BURLAP

BACK FROM TOP OF ROOT BALL BEFORE

ALL PRUNING TO FOLLOW STANDARD ARBORICULTURAL PRACTICES AS

SPECIFIED BY INTERNATIONAL SOCIETY

DO NOT ATTEMPT TO STRAIGHTEN A TREE

THAT HAS BEEN PLANTED AT AN ANGLE

WITH THE USE OF STAKING OR GUYING.

PLANT BED FUMIGATION AND HERBICIDAL

OF TRUNK OR STEM

NOTES:

DIAMETER.

TREATMENT.


TO APPLICATION.

OF ARBORICULTURE.

BACKFILLING IS COMPLETE.

MIN. 12" DEEP CLASS "A" STONE ON FILTER FABRIC LINER IN DITCH. PLACE STONE FLUSH WITH DITCH GRADE FOR MAXINUM WATER FLOW.

CLASS "A" STONE





ncdot - Roadside environmental unit landscape design & Development


1557 mail service center raleigh nc 27699-1557 ph: 919-707-2935 fax: 919-715-2554 http://www.ncdot.org/doh/operations/dp\_chief\_eng/roadside/

Mt. Herman Rd RoundAbout Caldwell County



on:	prel. design date :	jan/2014	enhancement
escription:	checked by & date:		wall layout sheet
sheet d	final design date:	jan/2014	







ncdot - Roadside environmental unit landscape design & Development

http://www.ncdot.org/doh/operations/dp.chief.eng/roadside/

1557 mail service center raleigh nc 27699-1557 ph. 919-707-2935 fax: 919-715-2554

Mt. Herman Rd RoundAbout Caldwell County



theet description:	prel. design date :	jan/2014	enhancement		
	checked by & date:		landscape plan sheet		
	final design date :	jan/2014			



T.I.P. # E-2973K

WBS # 3711.3.17

FED I.D. #

sheet no: total sheet no:

TEB-2014 14:43 J3437\Landscape\U-3437 Ladscap \$USERNAME\$\$\$\$