

REFERENCE: SF-010291

PROJECT: 17BP.12.R.88

STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION  
DIVISION OF HIGHWAYS  
GEOTECHNICAL ENGINEERING UNIT

STRUCTURE  
SUBSURFACE INVESTIGATION

COUNTY ALEXANDER  
PROJECT DESCRIPTION BRIDGE 291 OVER DUCK  
CREEK ON SR 1348 (OLD NC 90)

CONTENTS

SHEET NO.	DESCRIPTION
1	TITLE SHEET
2	LEGEND
3	SITE PLAN
4-5	CROSS SECTIONS
6-15	BORE LOGS, CORE REPORTS, & CORE PHOTOGRAPHS

STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	SF-010291	1	15

CAUTION NOTICE

THE SUBSURFACE INFORMATION AND THE SUBSURFACE INVESTIGATION ON WHICH IT IS BASED WERE MADE FOR THE PURPOSE OF STUDY, PLANNING AND DESIGN, AND NOT FOR CONSTRUCTION OR PAY PURPOSES. THE VARIOUS FIELD BORING LOGS, ROCK CORES AND SOIL TEST DATA AVAILABLE MAY BE REVIEWED OR INSPECTED IN RALEIGH BY CONTACTING THE N. C. DEPARTMENT OF TRANSPORTATION, GEOTECHNICAL ENGINEERING UNIT AT (919) 707-6850. THE SUBSURFACE PLANS AND REPORTS, FIELD BORING LOGS, ROCK CORES AND SOIL TEST DATA ARE NOT PART OF THE CONTRACT.

GENERAL SOIL AND ROCK STRATA DESCRIPTIONS AND INDICATED BOUNDARIES ARE BASED ON A GEOTECHNICAL INTERPRETATION OF ALL AVAILABLE SUBSURFACE DATA AND MAY NOT NECESSARILY REFLECT THE ACTUAL SUBSURFACE CONDITIONS BETWEEN BORINGS OR BETWEEN SAMPLED STRATA WITHIN THE BOREHOLE. THE LABORATORY SAMPLE DATA AND THE IN SITU (IN-PLACE) TEST DATA CAN BE RELIED ON ONLY TO THE DEGREE OF RELIABILITY INHERENT IN THE STANDARD TEST METHOD. THE OBSERVED WATER LEVELS OR SOIL MOISTURE CONDITIONS INDICATED IN THE SUBSURFACE INVESTIGATIONS ARE AS RECORDED AT THE TIME OF THE INVESTIGATION. THESE WATER LEVELS OR SOIL MOISTURE CONDITIONS MAY VARY CONSIDERABLY WITH TIME ACCORDING TO CLIMATIC CONDITIONS INCLUDING TEMPERATURES, PRECIPITATION AND WIND, AS WELL AS OTHER NON-CLIMATIC FACTORS.

THE BIDDER OR CONTRACTOR IS CAUTIONED THAT DETAILS SHOWN ON THE SUBSURFACE PLANS ARE PRELIMINARY ONLY AND IN MANY CASES THE FINAL DESIGN DETAILS ARE DIFFERENT. FOR BIDDING AND CONSTRUCTION PURPOSES, REFER TO THE CONSTRUCTION PLANS AND DOCUMENTS FOR FINAL DESIGN INFORMATION ON THIS PROJECT. THE DEPARTMENT DOES NOT WARRANT OR GUARANTEE THE SUFFICIENCY OR ACCURACY OF THE INVESTIGATION MADE, NOR THE INTERPRETATIONS MADE, OR OPINION OF THE DEPARTMENT AS TO THE TYPE OF MATERIALS AND CONDITIONS TO BE ENCOUNTERED. THE BIDDER OR CONTRACTOR IS CAUTIONED TO MAKE SUCH INDEPENDENT SUBSURFACE INVESTIGATIONS AS HE DEEMS NECESSARY TO SATISFY HIMSELF AS TO CONDITIONS TO BE ENCOUNTERED ON THE PROJECT. THE CONTRACTOR SHALL HAVE NO CLAIM FOR ADDITIONAL COMPENSATION OR FOR AN EXTENSION OF TIME FOR ANY REASON RESULTING FROM THE ACTUAL CONDITIONS ENCOUNTERED AT THE SITE DIFFERING FROM THOSE INDICATED IN THE SUBSURFACE INFORMATION.

- NOTES:
- THE INFORMATION CONTAINED HEREIN IS NOT IMPLIED OR GUARANTEED BY THE N. C. DEPARTMENT OF TRANSPORTATION AS ACCURATE NOR IS IT CONSIDERED PART OF THE PLANS, SPECIFICATIONS OR CONTRACT FOR THE PROJECT.
  - BY HAVING REQUESTED THIS INFORMATION, THE CONTRACTOR SPECIFICALLY WAIVES ANY CLAIMS FOR INCREASED COMPENSATION OR EXTENSION OF TIME BASED ON DIFFERENCES BETWEEN THE CONDITIONS INDICATED HEREIN AND THE ACTUAL CONDITIONS AT THE PROJECT SITE.

PERSONNEL

J. Mize

A. Bozorgi

L. Gonzalez

D. Sutton

INVESTIGATED BY RK&K, LLP

DRAWN BY J. Mize

CHECKED BY M. Snyder

SUBMITTED BY RK&K, LLP

DATE December, 2017



SIGNATURE DATE



DOCUMENT NOT CONSIDERED FINAL  
UNLESS ALL SIGNATURES COMPLETED

**NORTH CAROLINA DEPARTMENT OF TRANSPORTATION  
DIVISION OF HIGHWAYS  
GEOTECHNICAL ENGINEERING UNIT  
SUBSURFACE INVESTIGATION  
SOIL AND ROCK LEGEND, TERMS, SYMBOLS, AND ABBREVIATIONS**

SOIL DESCRIPTION										GRADATION										ROCK DESCRIPTION										TERMS AND DEFINITIONS									
SOIL IS CONSIDERED UNCONSOLIDATED, SEMI-CONSOLIDATED, OR WEATHERED EARTH MATERIALS THAT CAN BE PENETRATED WITH A CONTINUOUS FLIGHT POWER AUGER AND YIELD LESS THAN 100 BLOWS PER FOOT ACCORDING TO THE STANDARD PENETRATION TEST (AASHTO T 206, ASTM D1586). SOIL CLASSIFICATION IS BASED ON THE AASHTO SYSTEM. BASIC DESCRIPTIONS GENERALLY INCLUDE THE FOLLOWING: CONSISTENCY, COLOR, TEXTURE, MOISTURE, AASHTO CLASSIFICATION, AND OTHER PERTINENT FACTORS SUCH AS MINERALOGICAL COMPOSITION, ANGULARITY, STRUCTURE, PLASTICITY, ETC. FOR EXAMPLE, VERY STIFF, GRAY, SILTY CLAY, MOIST WITH INTERBEDDED FINE SAND LAYERS, HIGHLY PLASTIC, A-7-6										WELL GRADED - INDICATES A GOOD REPRESENTATION OF PARTICLE SIZES FROM FINE TO COARSE. UNIFORMLY GRADED - INDICATES THAT SOIL PARTICLES ARE ALL APPROXIMATELY THE SAME SIZE. GAP-GRADED - INDICATES A MIXTURE OF UNIFORM PARTICLE SIZES OF TWO OR MORE SIZES.										HARD ROCK IS NON-COASTAL PLAIN MATERIAL THAT WOULD YIELD SPT REFUSAL IF TESTED. AN INFERRED ROCK LINE INDICATES THE LEVEL AT WHICH NON-COASTAL PLAIN MATERIAL WOULD YIELD SPT REFUSAL. SPT REFUSAL IS PENETRATION BY A SPLIT SPOON SAMPLER EQUAL TO OR LESS THAN 0.1 FOOT PER 60 BLOWS IN NON-COASTAL PLAIN MATERIAL. THE TRANSITION BETWEEN SOIL AND ROCK IS OFTEN REPRESENTED BY A ZONE OF WEATHERED ROCK. ROCK MATERIALS ARE TYPICALLY DIVIDED AS FOLLOWS: WEATHERED ROCK (WR) CRYSTALLINE ROCK (ICR) NON-CRYSTALLINE ROCK (INCR) COASTAL PLAIN SEDIMENTARY ROCK (CP)										ALLUVIUM (ALLUV.) - SOILS THAT HAVE BEEN TRANSPORTED BY WATER. AQUIFER - A WATER BEARING FORMATION OR STRATA. ARENACEOUS - APPLIED TO ROCKS THAT HAVE BEEN DERIVED FROM SAND OR THAT CONTAIN SAND. ARGILLACEOUS - APPLIED TO ALL ROCKS OR SUBSTANCES COMPOSED OF CLAY MINERALS, OR HAVING A NOTABLE PROPORTION OF CLAY IN THEIR COMPOSITION, SUCH AS SHALE, SLATE, ETC. ARTESIAN - GROUND WATER THAT IS UNDER SUFFICIENT PRESSURE TO RISE ABOVE THE LEVEL AT WHICH IT IS ENCOUNTERED, BUT WHICH DOES NOT NECESSARILY RISE TO OR ABOVE THE GROUND SURFACE. CALCAREOUS (CALC.) - SOILS THAT CONTAIN APPRECIABLE AMOUNTS OF CALCIUM CARBONATE. COLLUVIUM - ROCK FRAGMENTS MIXED WITH SOIL DEPOSITED BY GRAVITY ON SLOPE OR AT BOTTOM OF SLOPE. CORE RECOVERY (REC.) - TOTAL LENGTH OF ALL MATERIAL RECOVERED IN THE CORE BARREL DIVIDED BY TOTAL LENGTH OF CORE RUN AND EXPRESSED AS A PERCENTAGE. DIKE - A TABULAR BODY OF IGNEOUS ROCK THAT CUTS ACROSS THE STRUCTURE OF ADJACENT ROCKS OR CUTS MASSIVE ROCK. DIP - THE ANGLE AT WHICH A STRATUM OR ANY PLANAR FEATURE IS INCLINED FROM THE HORIZONTAL. DIP DIRECTION (DIP AZIMUTH) - THE DIRECTION OR BEARING OF THE HORIZONTAL TRACE OF THE LINE OF DIP, MEASURED CLOCKWISE FROM NORTH. FAULT - A FRACTURE OR FRACTURE ZONE ALONG WHICH THERE HAS BEEN DISPLACEMENT OF THE SIDES RELATIVE TO ONE ANOTHER PARALLEL TO THE FRACTURE. FISSILE - A PROPERTY OF SPLITTING ALONG CLOSELY SPACED PARALLEL PLANES. FLOAT - ROCK FRAGMENTS ON SURFACE NEAR THEIR ORIGINAL POSITION AND DISLODGED FROM PARENT MATERIAL. FLOOD PLAIN (FP) - LAND BORDERING A STREAM, BUILT OF SEDIMENTS DEPOSITED BY THE STREAM. FORMATION (FM) - A MAPPABLE GEOLOGIC UNIT THAT CAN BE RECOGNIZED AND TRACED IN THE FIELD. JOINT - FRACTURE IN ROCK ALONG WHICH NO APPRECIABLE MOVEMENT HAS OCCURRED. LEDGE - A SHELF-LIKE RIDGE OR PROJECTION OF ROCK WHOSE THICKNESS IS SMALL COMPARED TO ITS LATERAL EXTENT. LENS - A BODY OF SOIL OR ROCK THAT THINS OUT IN ONE OR MORE DIRECTIONS. MOTTLED (MOT.) - IRREGULARLY MARKED WITH SPOTS OF DIFFERENT COLORS. MOTTLING IN SOILS USUALLY INDICATES POOR AERATION AND LACK OF GOOD DRAINAGE. PERCHED WATER - WATER MAINTAINED ABOVE THE NORMAL GROUND WATER LEVEL BY THE PRESENCE OF AN INTERVENING IMPERVIOUS STRATUM. RESIDUAL (RES.) SOIL - SOIL FORMED IN PLACE BY THE WEATHERING OF ROCK. ROCK QUALITY DESIGNATION (RQD) - A MEASURE OF ROCK QUALITY DESCRIBED BY TOTAL LENGTH OF ROCK SEGMENTS EQUAL TO OR GREATER THAN 4 INCHES DIVIDED BY THE TOTAL LENGTH OF CORE RUN AND EXPRESSED AS A PERCENTAGE. SAPROLITE (SAP.) - RESIDUAL SOIL THAT RETAINS THE RELIC STRUCTURE OR FABRIC OF THE PARENT ROCK. SILL - AN INTRUSIVE BODY OF IGNEOUS ROCK OF APPROXIMATELY UNIFORM THICKNESS AND RELATIVELY THIN COMPARED WITH ITS LATERAL EXTENT, THAT HAS BEEN EMPLACED PARALLEL TO THE BEDDING OR SCHISTOSITY OF THE INTRUDED ROCKS. SLICKENSIDE - POLISHED AND STRIATED SURFACE THAT RESULTS FROM FRICTION ALONG A FAULT OR SLIP PLANE. STANDARD PENETRATION TEST (PENETRATION RESISTANCE) (SPT) - NUMBER OF BLOWS IN OR BPF OF A 140 LB. HAMMER FALLING 30 INCHES REQUIRED TO PRODUCE A PENETRATION OF 1 FOOT INTO SOIL WITH A 2 INCH OUTSIDE DIAMETER SPLIT SPOON SAMPLER. SPT REFUSAL IS PENETRATION EQUAL TO OR LESS THAN 0.1 FOOT PER 60 BLOWS. STRATA CORE RECOVERY (SRC.) - TOTAL LENGTH OF STRATA MATERIAL RECOVERED DIVIDED BY TOTAL LENGTH OF STRATUM AND EXPRESSED AS A PERCENTAGE. STRATA ROCK QUALITY DESIGNATION (SRQD) - A MEASURE OF ROCK QUALITY DESCRIBED BY TOTAL LENGTH OF ROCK SEGMENTS WITHIN A STRATUM EQUAL TO OR GREATER THAN 4 INCHES DIVIDED BY THE TOTAL LENGTH OF STRATA AND EXPRESSED AS A PERCENTAGE. TOPSOIL (TS.) - SURFACE SOILS USUALLY CONTAINING ORGANIC MATTER.									
SOIL LEGEND AND AASHTO CLASSIFICATION										MINERALOGICAL COMPOSITION										WEATHERING																			
GENERAL CLASS. GRANULAR MATERIALS (<= 35% PASSING #200) SILT-CLAY MATERIALS (> 35% PASSING #200) ORGANIC MATERIALS										MINERAL NAMES SUCH AS QUARTZ, FELDSPAR, MICA, TALC, KAOLIN, ETC. ARE USED IN DESCRIPTIONS WHEN THEY ARE CONSIDERED OF SIGNIFICANCE.										FINE TO COARSE GRAIN IGNEOUS AND METAMORPHIC ROCK THAT WOULD YIELD SPT REFUSAL IF TESTED. ROCK TYPE INCLUDES GRANITE, GNEISS, GABBRO, SCHIST, ETC. FINE TO COARSE GRAIN METAMORPHIC AND NON-COASTAL PLAIN SEDIMENTARY ROCK THAT WOULD YIELD SPT REFUSAL IF TESTED. ROCK TYPE INCLUDES PHYLLITE, SLATE, SANDSTONE, ETC. COASTAL PLAIN SEDIMENTS CEMENTED INTO ROCK, BUT MAY NOT YIELD SPT REFUSAL. ROCK TYPE INCLUDES LIMESTONE, SANDSTONE, CEMENTED SHELL BEDS, ETC.																			
GROUP CLASS. A-1-a A-1-b A-3 A-2-4 A-2-5 A-2-6 A-2-7 A-4 A-5 A-6 A-7 A-1, A-2 A-3 A-4, A-5 A-6, A-7										SLIGHTLY COMPRESSIBLE LL < 31 MODERATELY COMPRESSIBLE LL = 31 - 50 HIGHLY COMPRESSIBLE LL > 50										FRESH ROCK FRESH, CRYSTALS BRIGHT, FEW JOINTS MAY SHOW SLIGHT STAINING. ROCK RINGS UNDER HAMMER IF CRYSTALLINE. VERY SLIGHT (V SLI.) ROCK GENERALLY FRESH, JOINTS STAINED, SOME JOINTS MAY SHOW THIN CLAY COATINGS IF OPEN, CRYSTALS ON A BROKEN SPECIMEN FACE SHINE BRIGHTLY. ROCK RINGS UNDER HAMMER BLOWS IF OF A CRYSTALLINE NATURE. SLIGHT (SLI.) ROCK GENERALLY FRESH, JOINTS STAINED AND DISCOLORATION EXTENDS INTO ROCK UP TO 1 INCH. OPEN JOINTS MAY CONTAIN CLAY. IN GRANITOID ROCKS SOME OCCASIONAL FELDSPAR CRYSTALS ARE DULL AND DISCOLORED. CRYSTALLINE ROCKS RING UNDER HAMMER BLOWS. MODERATE (MOD.) SIGNIFICANT PORTIONS OF ROCK SHOW DISCOLORATION AND WEATHERING EFFECTS. IN GRANITOID ROCKS, MOST FELDSPARS ARE DULL AND DISCOLORED, SOME SHOW CLAY. ROCK HAS DULL SOUND UNDER HAMMER BLOWS AND SHOWS SIGNIFICANT LOSS OF STRENGTH AS COMPARED WITH FRESH ROCK. MODERATELY SEVERE (MOD. SEV.) ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED. IN GRANITOID ROCKS, ALL FELDSPARS DULL AND DISCOLORED AND A MAJORITY SHOW KAOLINIZATION. ROCK SHOWS SEVERE LOSS OF STRENGTH AND CAN BE EXCAVATED WITH A GEOLOGIST'S PICK. ROCK GIVES "CLUNK" SOUND WHEN STRUCK. SEVERE (SEV.) ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED. ROCK FABRIC CLEAR AND EVIDENT BUT REDUCED IN STRENGTH TO STRONG SOIL. IN GRANITOID ROCKS ALL FELDSPARS ARE KAOLINIZED TO SOME EXTENT. SOME FRAGMENTS OF STRONG ROCK USUALLY REMAIN. VERY SEVERE (V SEV.) ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED. ROCK FABRIC ELEMENTS ARE DISCERNIBLE BUT MASS IS EFFECTIVELY REDUCED TO SOIL STATUS, WITH ONLY FRAGMENTS OF STRONG ROCK REMAINING. SAPROLITE IS AN EXAMPLE OF ROCK WEATHERED TO A DEGREE THAT ONLY MINOR VESTIGES OF ORIGINAL ROCK FABRIC REMAIN. IF TESTED, WOULD YIELD SPT N VALUES < 100 BPF COMPLETE ROCK REDUCED TO SOIL. ROCK FABRIC NOT DISCERNIBLE, OR DISCERNIBLE ONLY IN SMALL AND SCATTERED CONCENTRATIONS. QUARTZ MAY BE PRESENT AS DIKES OR STRINGERS. SAPROLITE IS ALSO AN EXAMPLE.										SOILS WITH LITTLE OR MODERATE AMOUNTS OF ORGANIC MATTER HIGHLY ORGANIC SOILS									
SYMBOL										PERCENTAGE OF MATERIAL																													
% PASSING #10 #40 #200										ORGANIC MATERIAL GRANULAR SOILS SILT - CLAY SOILS OTHER MATERIAL										TRACE OF ORGANIC MATTER 2 - 3% 3 - 5% TRACE 1 - 10% LITTLE ORGANIC MATTER 3 - 5% 5 - 12% LITTLE 10 - 20% MODERATELY ORGANIC 5 - 10% 12 - 20% SOME 20 - 35% HIGHLY ORGANIC > 10% > 20% HIGHLY 35% AND ABOVE																			
MATERIAL PASSING #40 LL PI										GROUND WATER																													
GROUP INDEX										WATER LEVEL IN BORE HOLE IMMEDIATELY AFTER DRILLING																													
USUAL TYPES OF MAJOR MATERIALS										STATIC WATER LEVEL AFTER 24 HOURS																													
GEN. RATING AS SUBGRADE										PERCHED WATER, SATURATED ZONE, OR WATER BEARING STRATA																													
EXCELLENT TO GOOD										FAIR TO POOR																													
FAIR TO POOR										POOR																													
UNSATURABLE										SPRING OR SEEP																													
PI OF A-7-5 SUBGROUP IS <= LL - 30 ; PI OF A-7-6 SUBGROUP IS > LL - 30										MISCELLANEOUS SYMBOLS																													
CONSISTENCY OR DENSENESS										ROADWAY EMBANKMENT (RE) WITH SOIL DESCRIPTION										DIP & DIP DIRECTION OF ROCK STRUCTURES																			
PRIMARY SOIL TYPE										SOIL SYMBOL										SLOPE INDICATOR INSTALLATION																			
COMPACTNESS OR CONSISTENCY										ARTIFICIAL FILL (AF) OTHER THAN ROADWAY EMBANKMENT										CONE PENETROMETER TEST																			
RANGE OF STANDARD PENETRATION RESISTANCE (N-VALUE)										INFERRED SOIL BOUNDARY										SOUNDING ROD																			
RANGE OF UNCONFINED COMPRESSIVE STRENGTH (TONS/FT <sup>2</sup> )										INFERRED ROCK LINE										TEST BORING WITH CORE																			
VERY LOOSE										ALLUVIAL SOIL BOUNDARY										SPT N-VALUE																			
MEDIUM DENSE																																							
DENSE																																							
VERY DENSE																																							
VERY SOFT																																							
SOFT																																							
MEDIUM STIFF																																							
STIFF																																							
VERY STIFF																																							
HARD																																							
> 30																																							
TEXTURE OR GRAIN SIZE										RECOMMENDATION SYMBOLS																													
U.S. STD. SIEVE SIZE OPENING (MM)										UNDERCUT										UNCLASSIFIED EXCAVATION - UNSUITABLE WASTE										UNCLASSIFIED EXCAVATION - ACCEPTABLE, BUT NOT TO BE USED IN THE TOP 3 FEET OF EMBANKMENT OR BACKFILL									
BOULDER (BLDR.)										SHALLOW UNDERCUT										UNCLASSIFIED EXCAVATION - ACCEPTABLE DEGRADABLE ROCK																			
GRAIN SIZE										ABBREVIATIONS																													
MM 305 75 2.0 0.25 0.05 0.005										AR - AUGER REFUSAL										MED. - MEDIUM										VST - VANE SHEAR TEST									
IN. 12 3										BT - BORING TERMINATED										MICA - MICACEOUS										WEA. - WEATHERED									
										CL. - CLAY										MOD. - MODERATELY										UNIT WEIGHT									
										CPT - CONE PENETRATION TEST										NP - NON PLASTIC										DRY UNIT WEIGHT									
										CSE. - COARSE										ORG. - ORGANIC										SAMPLE ABBREVIATIONS									
										DMT - DILATOMETER TEST										PMT - PRESSUREMETER TEST										S - BULK									
										DPT - DYNAMIC PENETRATION TEST										SAP. - SAPROLITIC										SS - SPLIT SPOON									
										e - VOID RATIO										SD. - SAND, SANDY										ST - SHELVE TUBE									
										F - FINE										SL. - SILT, SILTY										RS - ROCK									
										FOSS. - FOSSILIFEROUS										SLI. - SLIGHTLY										RT - RECOMPACTED TRIAXIAL									
										FRAC. - FRACTURED, FRACTURES										TCR - TRICONE REFUSAL										CBR - CALIFORNIA BEARING RATIO									
										FRAGS. - FRAGMENTS										w - MOISTURE CONTENT																			
										HL. - HIGHLY										V - VERY																			
SOIL MOISTURE - CORRELATION OF TERMS										EQUIPMENT USED ON SUBJECT PROJECT																													
SOIL MOISTURE SCALE (ATTERBERG LIMITS)										DRILL UNITS:										ADVANCING TOOLS:										HAMMER TYPE:									
FIELD MOISTURE DESCRIPTION										<input type="checkbox"/> CME-45C										<input type="checkbox"/> CLAY BITS										<input checked="" type="checkbox"/> AUTOMATIC <input type="checkbox"/> MANUAL									
GUIDE FOR FIELD MOISTURE DESCRIPTION										<input type="checkbox"/> CME-55										<input type="checkbox"/> 6" CONTINUOUS FLIGHT AUGER										CORE SIZE:									
- SATURATED - (SAT.)										<input type="checkbox"/> CME-550										<input type="checkbox"/> 8" HOLLOW AUGERS										<input type="checkbox"/> -B <input type="checkbox"/> -H									
USUALLY LIQUID; VERY WET, USUALLY FROM BELOW THE GROUND WATER TABLE										<input type="checkbox"/> VANE SHEAR TEST										<input type="checkbox"/> HARD FACED FINGER BITS										<input checked="" type="checkbox"/> -N Q									
- WET - (W)										<input type="checkbox"/> PORTABLE HOIST										<input type="checkbox"/> TUNG.-CARBIDE INSERTS										HAND TOOLS:									
SEMISOLID; REQUIRES DRYING TO ATTAIN OPTIMUM MOISTURE										<input type="checkbox"/>										<input checked="" type="checkbox"/> CASING <input checked="" type="checkbox"/> W/ ADVANCER										<input type="checkbox"/> POST HOLE DIGGER									
SOLID; AT OR NEAR OPTIMUM MOISTURE										<input type="checkbox"/>										<input type="checkbox"/> TRICONE *STEEL TEETH										<input type="checkbox"/> HAND AUGER									
- MOIST - (M)										<input type="checkbox"/>										<input type="checkbox"/> TRICONE *TUNG.-CARB.										<input type="checkbox"/> SOUNDING ROD									
REQUIRES ADDITIONAL WATER TO ATTAIN OPTIMUM MOISTURE										<input type="checkbox"/>										<input type="checkbox"/> CORE BIT										<input type="checkbox"/> VANE SHEAR TEST									
- DRY - (D)										<input type="checkbox"/>										<input checked="" type="checkbox"/> 3/4" H.S. AUGER																			
PLASTICITY										INDURATION																													
NON PLASTIC										FOR SEDIMENTARY ROCKS, INDURATION IS THE HARDENING OF MATERIAL BY CEMENTING, HEAT, PRESSURE, ETC.																													
SLIGHTLY PLASTIC										FRIABLE										RUBBING WITH FINGER FREES NUMEROUS GRAINS; GENTLE BLOW BY HAMMER DISINTEGRATES SAMPLE.																			
MODERATELY PLASTIC										MODERATELY INDURATED										GRAINS CAN BE SEPARATED FROM SAMPLE WITH STEEL PROBE; BREAKS EASILY WHEN HIT WITH HAMMER.																			
HIGHLY PLASTIC										INDURATED										GRAINS ARE DIFFICULT TO SEPARATE WITH STEEL PROBE; DIFFICULT TO BREAK WITH HAMMER.																			
PLASTICITY INDEX (PI)										EXTREMELY INDURATED										SHARP HAMMER BLOWS REQUIRED TO BREAK SAMPLE; SAMPLE BREAKS ACROSS GRAINS.																			
DRY STRENGTH																																							
VERY LOW																																							
SLIGHT																																							
MEDIUM																																							
HIGH																																							
COLOR																																							
DESCRIPTIONS MAY INCLUDE COLOR OR COLOR COMBINATIONS (TAN, RED, YELLOW-BROWN, BLUE-GRAY). MODIFIERS SUCH AS LIGHT, DARK, STREAKED, ETC. ARE USED TO DESCRIBE APPEARANCE.																																							
																														BENCH MARK: Monument B4980-2; N 800036.87, E 1316453.34									
																														ELEVATION: 1145.83 FEET									
																														NOTES:									
																														F.I.A.D. - FILLED IMMEDIATELY AFTER DRILLING									


PROJECT REFERENCE NO.	SHEET NO.
SF-010291	3
<b>SITE PLAN</b>	


Skew = 60°



**BEGIN CONSTRUCTION**  
-L- STA. 14 + 30.00

**END CONSTRUCTION**  
-L- STA. 18 + 40.00





# GEOTECHNICAL BORING REPORT

## BORE LOG


WBS 17BP.12.R.88		TIP SF-010291		COUNTY ALEXANDER		GEOLOGIST J Mize									
SITE DESCRIPTION Bridge 291 over Duck Creek on SR 1348 (Old NC 90)							GROUND WTR (ft)								
BORING NO. EB1-A		STATION 15+67		OFFSET 3 ft LT		ALIGNMENT -L-									
COLLAR ELEV. 1,146.0 ft		TOTAL DEPTH 25.4 ft		NORTHING 800,096		EASTING 1,316,556									
DRILL RIG/HAMMER EFF./DATE SUM3123 CME-550X 93% 11/06/2015				DRILL METHOD H.S. Augers		HAMMER TYPE Automatic									
DRILLER L Gonzalez		START DATE 12/07/17		COMP. DATE 12/07/17		SURFACE WATER DEPTH N/A									
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100					
1150															
1145	1,144.6	1.4	4	4	4								M	1,146.0 GROUND SURFACE 0.0 1,144.9 Asphalt 1.1	
1140	1,142.2	3.8	1	1	2								M	1,142.5 ROADWAY EMBANKMENT 3.5 Brown, loose, clayey fine to coarse SAND (A-2-6) Red, brown, soft, coarse sandy SILT (A-5)	
1135	1,137.2	8.8	1	2	2								M		
1130	1,132.2	13.8	1	2	1								M	1,133.0 ALLUVIAL 13.0 Gray, brown, very loose, silty SAND (A-2-4), trace mica	
1125	1,127.2	18.8	100/0.2											1,128.0 WEATHERED ROCK 18.0 METAMORPHOSED GRANITE	
	1,125.6	20.4	60/0.0											1,125.6 CRYSTALLINE ROCK 20.4 METAMORPHOSED GRANITE	
														1,120.6 Boring Terminated at Elevation 1,120.6 ft in Crystalline Rock: METAMORPHOSED GRANITE 25.4	

WBS 17BP.12.R.88		TIP SF-010291		COUNTY ALEXANDER		GEOLOGIST J Mize									
SITE DESCRIPTION Bridge 291 over Duck Creek on SR 1348 (Old NC 90)							GROUND WTR (ft)								
BORING NO. EB1-B		STATION 15+60		OFFSET 3 ft RT		ALIGNMENT -L-									
COLLAR ELEV. 1,145.9 ft		TOTAL DEPTH 19.0 ft		NORTHING 800,087		EASTING 1,316,552									
DRILL RIG/HAMMER EFF./DATE SUM3123 CME-550X 93% 11/06/2015				DRILL METHOD H.S. Augers		HAMMER TYPE Automatic									
DRILLER L Gonzalez		START DATE 12/07/17		COMP. DATE 12/07/17		SURFACE WATER DEPTH N/A									
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100					
1150															
1145	1,144.8	1.1	4	3	2								M	1,145.9 GROUND SURFACE 0.0 1,144.8 Asphalt 1.1	
1140	1,141.9	4.0	WOH	WOH	WOH								M	1,142.4 ROADWAY EMBANKMENT 3.5 Brown, orange, loose, silty fine to coarse SAND (A-2-4) Red, very soft to soft, coarse sandy moderate plasticity SILT (A-5)	
1135	1,136.9	9.0	1	1	2								M		
1130	1,131.9	14.0	1	1	3								M	1,132.9 ALLUVIAL 13.0 Gray, brown, loose, silty SAND (A-2-4), little mica	
	1,127.4	18.5												1,127.4 WEATHERED ROCK 18.5 METAMORPHOSED GRANITE	
	1,126.9	19.0	60/0.0											1,126.9 Boring Terminated with Standard Penetration Test Refusal at Elevation 1,126.9 ft on Crystalline Rock: METAMORPHOSED GRANITE 19.0	

NCDOT BORE DOUBLE 01\_GEO\_BRDG0291.GPJ NC\_DOT.GDT 1/2/18

# GEOTECHNICAL BORING REPORT

## CORE LOG

WBS 17BP.12.R.88		TIP SF-010291		COUNTY ALEXANDER		GEOLOGIST J Mize					
SITE DESCRIPTION Bridge 291 over Duck Creek on SR 1348 (Old NC 90)							GROUND WTR (ft)				
BORING NO. EB1-A		STATION 15+67		OFFSET 3 ft LT		ALIGNMENT -L-					
COLLAR ELEV. 1,146.0 ft		TOTAL DEPTH 25.4 ft		NORTHING 800,096		EASTING 1,316,556					
DRILL RIG/HAMMER EFF./DATE SUM3123 CME-550X 93% 11/06/2015				DRILL METHOD H.S. Augers		HAMMER TYPE Automatic					
DRILLER L Gonzalez		START DATE 12/07/17		COMP. DATE 12/07/17		SURFACE WATER DEPTH N/A					
CORE SIZE NQ		TOTAL RUN 5.0 ft									
ELEV (ft)	RUN ELEV (ft)	DEPTH (ft)	RUN (ft)	DRILL RATE (Min/ft)	RUN		STRATA		LOG	DESCRIPTION AND REMARKS	DEPTH (ft)
					REC. (ft) %	RQD (ft) %	REC. (ft) %	RQD (ft) %			
1125.6	1,125.6	20.4	5.0	N=60/0.0 1:28/1.0 0:57/1.0 0:59/1.0 1:09/1.0 1:11/1.0	(3.5) 70%	(0.5) 10%	(3.5) 70%	(0.5) 10%		Begin Coring @ 20.4 ft CRYSTALLINE ROCK METAMORPHOSED GRANITE Slight to moderate weathering, moderately hard to soft, close to very close fractures	20.4
	1,120.6	25.4								Boring Terminated at Elevation 1,120.6 ft in Crystalline Rock: METAMORPHOSED GRANITE	25.4

NCDOT CORE DOUBLE 01\_GEO\_BRDG0291.GPJ NC\_DOT.GDT 1/2/18

# CORE PHOTOGRAPHS

EB1-A  
BOX 1 OF 1: 20.4' TO 25.4'





# GEOTECHNICAL BORING REPORT

## BORE LOG

WBS 17BP.12.R.88		TIP SF-010291		COUNTY ALEXANDER		GEOLOGIST J Mize										
SITE DESCRIPTION Bridge 291 over Duck Creek on SR 1348 (Old NC 90)							GROUND WTR (ft)									
BORING NO. B1-A		STATION 16+05		OFFSET 6 ft LT		ALIGNMENT -L-										
COLLAR ELEV. 1,132.5 ft		TOTAL DEPTH 39.5 ft		NORTHING 800,113		EASTING 1,316,590										
DRILL RIG/HAMMER EFF./DATE SUM3123 CME-550X 93% 11/06/2015			DRILL METHOD NW Casing w/ Advancer		HAMMER TYPE Automatic											
DRILLER L Gonzalez		START DATE 12/05/17		COMP. DATE 12/05/17		SURFACE WATER DEPTH N/A										
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)		
			0.5ft	0.5ft	0.5ft	0	25	50	75	100						
1135																
	1,132.5	0.0	2	23	13									1,132.5	GROUND SURFACE	0.0
1130	1,128.2	4.3	1	1	WOH										<b>ALLUVIAL</b> Brown to gray, very loose to dense, silty SAND (A-2-4), trace organics and gravel	
1125	1,123.2	9.3	8	11	12											
1120	1,118.2	14.3	12	30	70/0.1									1,117.7	<b>RESIDUAL</b> Brown, tan, dark gray, medium dense, silty SAND (A-2-4), saprolitic	14.8
1115	1,113.2	19.3	100/0.2											1,117.7	<b>WEATHERED ROCK</b> METAMORPHOSED GRANITE	
1110	1,108.2	24.3	60/0.0											1,108.2	<b>CRYSTALLINE ROCK</b> METAMORPHOSED GRANITE	24.3
1105																
1100																
1095														1,093.0	Boring Terminated at Elevation 1,093.0 ft in Crystalline Rock: METAMORPHOSED GRANITE	39.5

WBS 17BP.12.R.88		TIP SF-010291		COUNTY ALEXANDER		GEOLOGIST J Mize										
SITE DESCRIPTION Bridge 291 over Duck Creek on SR 1348 (Old NC 90)							GROUND WTR (ft)									
BORING NO. B1-B		STATION 15+95		OFFSET 11 ft RT		ALIGNMENT -L-										
COLLAR ELEV. 1,132.7 ft		TOTAL DEPTH 21.0 ft		NORTHING 800,093		EASTING 1,316,587										
DRILL RIG/HAMMER EFF./DATE SUM3123 CME-550X 93% 11/06/2015			DRILL METHOD H.S. Augers		HAMMER TYPE Automatic											
DRILLER L Gonzalez		START DATE 12/06/17		COMP. DATE 12/07/17		SURFACE WATER DEPTH N/A										
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)		
			0.5ft	0.5ft	0.5ft	0	25	50	75	100						
1135																
	1,132.7	0.0	1	0	1									1,132.7	GROUND SURFACE	0.0
1130	1,128.2	4.5	2	2	4										<b>ALLUVIAL</b> Brown to gray, very loose to loose, silty SAND (A-2-4)	
1125	1,123.2	9.5	2	4	5											
1120	1,118.2	14.5	11	27	21									1,114.2	<b>RESIDUAL</b> Brown, orange, gray, loose to dense, silty coarse SAND (A-2-4), saprolitic	9.0
1115	1,113.2	19.5	12	88/0.3										1,114.2	<b>WEATHERED ROCK</b> METAMORPHOSED GRANITE	18.5
	1,111.7	21.0	60/0.0											1,111.7	<b>WEATHERED ROCK</b> METAMORPHOSED GRANITE	21.0
															Boring Terminated with Standard Penetration Test Refusal at Elevation 1,111.7 ft on Crystalline Rock: METAMORPHOSED GRANITE	

NCDOT BORE DOUBLE 01\_GEO\_BRDG0291.GPJ NC\_DOT.GDT 1/2/18

# GEOTECHNICAL BORING REPORT

## CORE LOG

WBS 17BP.12.R.88		TIP SF-010291		COUNTY ALEXANDER		GEOLOGIST J Mize						
SITE DESCRIPTION Bridge 291 over Duck Creek on SR 1348 (Old NC 90)							GROUND WTR (ft)					
BORING NO. B1-A		STATION 16+05		OFFSET 6 ft LT		ALIGNMENT -L-						
COLLAR ELEV. 1,132.5 ft		TOTAL DEPTH 39.5 ft		NORTHING 800,113		EASTING 1,316,590						
DRILL RIG/HAMMER EFF./DATE SUM3123 CME-550X 93% 11/06/2015				DRILL METHOD NW Casing w/ Advancer		HAMMER TYPE Automatic						
DRILLER L Gonzalez		START DATE 12/05/17		COMP. DATE 12/05/17		SURFACE WATER DEPTH N/A						
CORE SIZE NQ		TOTAL RUN 15.2 ft										
ELEV (ft)	RUN ELEV (ft)	DEPTH (ft)	RUN (ft)	DRILL RATE (Min/ft)	RUN		STRATA		LOG	DESCRIPTION AND REMARKS	DEPTH (ft)	
					REC. (ft) %	RQD (ft) %	REC. (ft) %	RQD (ft) %				
1108.2	1,108.2	24.3	1.2	N=60/0.0	(1.1)	(0.8)	(13.0)	(7.1)		Begin Coring @ 24.3 ft	24.3	
	1,107.0	25.5	5.0	1:55/1.2	92%	67%	86%	47%		1,108.2	CRYSTALLINE ROCK METAMORPHOSED GRANITE	
1105				0:33/1.0	(3.6)	(1.6)					Very slight weathering, hard rock, close fractures (24.3'-27.6')	
				0:50/1.0	72%	32%					Moderate weathering, very soft, very close fractures (27.6'-31')	
	1,102.0	30.5		0:55/1.0								
1100			5.0	0:46/1.0	(4.3)	(3.4)				Very slight weathering, moderately hard to hard, very close to close fractures (31'-39.5')		
				1:07/1.0	86%	68%						
				1:19/1.0								
	1,097.0	35.5		1:03/1.0								
				1:09/1.0								
1095			4.0	1:27/1.0	(4.0)	(1.3)						
				1:19/1.0	100%	33%						
				1:17/1.0								
	1,093.0	39.5		1:14/1.0						Boring Terminated at Elevation 1,093.0 ft in Crystalline Rock: METAMORPHOSED GRANITE	39.5	

NCDOT CORE DOUBLE 01\_GEO\_BRDG0291.GPJ NC\_DOT.GDT 1/2/18



# CORE PHOTOGRAPHS

B1-A  
BOX 1 AND 2 OF 2: 24.3' TO 39.5'





# GEOTECHNICAL BORING REPORT

## BORE LOG

WBS 17BP.12.R.88		TIP SF-010291		COUNTY ALEXANDER		GEOLOGIST J Mize										
SITE DESCRIPTION Bridge 291 over Duck Creek on SR 1348 (Old NC 90)							GROUND WTR (ft)									
BORING NO. B2-A		STATION 16+59		OFFSET 17 ft LT		ALIGNMENT -L-										
COLLAR ELEV. 1,135.2 ft		TOTAL DEPTH 32.0 ft		NORTHING 800,144		EASTING 1,316,635										
DRILL RIG/HAMMER EFF./DATE SUM3123 CME-550X 93% 11/06/2015			DRILL METHOD H.S. Augers		HAMMER TYPE Automatic											
DRILLER L Gonzalez		START DATE 12/06/17		COMP. DATE 12/06/17		SURFACE WATER DEPTH N/A										
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION			
			0.5ft	0.5ft	0.5ft	0	25	50	75	100			ELEV. (ft)	DEPTH (ft)		
1140																
1135	1,135.2	0.0													1,135.2	0.0
1130	1,131.1	4.1	1	1	1									1,132.2	3.0	GROUND SURFACE
1125	1,126.1	9.1	4	2	1									1,128.2	7.0	ALLUVIAL Brown, very loose, silty fine SAND (A-2-4) Brown, very soft, sandy SILT (A-4)
1120	1,121.1	14.1	3	4	5									1,122.2	13.0	Brown, very loose, sandy GRAVEL (A-1-b)
1115	1,116.1	19.1	5	7	9									1,122.2	13.0	RESIDUAL Orange, brown, loose to dense, silty SAND (A-2-4), saprolitic
1110	1,111.1	24.1	27	25	23									1,107.1	28.1	CRYSTALLINE ROCK METAMORPHOSED GRANITE
1105	1,106.1	29.1	60/0.0											1,103.2	32.0	Boring Terminated with Standard Penetration Test Refusal at Elevation 1,103.2 ft in Crystalline Rock: METAMORPHOSED GRANITE
	1,103.2	32.0	60/0.0													

WBS 17BP.12.R.88		TIP SF-010291		COUNTY ALEXANDER		GEOLOGIST J Mize										
SITE DESCRIPTION Bridge 291 over Duck Creek on SR 1348 (Old NC 90)							GROUND WTR (ft)									
BORING NO. B2-B		STATION 16+46		OFFSET 11 ft RT		ALIGNMENT -L-										
COLLAR ELEV. 1,134.6 ft		TOTAL DEPTH 40.1 ft		NORTHING 800,113		EASTING 1,316,634										
DRILL RIG/HAMMER EFF./DATE SUM3123 CME-550X 93% 11/06/2015			DRILL METHOD H.S. Augers		HAMMER TYPE Automatic											
DRILLER L Gonzalez		START DATE 12/06/17		COMP. DATE 12/06/17		SURFACE WATER DEPTH N/A										
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION			
			0.5ft	0.5ft	0.5ft	0	25	50	75	100			ELEV. (ft)	DEPTH (ft)		
1135	1,134.6	0.0	1	1	2									1,134.6	0.0	GROUND SURFACE
1130	1,130.4	4.2	2	3	2									1,121.6	13.0	ALLUVIAL Brown, very loose, silty fine SAND (A-2-4), trace organics and mica, some gravel
1125	1,125.4	9.2	3	2	1									1,121.6	13.0	RESIDUAL Brown, gray, black, medium dense, silty coarse SAND (A-2-4), saprolitic
1120	1,120.4	14.2	16	16	7									1,116.1	18.5	WEATHERED ROCK METAMORPHOSED GRANITE
1115	1,115.4	19.2	100/0.2											1,114.1	20.5	RESIDUAL Brown, gray, black, medium dense, silty coarse SAND (A-2-4), saprolitic
1110	1,110.4	24.2	5	13	87/0.2									1,109.9	24.7	WEATHERED ROCK METAMORPHOSED GRANITE
1105	1,108.3	26.3	60/0.0											1,108.3	26.3	CRYSTALLINE ROCK METAMORPHOSED GRANITE
1100																
1095														1,094.5	40.1	Boring Terminated at Elevation 1,094.5 ft in Crystalline Rock: METAMORPHOSED GRANITE

NCDOT BORE DOUBLE 01\_GEO\_BRDG0291.GPJ NC\_DOT.GDT 1/2/18

# GEOTECHNICAL BORING REPORT

## CORE LOG

WBS 17BP.12.R.88		TIP SF-010291		COUNTY ALEXANDER		GEOLOGIST J Mize					
SITE DESCRIPTION Bridge 291 over Duck Creek on SR 1348 (Old NC 90)							GROUND WTR (ft)				
BORING NO. B2-B		STATION 16+46		OFFSET 11 ft RT		ALIGNMENT -L-					
COLLAR ELEV. 1,134.6 ft		TOTAL DEPTH 40.1 ft		NORTHING 800,113		EASTING 1,316,634					
DRILL RIG/HAMMER EFF./DATE SUM3123 CME-550X 93% 11/06/2015				DRILL METHOD H.S. Augers		HAMMER TYPE Automatic					
DRILLER L Gonzalez		START DATE 12/06/17		COMP. DATE 12/06/17		SURFACE WATER DEPTH N/A					
CORE SIZE NQ		TOTAL RUN 13.8 ft									
ELEV (ft)	RUN ELEV (ft)	DEPTH (ft)	RUN (ft)	DRILL RATE (Min/ft)	RUN		STRATA		LOG	DESCRIPTION AND REMARKS	DEPTH (ft)
					REC. (ft) %	RQD (ft) %	REC. (ft) %	RQD (ft) %			
1108.3	1,108.3	26.3	3.8	N=60/0.0 1:08/0.8 1:15/1.0 1:37/1.0 1:53/1.0	(3.6) 95%	(3.6) 95%	(13.3) 96%	(8.8) 64%		Begin Coring @ 26.3 ft <b>CRYSTALLINE ROCK</b> METAMORPHOSED GRANITE	26.3
1105	1,104.5	30.1	5.0	1:27/1.0 1:18/1.0 1:48/1.0 1:45/1.0 1:35/1.0	(4.9) 98%	(4.1) 82%				Very slight weathering, hard to very hard, close to moderately close fractures (26.3'-37')	
1100	1,099.5	35.1	5.0	1:10/1.0 1:14/1.0 1:09/1.0 1:29/1.0 1:37/1.0	(4.8) 96%	(4.1) 82%				Slight to moderate weathering, close fractures (37'-38.5')	
1095	1,094.5	40.1								Boring Terminated at Elevation 1,094.5 ft in Crystalline Rock: METAMORPHOSED GRANITE	40.1

NCDOT CORE DOUBLE 01\_GEO\_BRDG0291.GPJ NC\_DOT.GDT 1/2/18

# CORE PHOTOGRAPHS

**B2-B**  
BOXES 1 AND 2 OF 2: 26.3' TO 40.1'





# GEOTECHNICAL BORING REPORT

## BORE LOG

<b>WBS</b> 17BP.12.R.88			<b>TIP</b> SF-010291			<b>COUNTY</b> ALEXANDER			<b>GEOLOGIST</b> J Mize									
<b>SITE DESCRIPTION</b> Bridge 291 over Duck Creek on SR 1348 (Old NC 90)								<b>GROUND WTR (ft)</b>										
<b>BORING NO.</b> EB2-A		<b>STATION</b> 16+97		<b>OFFSET</b> 13 ft LT		<b>ALIGNMENT</b> -L-		0 HR. Dry										
<b>COLLAR ELEV.</b> 1,144.4 ft		<b>TOTAL DEPTH</b> 30.4 ft		<b>NORTHING</b> 800,154		<b>EASTING</b> 1,316,672		24 HR. Caved										
<b>DRILL RIG/HAMMER EFF./DATE</b> SUM3123 CME-550X 93% 11/06/2015						<b>DRILL METHOD</b> H.S. Augers			<b>HAMMER TYPE</b> Automatic									
<b>DRILLER</b> L Gonzalez			<b>START DATE</b> 12/04/17		<b>COMP. DATE</b> 12/04/17		<b>SURFACE WATER DEPTH</b> N/A											
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)				
			0.5ft	0.5ft	0.5ft	0	25	50	75	100								
1145															1,144.4	GROUND SURFACE	0.0	
1140	1,140.3	4.1	WOH	WOH	1								M			<b>ROADWAY EMBANKMENT</b> Brown, red, orange, very soft, silty CLAY (A-7-6), trace mica		
1135	1,135.3	9.1											M		1,135.4	<b>ALLUVIAL</b> Brown, loose, silty SAND (A-2-4)	9.0	
1130	1,130.3	14.1	WOH	WOH	WOH								M		1,131.4	Gray, very loose, clayey SAND (A-2-6)	13.0	
1125	1,125.3	19.1											W		1,126.4	Brown, medium dense, sandy GRAVEL (A-1-b)	18.0	
1120	1,120.3	24.1											M		1,122.4	<b>RESIDUAL</b> Orange, brown, gray, loose, silty SAND (A-2-5), trace mica, saprolitic	22.0	
1115	1,115.3	29.1													1,114.4	<b>WEATHERED ROCK</b> METAMORPHOSED GRANITE	30.0	
	1,114.0	30.4													1,114.0	Boring Terminated with Standard Penetration Test Refusal at Elevation 1,114.0 ft on Crystalline Rock: METAMORPHOSED GRANITE	30.4	

<b>WBS</b> 17BP.12.R.88			<b>TIP</b> SF-010291			<b>COUNTY</b> ALEXANDER			<b>GEOLOGIST</b> A Bozorgi									
<b>SITE DESCRIPTION</b> Bridge 291 over Duck Creek on SR 1348 (Old NC 90)								<b>GROUND WTR (ft)</b>										
<b>BORING NO.</b> EB2-B		<b>STATION</b> 16+91		<b>OFFSET</b> 2 ft RT		<b>ALIGNMENT</b> -L-		0 HR. Dry										
<b>COLLAR ELEV.</b> 1,145.7 ft		<b>TOTAL DEPTH</b> 29.3 ft		<b>NORTHING</b> 800,138		<b>EASTING</b> 1,316,672		24 HR. FIAD										
<b>DRILL RIG/HAMMER EFF./DATE</b> SUM3123 CME-550X 93% 11/06/2015						<b>DRILL METHOD</b> H.S. Augers			<b>HAMMER TYPE</b> Automatic									
<b>DRILLER</b> L Gonzalez			<b>START DATE</b> 12/04/17		<b>COMP. DATE</b> 12/04/17		<b>SURFACE WATER DEPTH</b> N/A											
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)				
			0.5ft	0.5ft	0.5ft	0	25	50	75	100								
1150															1,145.7	GROUND SURFACE	0.0	
1145													M		1,144.6	Asphalt/base	1.1	
1140	1,141.7	4.0											M			<b>ROADWAY EMBANKMENT</b> Brown, orange, soft, fine to coarse sandy moderate plasticity CLAY (A-6), trace mica		
1135	1,136.7	9.0											M		1,133.7	<b>ALLUVIAL</b> Gray, light brown, very loose, silty fine SAND (A-2-4)	12.0	
1130	1,131.7	14.0											W		1,128.7	Brown, dense, sandy silty GRAVEL (A-1-b)	17.0	
1125	1,126.7	19.0											Sat.		1,122.7	<b>RESIDUAL</b> Brown, orange, loose, silty SAND (A-2-4), saprolitic	23.0	
1120	1,121.7	24.0											W		1,116.7	<b>WEATHERED ROCK</b> METAMORPHOSED GRANITE	29.0	
	1,116.4	29.3													1,116.4	Boring Terminated with Standard Penetration Test Refusal at Elevation 1,116.4 ft on Crystalline Rock: METAMORPHOSED GRANITE	29.3	