



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

ROY COOPER
GOVERNOR

J. ERIC BOYETTE
SECRETARY

May 16, 2023

Contract No.: DL00296
WBS No.: 17BP.12.R.56
TIP No.: None
F.A. No.: State Funded
County: Catawba
Description: Replacing Bridge No. 85 on SR 1734 (Travis Rd)
Let Date: May 23, 2023

RE: Addendum #1 to Contract DL00296

To Whom It May Concern:

Reference is made to the proposal form furnished to you on this project.

The following revisions have been made to the advertised proposal:

Page No.	Revision
Proposal Item Sheet No. 2	Item number 28 has modified from Work Zone Signs (Portable) to Work Zone Signs (Stationary).

The Contractor's Bid must include these revised pay item(s).

Please replace the above listed pages with the attached revised pages. The electronic bidding file has been updated to reflect these revisions. Please download the Addendum File and follow the instructions for applying the addendum. Bid Express will not accept your bid unless the addendum has been applied.

If you have any questions please contact Greg Brittain at (980) 552-4222.

The contract will be prepared accordingly.

Sincerely,

A handwritten signature in black ink that reads "Mark E. Stafford". The signature is written in a cursive style with a large, stylized initial "M".

Mark E. Stafford, P.E.
Division Engineer

MES/ghb

Attachments

Cc: Larry Carpenter, PE, Deputy Division Engineer
Rodney Gantt, Division Construction Engineer
Cole Gurley, PE, Division Project Development Engineer
Bryan Sowell, PE, Division Project Team Lead

County: CATAWBA

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	TYPE III REINFORCED APPROACH FILL, STATION ***** (STA. 12+77.00 -L-)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUBBING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	50 CY		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	30 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	50 CY		
0009	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	260 SY		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	10 TON		
0011	0320000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	30 SY		
0012	0335200000-E	305	15" DRAINAGE PIPE	40 LF		
0013	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		
0014	1330000000-E	607	INCIDENTAL MILLING	100 SY		
0015	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	166 TON		
0016	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	156 TON		
0017	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	73 TON		

County: CATAWBA

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	20 TON		
0019	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0020	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0021	2556000000-E	846	SHOULDER BERM GUTTER	33 LF		
0022	3030000000-E	862	STEEL BEAM GUARDRAIL	62.5 LF		
0023	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0024	3215000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0025	3288000000-N	SP	GUARDRAIL END UNITS, TYPE TL-2 (TL-2)	4 EA		
0026	3649000000-E	876	RIP RAP, CLASS B	5 TON		
0027	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	110 SY		
0028	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	465 SF		
0029	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	65 SF		
0030	4430000000-N	1130	DRUMS	50 EA		
0031	4445000000-E	1145	BARRICADES (TYPE III)	64 LF		
0032	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	3,200 LF		
0033	6000000000-E	1605	TEMPORARY SILT FENCE	445 LF		
0034	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	35 TON		

County: CATAWBA

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	110 TON		
0036	6012000000-E	1610	SEDIMENT CONTROL STONE	70 TON		
0037	6015000000-E	1615	TEMPORARY MULCHING	0.5 ACR		
0038	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0039	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.5 TON		
0040	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0041	6029000000-E	SP	SAFETY FENCE	260 LF		
0042	6030000000-E	1630	SILT EXCAVATION	160 CY		
0043	6036000000-E	1631	MATTING FOR EROSION CONTROL	6,410 SY		
0044	6037000000-E	SP	COIR FIBER MAT	100 SY		
0045	6042000000-E	1632	1/4" HARDWARE CLOTH	20 LF		
0046	6070000000-N	1639	SPECIAL STILLING BASINS	2 EA		
0047	6071010000-E	SP	WATTLE	40 LF		
0048	6071020000-E	SP	POLYACRYLAMIDE (PAM)	45 LB		
0049	6084000000-E	1660	SEEDING & MULCHING	0.5 ACR		
0050	6087000000-E	1660	MOWING	0.5 ACR		
0051	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		

County: CATAWBA

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0052	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0053	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0054	6108000000-E	1665	FERTILIZER TOPDRESSING	0.5 TON		
0055	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0056	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	13 EA		
0057	6117500000-N	SP	CONCRETE WASHOUT STRUCTURE	1 EA		

STRUCTURE ITEMS

0058	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (12+77.00 -L-)	Lump Sum	L.S.	
0059	8065000000-N	SP	ASBESTOS ASSESSMENT	Lump Sum	L.S.	
0060	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (STA. 12+77.00 -L-)	Lump Sum	L.S.	
0061	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	45 CY		
0062	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (STA. 12+77.00 -L-)	Lump Sum	L.S.	
0063	8217000000-E	425	REINFORCING STEEL (BRIDGE)	5,472 LB		
0064	8328200000-E	450	PILE DRIVING EQUIPMENT SETUP FOR *** STEEL PILES (HP 12 X 53)	10 EA		
0065	8364000000-E	450	HP 12 X 53 STEEL PILES	280 LF		
0066	8505000000-E	460	VERTICAL CONCRETE BARRIER RAIL	140 LF		

County: CATAWBA

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0067	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	189 TON		
0068	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	211 SY		
0069	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0070	8763000000-E	430	3'-0" X 2'-0" PRESTRESSED CONC CORED SLABS	700 LF		

1528/May16/Q20287.25/D320086930000/E70

Total Amount Of Bid For Entire Project :

