



STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION

PAT MCCRORY  
GOVERNOR

ANTHONY J. TATA  
SECRETARY

April 30, 2014

To Prospective Bidders:

Subject: Addendum 1 for: Concrete Sidewalk, Curb And Gutter, Paving And Drainage Structures

CONTRACT NO: DM00101  
WBS: 43911  
ROUTES: Haywood Road (SR 3548)  
COUNTY: Buncombe  
BID OPENING: May 21, 2014 @ 2:00pm

This letter is to advise all prospective bidders of the following contract addendum.

- The Pre-Bid minutes issued by the North Carolina Department of Transportation for the subject contract are considered a part of the contract bid document and shall be signed by an authorized agent of the company and returned with the bid proposal. Proposals submitted without the Pre-Bid minutes shall be considered irregular and will not be considered for award.

This addendum officially becomes a part of the contract bid document. If this office can provide additional information, please feel free to contact me at (828) 251-6171.

Sincerely,

A handwritten signature in black ink that reads "McCallum".

M.K. Calloway  
Division Project Manager

Cc: Mr. J.J. Swain, Jr., P.E., Division Engineer  
Mr. R.A. Tipton, P.E., PLS, Division Construction Engineer  
Mr. M.T. Gibbs, P.E., Division Maintenance Engineer  
Mr. C.E. Bandy, P.E., District Engineer  
Mr. C.D. Hood, P.E., Resident Engineer

---

Division Thirteen  
Phone: 828/251-6171

Office of the Division Engineer  
Post Office Box 3279

Asheville, NC 28802  
Fax: 828/251-6394

Pre-Bid Notes  
DM00101  
WBS# 43911  
Buncombe County  
Route: Haywood Rd (SR 3548)

4/29/2014

- Description- Concrete Sidewalk, Curb & Gutter, Paving and Drainage Structures.
- Bid Opening Weds. May 21, 2014 @ 2:00pm.
- 0% DBE goals, fills form out correctly.
- Available June 16, 2014 and Completion September 12, 2014. LDs \$500.00 per DAY.
- ICTs Liquidated damages \$500.00 per HOUR.
- No sub-surface information, it is the responsibility of the contractor to determine.
- Mobilization, traffic control, and erosion control is incidental to the contract.
- Line Item 13 is for converting existing Catch Basin to Junction Boxes.
- This contract requires the contractor to have liability insurance.
- Repair asphalt at intersection of Haywood road and Hanover St., which will require milling 1"-4".
- Removal of curb ramps is incidental to line item #11 Concrete Curb Ramps.
- On Hanover Street, asphalt is replaced all the way to the end of new curb & gutter.
- Major utilities across B&B Pharmacy on Hanover St.
- Roadway cross pipes should be a rigged structural pipe.
- Approved truncated domes on each curb ramps.
- Traffic services to address signs, will coordinate with contractor.
- Street signs contractor is responsible to replace signs back in new spots.
- Mill entire asphalt section off of I-240 Exit to Hanover St. edge of road alignment. 1"-4" Milling.
- Send foot traffic down safe alternate routes when closing sections of the sidewalk down for reconstruction.

Company Name: \_\_\_\_\_

Authorized Agent Signature: \_\_\_\_\_

Print Name: \_\_\_\_\_ Date: \_\_\_\_\_