



STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION

PAT MCCRORY  
GOVERNOR

ANTHONY J. TATA  
SECRETARY

June 11, 2014

To Prospective Bidders:

Subject: Addendum 1 for: Sidewalk, Curb & Gutter, Drainage Structures and Retaining Walls

CONTRACT NO: DM00109  
WBS: 3613.3.09  
TIP NO.: ER-2971  
F.A. NO.: 000S-424  
ROUTES: US 19/23  
COUNTY: Buncombe  
BID OPENING: June 18, 2014 @ 2:00pm

This letter is to advise all prospective bidders of the following contract addendum.

- The Pre-Bid minutes issued by the North Carolina Department of Transportation for the subject contract are considered a part of the contract bid document and shall be signed by an authorized agent of the company and returned with the bid proposal. Proposals submitted without the Pre-Bid minutes shall be considered irregular and will not be considered for award.

This addendum officially becomes a part of the contract bid document. If this office can provide additional information, please feel free to contact me at (828) 251-6171.

Sincerely,

A handwritten signature in black ink, appearing to read "M.K. Calloway".

M.K. Calloway  
Division Project Manager

Cc: Mr. J.J. Swain, Jr., P.E., Division Engineer  
Mr. R.A. Tipton, P.E., PLS, Division Construction Engineer  
Mr. M.T. Gibbs, P.E., Division Maintenance Engineer  
Mr. C.E. Bandy, P.E., District Engineer  
Mr. C.D. Hood, P.E., Resident Engineer

---

Division Thirteen  
Phone: 828/251-6171

Office of the Division Engineer  
Post Office Box 3279

Asheville, NC 28802  
Fax: 828/251-6394

**19/23 Sidewalk Project**

**DM00109 WBS: 3613.3.09 Buncombe**

- Bid opening: 2:00pm Wednesday, June 18, 2014
- Availability: July 21, 2014; Completion Date: October 31, 2014
- Liquidated damages: \$500.00 per calendar day
- Page 4 of contract; follow the 13 steps correctly before submitting bid.
- 0% DBE/MBE goals for this project.
- No sub-surface information given; contractor's responsibility.
- Design drawings for retaining wall located on website.
- Contractor is aware that they must patch asphalt back from the removal of curb and gutter.
- There are five concrete flumes for this project.
- Curb ramps require ADA/NCDOT approved truncated domes.
- Seeding and mulching of exposed soil must be done within seven days to be accepted by the NCDOT.
- Traffic control, mobilization, seeding and mulching were added to re-advertised contract.
- Standard special provision: availability of funds for this project could be terminated due to it being a federally aided project.
- NCDOT will complete interviews with contractor's employees for federal requirements.
- Removal of concrete driveways is incidental to Line Item #10, #1, and #14. Quantities should be a lump sum of one.
- Under NCDOT specifications, 8 in. of stone should be placed under concrete driveways, and 3-4 in. of stone should be placed under curb and gutter.
- Concrete material must be to NCDOT specifications. A department representative will check sample and accept or deny before placement. NCDOT is not responsible for unacceptable concrete brought to project.

**Authorized Agent Name:** \_\_\_\_\_

**Signature:** \_\_\_\_\_ **Date:** \_\_\_\_\_