PROJECT NO.	SHEET NO.	TOTAL NO.
14CR.10501.13	5	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	1½" MILLING SY	3" MILLING SY	INTERMEDIATE COURSE, I19.0B TONS	SURFACE COURSE, S9.5C TONS	ASPHALT BINDER FOR PLANT MIX TONS	PORTABLE LIGHTING EA	INDUCTIVE LOOP SAW CUT LF	LEAD-IN CABLE LF	GENERIC STRUCTURE ITEM ASPHALTIC PLUG JOINT LF
14CR.10501.13	Jackson	1	US 23/441 SOUTH	FROM BRIDGE 133 OVER US 74 TO SOUTH END BRIDGE 75	1	5	MU	NO	NO	1	68	51,861	36,250	6,250	3,626	514	1.0	1,742	250	1,212.00
TOTAL FOR MAP NO. 1										**1**		**51,861**	**36,250**	**6,250**	**3,626**	**514**	**1.0**	**1,742**	**250**	**1,212.00**
14CR.10501.13	Jackson	2	RAMPS	FROM US 23/441 TO US 74 EAST	2	1		NO	NO	0.3	26	3,200	2,000	345	270	32				
TOTAL FOR MAP NO. 2										**0.3**		**3,200**	**2,000**	**345**	**270**	**32**				
TOTAL FOR PROJ NO. 14CR.10501.13										**1.3**		**55,061**	**38,250**	**6,595**	**3,896**	**546**	**1.0**	**1,742**	**250**	**1,212.00**
GRAND TOTAL										**1.3**		**55,061**	**38,250**	**6,595**	**3,896**	**546**	**1.0**	**1,742**	**250**	**1,212.00**