PROJECT REFERENCE NO.	SHEET NO.
WBS#: 43996.3.1	1-A

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

INDEX OF SHEETS

1	TITLE SHEET
1-A	INDEX OF SHEETS, GENERAL NOTES AND LIST OF STANDARDS
2	CONVENTIONAL SYMBOLS
3-3B	TYPCIAL SECTION, PAVEMENT SCHEDULE
4-6	PLAN SHEET
PMP-1- PMP-4	PAVEMENT MARKING PLANS

GENERAL NOTES

GENERAL NOTES: 2012 SPECIFICATIONS
EFFECTIVE: 01-17-2012

1 CARE SHALL BE TAKEN TO PREVENT DAMAGE TO EXISTING UTILITIES DURING CONSTRUCTION. ANY DAMAGE TO THESE UTILITIES SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE.

2 THE CONTRACTOR SHALL MAINTAIN THE SITE IN A MANNER SO THAT WORKMEN AND PUBLIC SHALL BE PROTECTED FROM INJURY.

3 UTILITIES ON THIS PROJECT ARE:
TELEPHONE- FRONTIER COMMUNICATIONS
FIBER- BALSAM WEST FIBER
POWER- DUKE ENERGY

4 NO SUBSURFACE PLANS ARE AVIABLE ON THIS PROJECT. CONTRACTOR SHOULD MAKE HIS OWN INVESTIGATION

LIST OF ROADWAY STANDARDS

2012 ROADWAY STANDARD DRAWINGS

The following Roadway Standards as appear in "Roadway Standard Drawings" - Highway Design Branch - N.C. Department of Transportation - Raleigh, N.C., dated January 17, 2012 and the latest revision thereto are applicable to this project and by reference hereby are considered a part of these plans.

STD. NO.	TITLE
DIVISION 3 - PIPE CULVERTS	
300.01	Method of Pipe Installation
DIVISION 8 - INCIDENTALS	
840.31	Concrete Junction Box - 12" thru 66" Pipe
852.01	Concrete Islands
DIVISION 11- WORK ZONE TRAFFIC CONTROL	
1110.01	Stationary Work Zone Signs
1110.02	Portable Work Zone Signs
1150.01	Flagging Devices
DIVISION 12- PAVEMENT MARKERS AND DELINEATION	
1205.05	Turn Lanes
DIVISION 16- EROSION CONTROL AND ROADSIDE DEVELOPMENT	
1605.01	Temporary Silt Fence
1632.02	Rock inlet Sediment Trap Type A