



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

PAT MCCRORY
GOVERNOR

ANTHONY J. TATA
SECRETARY

January 23, 2015

ADDENDUM #1

To: Plan Holders

From: Wanda H. Austin, PE
Proposals Engineer

RE:
Contract ID: DN00328
County: Cherokee
Letting Date: February 10, 2015

The pay items and plan sheets have been modified for the above project. The revised plan has been uploaded to connect.ncdot.gov. Please use the revised plan, item sheet and ebs when submitting a bid.

Please insert this letter into the addendum section of the proposal and sign the verification. Thank you for your attention to this matter.

Fourteenth Division Office

Phone: (828)586-2141

253 Webster Road, Sylva, North Carolina 28779

Fax: (828)586-4043

County : Cherokee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	20 TON		
0005	0343000000-E	310	15" SIDE DRAIN PIPE	112 LF		
0006	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	784 LF		
0007	0448300000-E	310	18" RC PIPE CULVERTS, CLASS IV	520 LF		
0008	0448400000-E	310	24" RC PIPE CULVERTS, CLASS IV	48 LF		
0009	0448500000-E	310	30" RC PIPE CULVERTS, CLASS IV	40 LF		
0010	1220000000-E	545	INCIDENTAL STONE BASE	195 TON		
0011	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (3")	2,100 SY		
0012	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	355 TON		
0013	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	1,148 TON		
0015	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	136 TON		
0016	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	40 TON		
0017	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	24 EA		
0018	2363000000-N	840	FRAME WITH TWO GRATES, STD 840.***** (840.37)	2 EA		
0019	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	6 EA		

County : Cherokee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	16 EA		
0021	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	3,121 LF		
0022	2580000000-E	846	CONCRETE VALLEY GUTTER	175 LF		
0023	2591000000-E	848	4" CONCRETE SIDEWALK	1,956 SY		
0024	2605000000-N	848	CONCRETE CURB RAMP	11 EA		
0025	2612000000-E	848	6" CONCRETE DRIVEWAY	336 SY		
0026	2647000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED)	14 SY		
0027	2830000000-N	858	ADJUSTMENT OF MANHOLES	4 EA		
0028	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	5 EA		
0029	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (TYPE D)	1 EA		
0030	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (TYPE E)	3 EA		
0031	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	240 SF		
0032	4457000000-N	SP	TEMPORARY TRAFFIC CONTROL	Lump Sum	L.S.	
0033	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	39,920 LF		
0036	5648000000-N	1515	RELOCATE WATER METER	4 EA		
0037	5649000000-N	1515	RECONNECT WATER METER	4 EA		
0038	6000000000-E	1605	TEMPORARY SILT FENCE	1,500 LF		
0039	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	20 TON		

County : Cherokee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0040	6012000000-E	1610	SEDIMENT CONTROL STONE	42		TON
0041	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,000		SY
0042	6042000000-E	1632	1/4" HARDWARE CLOTH	384		LF
0043	6071010000-E	SP	WATTLE	105		LF
0044	6071020000-E	SP	POLYACRYLAMIDE (PAM)	3		LB
0045	6084000000-E	1660	SEEDING & MULCHING	1		ACR
0046	8802030000-E	SP	SEGMENTAL GRAVITY RETAINING WALLS	110		SF
0047	1880000000-E	SP	GENERIC PAVING ITEM (LEVELING COURSE, I19.0B)	443		TON
0048	1525100000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A (LEVELING COURSE)	356		TON
0049	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	872		LF

1627/Jan23/Q57180.0/D140384260000/E46

Total Amount Of Bid For Entire Project :