


CONTRACT: DN00164 PROJECT: WBS 17BP.14.R.41

See Sheet 1-A For Index of Sheets
See Sheet 1-B For Symbology






STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

GRAHAM COUNTY

**LOCATION: BRIDGE NO. 102 ON SR 1254 (EAST BUFFALO ROAD)
OVER EAST BUFFALO CREEK**

**TYPE OF WORK: GRADING, PAVING, DRAINAGE, CULVERT AND
TRAFFIC CONTROL**

| STATE | STATE PROJECT REFERENCE NO. | SHEET NO. | TOTAL SHEETS |
|-----------------|-----------------------------|----------------|--------------|
| N.C. | 17BP.14.R.41 | 1 | |
| STATE PROJ. NO. | F.A. PROJ. NO. | DESCRIPTION | |
| 17BP.14.R.41 | | PE, R/W, UTIL. | |
| 17BP.14.R.41 | | CONST. | |
| | | | |
| | | | |
| | | | |
| | | | |



DESIGN DATA

ADT 2001 = 210

V = N/A

FUNC CLASS = LOCAL

SUB-REGIONAL TIER

PROJECT LENGTH

Length Roadway Project 17BP.14.R.41 = 0.064 Miles

NCDOT CONTACT: **Joshua B. Deyton, PE**
NCDOT DIVISION II BRIDGE MANAGER

Prepared By:

Stantec

Stantec Consulting Services Inc.
801 Jones Franklin Road
Suite 300
Raleigh, NC 27609
Tel. (919) 851-6968
Fax. (919) 851-7024
www.stantec.com
License No. F-0872

Prepared for the Office of:
DIVISION OF HIGHWAYS
1000 Birch Ridge Dr., Raleigh NC, 27610

2012 STANDARD SPECIFICATIONS

RIGHT OF WAY DATE:
August 22, 2013

LETTING DATE:

Michael D. Lindgren, PE
PROJECT ENGINEER


Robert Williams, PE
PROJECT DESIGN ENGINEER

HYDRAULICS ENGINEER

ROADWAY DESIGN ENGINEER

11-22-2013





GENERAL NOTES

GENERAL NOTES:

2012 SPECIFICATIONS
EFFECTIVE: 01-17-12
REVISED: 11/01/11

GRADE LINE:

GRADING AND SURFACING:

THE GRADE LINES SHOWN DENOTE THE FINISHED ELEVATION OF THE PROPOSED SURFACING AT GRADE POINTS SHOWN ON THE TYPICAL SECTIONS. GRADE LINES MAY BE ADJUSTED AT THEIR BEGINNING AND ENDING AND AT STRUCTURES AS DIRECTED BY THE ENGINEER IN ORDER TO SECURE A PROPER TIE-IN.

CLEARING:

CLEARING ON THIS PROJECT SHALL BE PERFORMED TO THE LIMITS ESTABLISHED BY METHOD II.

SHOULDER CONSTRUCTION:

ASPHALT, EARTH, AND CONCRETE SHOULDER CONSTRUCTION ON THE HIGH SIDE OF SUPERELEVATED CURVES SHALL BE IN ACCORDANCE WITH STD. NO. 560.01.

SIDE ROADS:

THE CONTRACTOR WILL BE REQUIRED TO DO ALL NECESSARY WORK TO PROVIDE SUITABLE CONNECTIONS WITH ALL ROADS, STREETS, AND DRIVES ENTERING THIS PROJECT. THIS WORK WILL BE PAID FOR AT THE CONTRACT UNIT PRICE FOR THE PARTICULAR ITEMS INVOLVED.

TEMPORARY SHORING:

SHORING REQUIRED FOR THE MAINTENANCE OF TRAFFIC NOT SHOWN ON THE PLANS WILL BE PAID FOR AT THE CONTRACT PRICE FOR "TEMPORARY SHORING".

SUBSURFACE PLANS:

NO SUBSURFACE PLANS ARE AVAILABLE ON THIS PROJECT. THE CONTRACTOR SHOULD MAKE HIS OWN INVESTIGATION AS TO THE SUBSURFACE CONDITIONS.

UTILITIES:

UTILITY OWNER ON THIS PROJECT IS DUKE ENERGY AND FRONTIER COMMUNICATIONS (TELEPHONE).

RIGHT-OF-WAY MARKERS:

ALL RIGHT-OF-WAY MARKERS ON THIS PROJECT SHALL BE PLACED BY OTHERS.

ROADWAY STANDARD DRAWINGS

2012 ROADWAY ENGLISH STANDARD DRAWINGS

The following Roadway Standards as appear in "Roadway Standard Drawings" Highway Design Branch - N. C. Department of Transportation - Raleigh, N. C., Dated January, 2012 are applicable to this project and by reference hereby are considered a part of these plans:

STD.NO.

TITLE

DIVISION 2 - EARTHWORK

200.02 Method of Clearing - Method II

225.02 Guide for Grading Subgrade - Secondary and Local

DIVISION 3 - PIPE CULVERTS

300.01 Method of Pipe Installation

DIVISION 5 - SUBGRADE, BASES AND SHOULDERS

560.01 Method of Shoulder Construction - High Side of Superelevated Curve - Method I

DIVISION 8 - INCIDENTALS

806.02 Granite Right-of-Way Marker

INDEX OF SHEETS

| SHEET NUMBER | SHEET |
|------------------|---------------------------------------------------------------|
| 1 | TITLE SHEET |
| 1-A | INDEX OF SHEETS, GENERAL NOTES, AND LIST OF STANDARD DRAWINGS |
| 1-B | CONVENTIONAL SYMBOLS |
| 1-C | SURVEY CONTROL SHEET (PENDING) |
| 2 | PAVEMENT SCHEDULE & TYPICAL SECTIONS |
| 2A | TEMPORARY UTILITY EASEMENT DETAIL |
| 2B | TEMPORARY SHORING DETAIL |
| 3 | SUMMARY OF QUANTITIES |
| 3A | SUMMARY OF EARTHWORK, DRAINAGE AND PAVEMENT REMOVAL |
| 4 | PLAN/PROFILE SHEET |
| 5 | TEMPORARY DETOUR PLAN |
| TMP-1 THRU TMP-4 | TRAFFIC MANAGMENT PLANS |
| PMP-1 | PAVEMENT MARKING PLAN |
| EC-1 THRU EC-2 | EROSION CONTROL PLANS |
| SIGN-1 | SIGNING PLAN |
| UO-1 | UTILITIES BY OTHERS |
| X-1 THRU X-3 | CROSS-SECTIONS |
| C-1 THRU C-5 | CULVERT PLANS |

04/16/11

Note: Not to Scale

*S.U.E. = Subsurface Utility Engineering

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CONVENTIONAL PLAN SHEET SYMBOLS

BOUNDARIES AND PROPERTY:

| | |
|--------------------------------------------|----------|
| State Line | ----- |
| County Line | ----- |
| Township Line | ----- |
| City Line | ----- |
| Reservation Line | ----- |
| Property Line | ----- |
| Existing Iron Pin | ○ EIP |
| Property Corner | -----x |
| Property Monument | □ ECM |
| Parcel/Sequence Number | ①23 |
| Existing Fence Line | -x-x-x- |
| Proposed Woven Wire Fence | ○ |
| Proposed Chain Link Fence | □ |
| Proposed Barbed Wire Fence | ◇ |
| Existing Wetland Boundary | -----WLB |
| Proposed Wetland Boundary | -----WLB |
| Existing Endangered Animal Boundary | -----EAB |
| Existing Endangered Plant Boundary | -----EPB |
| Known Soil Contamination: Area or Site | ☠ ☠ |
| Potential Soil Contamination: Area or Site | ☠ ? |

BUILDINGS AND OTHER CULTURE:

| | |
|-------------------------------|---|
| Gas Pump Vent or U/G Tank Cap | ○ |
| Sign | ○ |
| Well | ○ |
| Small Mine | ✕ |
| Foundation | □ |
| Area Outline | □ |
| Cemetery | □ |
| Building | □ |
| School | □ |
| Church | □ |
| Dam | □ |

HYDROLOGY:

| | |
|------------------------------------|-----------|
| Stream or Body of Water | ----- |
| Hydro, Pool or Reservoir | □ |
| Jurisdictional Stream | -----JS |
| Buffer Zone 1 | -----BZ 1 |
| Buffer Zone 2 | -----BZ 2 |
| Flow Arrow | → |
| Disappearing Stream | → |
| Spring | ○ |
| Wetland | ----- |
| Proposed Lateral, Tail, Head Ditch | ----- |
| False Sump | ----- |

RAILROADS:

| | |
|--------------------|-------|
| Standard Gauge | ----- |
| RR Signal Milepost | ----- |
| Switch | ----- |
| RR Abandoned | ----- |
| RR Dismantled | ----- |

RIGHT OF WAY:

| | |
|----------------------------------------------------------------|-------|
| Baseline Control Point | ◆ |
| Existing Right of Way Marker | △ |
| Existing Right of Way Line | ----- |
| Proposed Right of Way Line | ----- |
| Proposed Right of Way Line with Iron Pin and Cap Marker | ----- |
| Proposed Right of Way Line with Concrete or Granite R/W Marker | ----- |
| Proposed Control of Access Line with Concrete C/A Marker | ----- |
| Existing Control of Access | ----- |
| Proposed Control of Access | ----- |
| Existing Easement Line | ----- |
| Proposed Temporary Construction Easement | ----- |
| Proposed Temporary Drainage Easement | ----- |
| Proposed Permanent Drainage Easement | ----- |
| Proposed Permanent Drainage / Utility Easement | ----- |
| Proposed Permanent Utility Easement | ----- |
| Proposed Temporary Utility Easement | ----- |
| Proposed Aerial Utility Easement | ----- |
| Proposed Permanent Easement with Iron Pin and Cap Marker | ----- |

ROADS AND RELATED FEATURES:

| | |
|----------------------------|-------|
| Existing Edge of Pavement | ----- |
| Existing Curb | ----- |
| Proposed Slope Stakes Cut | ----- |
| Proposed Slope Stakes Fill | ----- |
| Proposed Curb Ramp | ----- |
| Existing Metal Guardrail | ----- |
| Proposed Guardrail | ----- |
| Existing Cable Guiderail | ----- |
| Proposed Cable Guiderail | ----- |
| Equality Symbol | ⊕ |
| Pavement Removal | ----- |
| VEGETATION: | |
| Single Tree | ☼ |
| Single Shrub | ☼ |
| Hedge | ----- |
| Woods Line | ----- |

| | |
|----------|-------|
| Orchard | ----- |
| Vineyard | ----- |

EXISTING STRUCTURES:

| | |
|------------------------------------------|-------|
| MAJOR: | |
| Bridge, Tunnel or Box Culvert | ----- |
| Bridge Wing Wall, Head Wall and End Wall | ----- |
| MINOR: | |
| Head and End Wall | ----- |
| Pipe Culvert | ----- |
| Footbridge | ----- |
| Drainage Box: Catch Basin, DI or JB | ----- |
| Paved Ditch Gutter | ----- |
| Storm Sewer Manhole | ----- |
| Storm Sewer | ----- |

UTILITIES:

| | |
|-------------------------------------|-------|
| POWER: | |
| Existing Power Pole | ● |
| Proposed Power Pole | ○ |
| Existing Joint Use Pole | ● |
| Proposed Joint Use Pole | ○ |
| Power Manhole | ⊕ |
| Power Line Tower | ⊗ |
| Power Transformer | ⊗ |
| U/G Power Cable Hand Hole | ----- |
| H-Frame Pole | ● |
| Recorded U/G Power Line | ----- |
| Designated U/G Power Line (S.U.E.*) | ----- |

TELEPHONE:

| | |
|---------------------------------------------|-------|
| Existing Telephone Pole | ● |
| Proposed Telephone Pole | ○ |
| Telephone Manhole | ⊕ |
| Telephone Booth | ⊕ |
| Telephone Pedestal | ⊕ |
| Telephone Cell Tower | ⊕ |
| U/G Telephone Cable Hand Hole | ----- |
| Recorded U/G Telephone Cable | ----- |
| Designated U/G Telephone Cable (S.U.E.*) | ----- |
| Recorded U/G Telephone Conduit | ----- |
| Designated U/G Telephone Conduit (S.U.E.*) | ----- |
| Recorded U/G Fiber Optics Cable | ----- |
| Designated U/G Fiber Optics Cable (S.U.E.*) | ----- |

WATER:

| | |
|-------------------------------------|-------|
| Water Manhole | ⊕ |
| Water Meter | ○ |
| Water Valve | ⊗ |
| Water Hydrant | ⊕ |
| Recorded U/G Water Line | ----- |
| Designated U/G Water Line (S.U.E.*) | ----- |
| Above Ground Water Line | ----- |

TV:

| | |
|--------------------------------------------|-------|
| TV Satellite Dish | ☼ |
| TV Pedestal | ⊕ |
| TV Tower | ⊗ |
| U/G TV Cable Hand Hole | ----- |
| Recorded U/G TV Cable | ----- |
| Designated U/G TV Cable (S.U.E.*) | ----- |
| Recorded U/G Fiber Optic Cable | ----- |
| Designated U/G Fiber Optic Cable (S.U.E.*) | ----- |

GAS:

| | |
|-----------------------------------|-------|
| Gas Valve | ◇ |
| Gas Meter | ⊕ |
| Recorded U/G Gas Line | ----- |
| Designated U/G Gas Line (S.U.E.*) | ----- |
| Above Ground Gas Line | ----- |

SANITARY SEWER:

| | |
|------------------------------------------|-------|
| Sanitary Sewer Manhole | ⊕ |
| Sanitary Sewer Cleanout | ⊕ |
| U/G Sanitary Sewer Line | ----- |
| Above Ground Sanitary Sewer | ----- |
| Recorded SS Forced Main Line | ----- |
| Designated SS Forced Main Line (S.U.E.*) | ----- |

MISCELLANEOUS:

| | |
|----------------------------------------|--------|
| Utility Pole | ● |
| Utility Pole with Base | □ |
| Utility Located Object | ○ |
| Utility Traffic Signal Box | ⊕ |
| Utility Unknown U/G Line | ----- |
| U/G Tank; Water, Gas, Oil | ----- |
| Underground Storage Tank, Approx. Loc. | ⊕ |
| A/G Tank; Water, Gas, Oil | ----- |
| Geoenvironmental Boring | ⊕ |
| U/G Test Hole (S.U.E.*) | ⊕ |
| Abandoned According to Utility Records | AATUR |
| End of Information | E.O.I. |

SURVEY CONTROL SHEET 37-0102

-FINAL-

| BL | POINT | DESC. | NORTH | EAST | ELEVATION | L STATION | OFFSET |
|----|-------|-------|-------------|-------------|-----------|------------------------|----------|
| 1 | BL-1 | | 622383.0190 | 564191.8077 | 1954.18 | 10+13.17 | 12.20 LT |
| 2 | BL-2 | | 622391.0749 | 564527.2871 | 1956.53 | 13+48.41 | 11.60 RT |
| 3 | BL-3 | | 622419.7515 | 564872.1119 | 1959.99 | OUTSIDE PROJECT LIMITS | |

| -FINAL- ROW MARKER IRON PIN AND CAP -E | | | | |
|----------------------------------------|----------|--------|-------------|-------------|
| ALIGN | STATION | OFFSET | NORTH | EAST |
| L | 14+50.00 | 25.00 | 622384.6504 | 564630.3601 |
| L | 15+00.00 | 40.00 | 622374.8474 | 564682.3269 |
| L | 16+34.00 | 40.00 | 622390.6782 | 564813.6464 |
| L | 16+45.85 | 28.85 | 622402.5037 | 564824.2511 |


| -FINAL- ROW MARKER PERMANENT EASEMENT -E | | | | |
|------------------------------------------|----------|--------|-------------|-------------|
| ALIGN | STATION | OFFSET | NORTH | EAST |
| L | 14+69.00 | -35.47 | 622446.6346 | 564643.5370 |
| L | 14+80.00 | -53.00 | 622465.1639 | 564652.5027 |
| L | 15+06.00 | -53.00 | 622467.9269 | 564677.7474 |
| L | 15+20.00 | -36.61 | 622453.2635 | 564693.3032 |
| L | 15+06.00 | 40.00 | 622375.5382 | 564688.3929 |
| L | 14+91.00 | 71.00 | 622343.0221 | 564676.5703 |
| L | 14+60.00 | 61.00 | 622349.7435 | 564643.8251 |
| L | 14+62.00 | 28.48 | 622382.3103 | 564642.7710 |

 BM1 ELEVATION = 1959.67
 N 622315 E 564204
 L STATION 10+17.00 57 RIGHT
 8" SPIKE SET IN THE ROOT OF A 24" PINE TREE

 BM2 ELEVATION = 1955.66
 N 622471 E 564521
 L STATION 13+46.00 68 LEFT
 8" SPIKE SET IN THE ROOT OF A 24" OAK TREE

 BM3 ELEVATION = 1959.29
 N 622400 E 564827
 L STATION 16+49.00 32 RIGHT
 8" SPIKE SET IN THE ROOT OF A 14" WALNUT TREE

NC GRID
 NAD 83/NSRS 2007



| FINAL -L- | | | |
|-----------|----------|-------------|-------------|
| TYPE | STATION | NORTH | EAST |
| POT | 10+00.00 | 622369.4025 | 564180.1097 |
| PC | 10+40.96 | 622374.0503 | 564220.8051 |
| PRC | 10+99.56 | 622381.4468 | 564278.9308 |
| PRC | 13+30.93 | 622401.9291 | 564509.3013 |
| PRC | 15+76.20 | 622424.3825 | 564753.4132 |
| PT | 16+92.94 | 622432.3889 | 564869.7655 |
| POT | 16+94.97 | 622432.3724 | 564871.7995 |

DATUM DESCRIPTION

THE LOCALIZED COORDINATE SYSTEM DEVELOPED FOR THIS PROJECT IS BASED ON THE STATE PLANE COORDINATES ESTABLISHED BY NCDOT FOR MONUMENT "370063 (BL-2)" WITH NAD 83/NSRS 2007 STATE PLANE GRID COORDINATES OF NORTHING: 622580.9150(±) EASTING: 563679.1770(±) ELEVATION: 1948.65(±)

THE AVERAGE COMBINED GRID FACTOR USED ON THIS PROJECT (GROUND TO GRID) IS: 0.999785801

THE N.C. LAMBERT GRID BEARING AND LOCALIZED HORIZONTAL GROUND DISTANCE FROM "370063 (BL-2)" TO -L- STATION 13+50.00 IS S 78°08'58.1" E 867.67'


ALL LINEAR DIMENSIONS ARE LOCALIZED HORIZONTAL DISTANCES VERTICAL DATUM USED IS NAVD 88

GEOID MODEL: G09NC
 NOTE: DRAWING NOT TO SCALE

NOTES:


- THE CONTROL DATA FOR THIS PROJECT CAN BE FOUND ELECTRONICALLY BY SELECTING PROJECT CONTROL DATA AT:
[HTTPS://CONNECT.NCDOT.GOV/RESOURCES/LOCATION](https://connect.ncdot.gov/resources/location)
 THE FILES TO BE FOUND ARE AS FOLLOWS:
 370102_LS_CONTROL.TXT
 - SITE CALIBRATION INFORMATION HAS NOT BEEN PROVIDED FOR THIS PROJECT. IF FURTHER INFORMATION IS NEEDED, PLEASE CONTACT THE LOCATION AND SURVEYS UNIT.
- ⊗ INDICATES GEODETIC CONTROL MONUMENTS USED OR SET FOR HORIZONTAL PROJECT CONTROL BY THE NCDOT LOCATION AND SURVEYS UNIT.
 PROJECT CONTROL ESTABLISHED USING GLOBAL POSITIONING SYSTEM.

3/10/2014
 C:\Rechen\Proj\GR04H0102_1s_1c.dgn
 mltt@field




| PAVEMENT SCHEDULE | |
|-------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| C1 | PROP. APPROX. 3" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 168 LBS. PER SQ. YD. IN EACH OF TWO LAYERS |
| C2 | PROP. VAR. DEPTH ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 112 LBS. PER SQ. YD. PER 1" DEPTH. TO BE PLACED IN LAYERS NOT TO EXCEED 2" IN DEPTH. |
| E1 | PROP. APPROX. 5" ASPHALT CONCRETE BASE COURSE, TYPE B25.0B, AT AN AVERAGE RATE OF 570 LBS. PER SQ. YD. IN EACH OF TWO LAYERS |
| E2 | PROP. VAR. DEPTH ASPHALT CONCRETE BASE COURSE, TYPE B25.0B, AT AN AVERAGE RATE OF 114 LBS. PER SQ. YD. PER 1" DEPTH. TO BE PLACED IN LAYERS NOT LESS THAN 3" IN DEPTH OR GREATER THAN 5 1/2" IN DEPTH. |
| T | EARTH MATERIAL |
| U | EXISTING PAVEMENT |
| W | WEDGING |

NOTE: PAVEMENT EDGE SLOPES ARE 1:1 UNLESS SHOWN OTHERWISE.




TYPICAL SECTION NO. 1

-L- STA. 13+50.00 TO STA. 16+90.00




WEDGING DETAIL




PARTIAL TYPICAL SECTION NO. 1A

USE PARTIAL TYPICAL SECTION No. 1A IN CONJUNCTION WITH TYPICAL SECTION No. 1:


-L- STA. 13+55.63 TO STA. 16+13.38 (TEMPORARY WIDENING FOR TRAFFIC CONTROL)



TEMPORARY UTILITY EASEMENT DETAIL




| -L- | | | |
|--------------------------------------|--------------------------------------|--------------------------------------|--------------------------------------|
| PI Sta 10+70.26 | PI Sta 12+15.34 | PI Sta 14+53.68 | PI Sta 16+34.68 |
| $\Delta = 1^{\circ} 28' 21.0''$ (LT) | $\Delta = 5^{\circ} 48' 52.1''$ (RT) | $\Delta = 6^{\circ} 09' 48.0''$ (LT) | $\Delta = 8^{\circ} 48' 03.9''$ (RT) |
| $D = 2^{\circ} 30' 46.7''$ | $D = 2^{\circ} 30' 46.7''$ | $D = 2^{\circ} 30' 46.7''$ | $D = 7^{\circ} 32' 20.1''$ |
| $L = 58.60'$ | $L = 231.38'$ | $L = 245.26'$ | $L = 116.74'$ |
| $T = 29.30'$ | $T = 115.79'$ | $T = 122.75'$ | $T = 58.49'$ |
| $R = 2,280.00'$ | $R = 2,280.00'$ | $R = 2,280.00'$ | $R = 760.00'$ |



BEGIN PROJECT 17BP.14.R.41
TIE TO PROJECT 17BP.14.R.34
-L- POT STA. 13+50.00

END PROJECT
-L- POT STA. 16+90

GEOTECHNICAL ENGINEER ENGINEER




11/19/13

| GROUNDWATER CONDITION (SEE NOTE 6) | H SHORING HEIGHT (FT) | SLOPE OR SURCHARGE CASE WITH NO TRAFFIC IMPACT | | | | | | SURCHARGE CASE WITH TRAFFIC IMPACT | | | | | |
|--------------------------------------------------------------|-----------------------|------------------------------------------------|--------------------------------------------------------|------------------------------------------------|----------|----------|---------------------------------|--------------------------------------------------------|------------------------------------------------|-----------------------------|----------|--|--|
| | | SHEET PILES | | H-PILES WITH TIMBER LAGGING | | | | SHEET PILES | | H-PILES WITH TIMBER LAGGING | | | |
| | | MINIMUM REQUIRED EMBEDMENT (FT) | MINIMUM REQUIRED SECTION MODULUS (IN ³ /FT) | MINIMUM REQUIRED EMBEDMENT* (FT) (SEE NOTE 10) | | | MINIMUM REQUIRED EMBEDMENT (FT) | MINIMUM REQUIRED SECTION MODULUS (IN ³ /FT) | MINIMUM REQUIRED EMBEDMENT* (FT) (SEE NOTE 10) | | | | |
| | | | | HP 10x42 | HP 12x53 | HP 14x73 | | | HP 10x42 | HP 12x53 | HP 14x73 | | |
| GROUNDWATER ELEVATION BETWEEN BOTTOM OF SHORING AND PILE TIP | < 6 | 11.5 | 4.5 | 11.5 | 11.5 | 11.5 | 16.0 | 12.0 | 13.0 | 13.0 | 13.0 | | |
| | 7 | 13.0 | 7.0 | 13.0 | 13.0 | 13.0 | 17.0 | 14.5 | 14.5 | 14.5 | 14.5 | | |
| | 8 | 15.0 | 10.0 | -- | 15.0 | 15.0 | 18.0 | 17.0 | -- | 15.5 | 15.5 | | |
| | 9 | 17.0 | 14.0 | -- | 17.0 | 17.0 | 19.0 | 20.0 | -- | 17.0 | 17.0 | | |
| | 10 | 18.5 | 19.5 | -- | -- | 18.5 | 20.0 | 23.5 | -- | -- | 18.5 | | |
| | 12 | 22.5 | 33.0 | -- | -- | -- | 22.0 | 33.0 | -- | -- | 21.5 | | |
| GROUNDWATER ELEVATION BELOW PILE TIP | < 6 | 7.5 | 3.0 | 8.0 | 8.0 | 8.0 | 11.0 | 10.0 | 9.5 | 9.5 | 9.5 | | |
| | 7 | 8.5 | 4.5 | 9.5 | 9.5 | 9.5 | 12.0 | 12.0 | 10.5 | 10.5 | 10.5 | | |
| | 8 | 10.0 | 6.5 | 10.5 | 10.5 | 10.5 | 12.5 | 14.0 | 11.5 | 11.5 | 11.5 | | |
| | 9 | 11.0 | 9.5 | -- | 12.0 | 12.0 | 13.5 | 16.5 | -- | 12.5 | 12.5 | | |
| | 10 | 12.5 | 13.0 | -- | -- | 13.5 | 14.0 | 19.5 | -- | 13.5 | 13.5 | | |
| | 12 | 15.0 | 21.5 | -- | -- | 16.0 | 16.0 | 25.5 | -- | -- | 15.5 | | |


- NOTES:**
- AT THE CONTRACTOR'S OPTION, USE STANDARD TEMPORARY SHORING AS NOTED IN THE PLANS.
 - FOR STANDARD TEMPORARY SHORING, SEE STANDARD SHORING PROVISION.
 - STANDARD TEMPORARY SHORING IS BASED ON THE FOLLOWING IN-SITU ASSUMED SOIL PARAMETERS:
UNIT WEIGHT, $\gamma = 120$ LB/CF
FRICTION ANGLE, $\phi = 30$ DEGREES
COHESION, $c = 0$ LB/SF
 - DO NOT USE STANDARD TEMPORARY SHORING IF ASSUMED SOIL PARAMETERS ARE NOT APPLICABLE.
 - DO NOT USE STANDARD TEMPORARY SHORING WHEN VERY LOOSE OR SOFT SOIL OR MUCK IS WITHIN THE EMBEDMENT DEPTH.
 - USE GROUNDWATER ELEVATION NOTED IN THE PLANS. IF NO GROUNDWATER ELEVATION IS SHOWN IN THE PLANS, USE "GROUNDWATER ELEVATION BETWEEN BOTTOM OF SHORING AND PILE TIP" FOR GROUNDWATER CONDITION. DO NOT USE STANDARD TEMPORARY SHORING IF GROUNDWATER IS ABOVE BOTTOM OF SHORING.
 - AT THE CONTRACTOR'S OPTION OR IF AVAILABLE CLEAR DISTANCE IS LESS THAN THE MINIMUM REQUIRED FOR CONCRETE BARRIER, SET BARRIER NEXT TO AND UP AGAINST TRAFFIC SIDE OF PILES AND USE "SURCHARGE CASE WITH TRAFFIC IMPACT".
 - AT THE CONTRACTOR'S OPTION OR IF AVAILABLE CLEAR DISTANCE IS LESS THAN 4' FOR TEMPORARY GUARDRAIL, ATTACH GUARDRAIL TO TRAFFIC SIDE OF PILES AS SHOWN IN THE PLANS AND USE "SURCHARGE CASE WITH TRAFFIC IMPACT".
 - MINIMUM REQUIRED EXTENSION IS 6" FOR "SLOPE OR SURCHARGE CASE WITH NO TRAFFIC IMPACT" AND 32" FOR "SURCHARGE CASE WITH TRAFFIC IMPACT".
 - MINIMUM REQUIRED EMBEDMENT FOR H-PILES WITH TIMBER LAGGING IS BASED ON DRIVEN H-PILES AT MAXIMUM 6' SPACING. AT THE CONTRACTOR'S OPTION, EMBEDMENT DEPTHS MAY BE REDUCED BY 25% FOR DRILLED-IN H-PILES.
 - SUBMIT A "STANDARD TEMPORARY SHORING SELECTION FORM" AT LEAST 7 DAYS BEFORE STARTING TEMPORARY SHORING CONSTRUCTION. UP TO 3 SHORING LOCATIONS MAY BE INCLUDED ON EACH FORM.
 - CONTACT THE ENGINEER IF PILES DO NOT ATTAIN THE MINIMUM REQUIRED EMBEDMENT.

MINIMUM REQUIRED EMBEDMENT AND SECTION MODULUS


***DO NOT USE H-PILES WITH TIMBER LAGGING FOR GROUNDWATER CONDITION, SHORING HEIGHT AND H-PILE SIZE SHOWN IF MINIMUM REQUIRED EMBEDMENT IS "--".**



CONCRETE BARRIER
**TOP OF SHORING = EDGE OF PAVEMENT




TEMPORARY GUARDRAIL
**GUARDRAIL FACE = EDGE OF PAVEMENT




STANDARD TEMPORARY SHORING (SLOPE CASE)
*SEE TABLE ABOVE.

STANDARD TEMPORARY SHORING (SURCHARGE CASE)
*SEE TABLE ABOVE.



AMEC Environment & Infrastructure, Inc.
4021 STIRRUP CREEK DRIVE, SUITE 100
DURHAM, NORTH CAROLINA 27703
NC Engineering F-1253 NC Geology C-247



GEOTECHNICAL ENGINEERING UNIT
STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH

STANDARD DRAWING NO. 1801.01

STANDARD TEMPORARY SHORING

DATE: 1-17-12

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
SUMMARY OF QUANTITIES

| Line Item | Des | Sec No. | Description | Quantity | Unit |
|--------------|-----|---------|--------------------------------------|----------|-------|
| 0000100000-N | | 800 | MOBILIZATION | 1 | LS |
| 0000400000-N | | 801 | CONSTRUCTION SURVEYING | 1 | LS |
| 0043000000-N | | 226 | GRADING | 1 | LS |
| | | | CLEARING AND GRUBBING | 0.78 | ACRES |
| | | | UNCLASSIFIED EXCAVATION | 140 | CY |
| | | | BORROW EXCAVATION | 190 | CY |
| | | | FINE GRADING | 420 | SY |
| | | | REMOVAL OF EXISTING ASPHALT PAVEMENT | 190 | SY |
| 0050000000-E | | 226 | SUPP CLEARING & GRUBBING | 1 | ACRES |
| 0057000000-E | | 226 | UNDERCUT EXCAVATION | 100 | CY |
| 0195000000-E | | 265 | SELECT GRANULAR MATERIAL | 100 | CY |
| 0196000000-E | | 270 | GEOTEXTILE SOIL STABILIZATION | 50 | SY |
| 0199000000-E | | SP | TEMPORARY SHORING | 800 | SF |
| 0318000000-E | | 300 | FND CONDUIT MATL MINOR STRS | 10 | TONS |
| 0320000000-E | | 300 | FND CONDUIT GEOTEXTILE | 20 | SY |
| 0335200000-E | | 305 | 15" DRAINAGE PIPE | 36 | LF |
| 0995000000-E | | 340 | PIPE REMOVAL | 60 | LF |
| 1220000000-E | | 545 | INCIDENTAL STONE BASE | 100 | TONS |
| 1489000000-E | | 610 | ASP CONC BASE CRS B25.0B | 140 | TONS |
| 1519000000-E | | 610 | ASP CONC SURF CRS S9.5B | 160 | TONS |
| 1575000000-E | | 620 | ASP FOR PLANT MIX | 20 | TONS |
| 2000000000-N | | 806 | RIGHT OF WAY MARKERS | 5 | EA |
| 4155000000-N | | 907 | DISPOSE SIGN SYST U-CHAN | 3 | EA |
| 4400000000-E | | 1110 | WORK ZONE SIGNS (STAT) | 164 | SF |
| 4405000000-E | | 1110 | WORK ZONE SIGNS (PORTABLE) | 96 | SF |
| 4410000000-E | | 1110 | WORK ZONE SIGNS (BARR) | 36 | SF |
| 4430000000-N | | 1130 | DRUMS | 25 | EA |
| 4435000000-N | | 1135 | CONES | 30 | EA |
| 4445000000-E | | 1145 | BARRICADES (TYPE III) | 32 | LF |
| 4450000000-N | | 1150 | FLAGGER | 48 | HR |
| 4465000000-N | | 1160 | TEMPORARY CRASH CUSHIONS | 4 | EA |
| 4470000000-N | | 1160 | RESET CRASH CUSHION | 2 | EA |

| | | | | | |
|--------------|--|------|-----------------------------------------------------|-------|-------|
| 4485000000-N | | 1170 | PORT CONC BARRIER | 16 | LF |
| 4490000000-E | | 1170 | PORT CONC BARRIER(ANCHR) | 280 | LF |
| 4505000000-E | | 1170 | RESET PORT CONC BARR,ANCH | 100 | LF |
| 4600000000-N | | SP | GENERIC TRAFFIC CONTROL ITEM (TEMP SIGNAL SYSTEM) | 1 | EA |
| 4795000000-E | | 1205 | COLD APPLIED PLASTIC (24") TYPE 4 - REMOVEABLE TAPE | 20 | LF |
| 4810000000-E | | 1205 | PAINT PVMT MARKINGS 4" | 4120 | LF |
| 4915000000-E | | 1264 | 7' U-CHANNEL POSTS | 4 | EA |
| 4957000000-N | | 1264 | OBJECT MARKERS (TYPE 3) | 4 | EA |
| 6000000000-E | | 1605 | TEMPORARY SILT FENCE | 765 | LF |
| 6012000000-E | | 1610 | SEDIMENT CONTROL STONE | 55 | TONS |
| 6009000000-E | | 1610 | EROS CONTRL STONE CL B | 10 | TONS |
| 6015000000-E | | 1615 | TEMPORARY MULCHING | 0.78 | ACR |
| 6018000000-E | | 1620 | SEED FOR TEMP SEEDING | 50 | LB |
| 6021000000-E | | 1620 | FERT FOR TEMP SEEDING | 0.25 | TONS |
| 6024000000-E | | 1622 | TEMPORARY SLOPE DRAINS | 200 | LF |
| 6029000000-E | | SP | SAFETY FENCE | 100 | LF |
| 6030000000-E | | 1630 | SILT EXCAVATION | 20 | CY |
| 6036000000-E | | 1631 | MATting FOR EROS CONTROL | 3800 | SY |
| 6042000000-E | | 1632 | 1/4" HARDWARE CLOTH | 70 | LF |
| 6045000000-E | | SP | 24" TEMPORARY PIPE | 114 | LF |
| 6070000000-N | | 1639 | SPECIAL STILLING BASINS | 2 | EA |
| 6084000000-E | | 1660 | SEEDING AND MULCHING | 0.78 | ACRES |
| 6090000000-E | | 1661 | SEED FOR REPAIR SEEDING | 50 | LB |
| 6093000000-E | | 1661 | FERT FOR REPAIR SEEDING | 0.25 | TONS |
| 6096000000-E | | 1662 | SEED FOR SUPP SEEDING | 50 | LB |
| 6108000000-E | | 1665 | FERTILIZER TOPDRESSING | 0.5 | TONS |
| 6117000000-N | | SP | RESPONSE FOR EROS CONTROL | 13 | EA |
| 8035000000-N | | 402 | REMOVAL OF EXISTING STRUCTURE | 1 | LS |
| 8126000000-N | | 414 | CULVERT EXCAVATION, STA 11+04.50 | 1 | LS |
| 8133000000-E | | 414 | FOUNDATION CONDITIONING MATERIAL, BOX CULVERT | 64 | TONS |
| 8196000000-E | | 420 | CLASS A CONCRETE (CULVERT) | 92.3 | CY |
| 8245000000-E | | 425 | REINFORCING STEEL (CULVERT) | 11369 | LBS |
| 8590000000-E | | 876 | RIP RAP, CLASS I | 60 | TONS |
| 8622000000-E | | 876 | GEOTEXTILE FOR DRAINAGE | 72 | SY |

EARTHWORK SUMMARY (CY)

| LOCATION | UNCLASSIFIED EXCAVATION | EMBT + % | BORROW | WASTE |
|-------------------------------------------------|-------------------------|----------|--------|-------|
| TEMPORARY WIDENING (PHASE I) | | | | |
| -L- STA. 13+50.00 TO -L- STA. 16+50.00 | 74 | 250 | 176 | |
| SUBTOTAL SUMMARY | 74 | 250 | 176 | |
| -L- FINAL/TEMPORARY WIDENING REMOVAL (PHASE II) | | | | |
| -L- STA. 14+00.00 TO -L- STA. 15+50.00 | 60 | | | 60 |
| SUBTOTAL SUMMARY | 60 | | | 60 |
| WASTE IN LIEU OF BORROW | | | | |
| PROJECT TOTAL | 134 | 250 | 176 | 60 |
| ESTIMATE 5% FOR TOPSOIL ON BORROW PITS | | | | |
| | | | 9 | |
| GRAND TOTAL | 134 | 250 | 185 | 60 |
| SAY | 140 | | 190 | |

CONTINGENCY ITEMS:
 UNDERCUT EXCAVATION - 100 CY
 SELECT GRANULAR MATERIAL - 100 TONS

SUMMARY OF EXISTING ASPHALT PAVEMENT REMOVAL

| LINE | STATION | STATION | LOCATION | SY |
|--------------------------|------------|------------|----------|--------|
| -L- (TEMPORARY WIDENING) | 13 + 50.00 | 16 + 90.00 | RT | 188.89 |
| | | | SAY | 190 |

NOTE: Earthwork quantities are calculated by the Roadway Design Unit. These earthwork quantities are based in part on subsurface data provided by the Geotechnical Engineering Unit.

Approximate quantities only. Unclassified Excavation, Borrow Excavation, Shoulder Borrow, Fine Grading, Clearing and Grubbing, Breaking of Existing Pavement, and Removal of Existing Pavement will be paid for at the contract lump sum price for "Grading".

NOTE: Invert Elevations are for Bid Purposes only and shall not be used for project construction stakeout. See "Standard Specifications For Roads and Structures, Section 300-5".

LIST OF PIPES, ENDWALLS, ETC. (FOR PIPES 48" & UNDER)

| STATION | LOCATION (L, RT, OR CU) | STRUCTURE NO. | TOP ELEVATION | INVERT ELEVATION | SLOPE CRITICAL | DRAINAGE PIPE (RCP, CSP, CAAP, HDPE, or PVC) | | | | C.S. PIPE (UNLESS NOTED OTHERWISE) | | | | CLASS III R.C. PIPE (UNLESS OTHERWISE NOTED) | | | | ENDWALLS | QUANTITIES FOR DRAINAGE STRUCTURES * TOTAL L.F. FOR PAY QUANTITY SHALL BE COL. 'A' + (.13 X COL.'B') | FRAME, GRATES AND HOOD STANDARD 840.03 | TYPE OF GRATE | CORR. STEEL ELBOWS NO. & SIZE | CONC. COLLARS CL. "B" C.Y. STD 840.72 | CONC. & BRICK PIPE PLUG, C.Y. STD. 840.71 | PIPE REMOVAL LIN. FT. | REMARKS | ABBREVIATIONS | | | | | | | | |
|-----------------|-------------------------|---------------|---------------|------------------|----------------|----------------------------------------------|-----|-----|-----|------------------------------------|-----|-----|-----|----------------------------------------------|-----|-----|-----|----------|------------------------------------------------------------------------------------------------------------|----------------------------------------|---------------|-------------------------------|---------------------------------------|-------------------------------------------|-----------------------|---------|---------------|-----|-----|-----|-----|-----|-----|-----|-----|
| | | | | | | 12" | 15" | 18" | 24" | 30" | 36" | 42" | 48" | 12" | 15" | 18" | 24" | | | | | | | | | | | 30" | 36" | 42" | 48" | 12" | 15" | 18" | 24" |
| 16+00 | RT | 1 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 16+45 | RT | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| PROJECT TOTALS: | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| SAY | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |

6/21/00
 11/2/2013
 U:\Roadway\Proje\GRAHAM\102_rdy_psh3A.dgn

BEGIN PROJECT 17BP.14.R.41
TIE TO PROJECT 17BP.14.R.34
-L- POT STA. 13+50.00

M. DENISE & V. GRANT BURKE JR.

BM #2
 -BL- STA. 18+31.00
 80' LEFT
 ELEV. = 1955.66'

001
 GRANT BURKE


END PROJECT
-L- POT STA. 16+90

Rita Haney

POT Sta. 16+94.97

PT Sta. 16+92.94

| | |
|---------------------------------------|---------------------|
| PROJECT REFERENCE NO. 17BP.14.R.41 | SHEET NO. 4 |
| RW SHEET NO. | |
| ROADWAY DESIGN ENGINEER | HYDRAULICS ENGINEER |
| | |




| | | | |
|---------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------|
| PI Sta 10+70.26 Δ = 1' 28" 21.0" (LT) D = 2' 30" 46.7" L = 58.60' T = 29.30' R = 2,280.00' e = NC | PI Sta 12+15.34 Δ = 5' 48" 52.1" (RT) D = 2' 30" 46.7" L = 231.38' T = 115.79' R = 2,280.00' e = NC | PI Sta 14+53.68 Δ = 6' 09" 48.0" (LT) D = 2' 30" 46.7" L = 245.26' T = 122.75' R = 2,280.00' e = NC | PI Sta 16+34.68 Δ = 8' 48" 03.9" (RT) D = 7' 32" 20.1" L = 116.74' T = 58.49' R = 760.00' e = NC |
|---------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------|

REVISIONS


003
 JOHNNY M. COLLINS

NOTE: SEE SHEETS C-1 THROUGH C-5 FOR CULVERT PLANS
 NOTE: SEE 2-A FOR REQUIRED TEMPORARY UTILITY EASEMENT




CULVERT HYDRAULIC DATA

| | | | |
|-----------------------|---|---------|-----|
| DESIGN DISCHARGE | = | 700 | CFS |
| DESIGN FREQUENCY | = | 25 | YRS |
| DESIGN HW ELEVATION | = | 1959.2 | FT |
| BASE DISCHARGE | = | 1230 | CFS |
| BASE FREQUENCY | = | 100 | YRS |
| BASE HW ELEVATION | = | 1959.87 | FT |
| OVERTOPPING DISCHARGE | = | 500 | CFS |
| OVERTOPPING FREQUENCY | = | 25 | YRS |
| OVERTOPPING ELEVATION | = | 1959.2 | FT |



FROM STA. 15+00 TO STA. 15+50 RT -L-

5/14/99



TEMPORARY WIDENING DETAIL

NOTE: SEE TRAFFIC MANAGEMENT PLANS FOR PROPOSED LANE GEOMETRY FOR THE PHASED CULVERT CONSTRUCTION


11/22/2013
 C:\design\17BP14.R.41\Roadway\Proj\GRAHAM102_rdy_psh_5_detail.dgn
 mlh:shf:ld

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS


TRANSPORTATION MANAGEMENT PLAN

GRAHAM COUNTY

DIVISION 14



BRIDGE #102 – E. Buffalo Road (SR 1254) over E. Buffalo Creek




VICINITY MAP

INDEX OF SHEETS


| SHEET NO. | TITLE |
|-----------|----------------------------------------------------------|
| TMP-1 | TITLE SHEET, VICINITY MAP, AND INDEX OF SHEETS |
| TMP-1A | LEGEND AND LIST OF ROADWAY STANDARD DRAWINGS |
| TMP-2 | GENERAL NOTES |
| TMP-2A | PORTABLE CONCRETE BARRIER AT TEMPORARY SHORING LOCATIONS |
| TMP-3 | PHASING |
| TMP-4 | PHASE I |
| TMP-5 | PHASE II |

SHEET NO.
TMP-1

WBS 17BP.14.R.41



PLAN PREPARED FOR NCDOT DIVISION 14




PLAN PREPARED BY:
Stantec Consulting Services Inc.
801 Jones Franklin Road-Suite 300
Raleigh, NC 27606

Tel. 919.851.8866
Fax. 919.851.7024
www.stantec.com

BETSY L. WATSON, P.E. TRAFFIC ENGINEER
GEORGE KARAGEORGE WORK ZONE TRANSPORTATION DESIGN MANAGER
BRIAN LATON, E.I. TRANSPORTATION DESIGNER

APPROVED: *Betsy L. Watson*
DATE: 11/26/13




ROADWAY STANDARD DRAWINGS

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" - PROJECT SERVICES UNIT - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2012 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

| STD. NO. | TITLE |
|----------|-----------------------------------------------------|
| 1101.01 | WORK ZONE ADVANCE WARNING SIGNS |
| 1101.02 | TEMPORARY LANE CLOSURES |
| 1101.04 | TEMPORARY SHOULDER CLOSURES |
| 1101.11 | TRAFFIC CONTROL DESIGN TABLES |
| 1110.01 | STATIONARY WORK ZONE SIGNS |
| 1110.02 | PORTABLE WORK ZONE SIGNS |
| 1130.01 | DRUMS |
| 1135.01 | CONES |
| 1150.01 | FLAGGING DEVICES |
| 1160.01 | TEMPORARY CRASH CUSHION |
| 1165.01 | WORK VEHICLE LIGHTING SYSTEMS AND TMA DELINEATION |
| 1170.01 | PORTABLE CONCRETE BARRIER |
| 1205.01 | PAVEMENT MARKINGS - LINE TYPES AND OFFSETS |
| 1205.02 | PAVEMENT MARKINGS - TWO LANE AND MULTILANE ROADWAYS |
| 1205.12 | PAVEMENT MARKINGS - BRIDGES |

LEGEND

- EXIST. PVMT.
- PROPOSED PVMT.
- DIRECTION OF TRAFFIC FLOW
- DIRECTION OF PEDESTRIAN TRAFFIC FLOW
- WORK AREA
- PAVEMENT REMOVAL
- TYPE III BARRICADE
- CONE
- DRUM
- SKINNY DRUM
- TUBULAR MARKER
- CHANGEABLE MESSAGE SIGN (CMS)
- FLAGGER
- AUTOMATED FLAGGER ASSISTANCE DEVICE (AFAD)
- FLASHING ARROW BOARD (TYPE C)
- LAW ENFORCEMENT
- TRUCK MOUNTED ATTENUATOR (TMA)
- WORK ZONE SIGN-PORTABLE
- WORK ZONE SIGN-STATIONARY
- WORK ZONE SIGN-STATIONARY OR PORTABLE
- TEMPORARY SHORING
- TEMPORARY CRASH CUSHION
- ANCHORED PORTABLE CONCRETE BARRIER



SIGNALS

- EXISTING
- PROPOSED
- TEMPORARY
- PORTABLE TEMPORARY

PAVEMENT MARKINGS

- DOUBLE YELLOW CENTER LINE
- SKIP LINES
- MINI-SKIP LINES
- SOLID LINES
- EXISTING PAVEMENT MARKING (GRAY)

PAVEMENT MARKERS

- CRYSTAL / CRYSTAL
- CRYSTAL / RED
- YELLOW / YELLOW

PAVEMENT MARKING SYMBOLS

- PAVEMENT MARKING SYMBOLS
- EXISTING PAVEMENT MARKING SYMBOLS (HOLLOW)
- ONLY PAVEMENT MARKING ALPHANUMERIC CHARACTERS

11/20/2013 U:\CG\dm02\TrafficControl\TCP\Plan Sheets\17BP.14.R.41.TC.TMP.01A.RD.WYSTD.SLEGEND.dgn

| | | | | |
|--|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------|--|------------------------------------------|
| | Stantec Consulting Services Inc. 801 Jones Franklin Road Suite 300 Raleigh, NC 27606 Tel. (919) 851-6866 Fax. (919) 851-7024 www.stantec.com License No. F-0672 | APPROVED: <i>Betsy L. Watson</i> DATE: 11/26/13 | | LEGEND & ROADWAY STANDARD DRAWINGS |
| | | | | |

GENERAL NOTES

THE FOLLOWING GENERAL NOTES APPLY AT ALL TIMES FOR THE DURATION OF THE PROJECT EXCEPT WHEN OTHERWISE NOTED IN THE PLAN OR DIRECTED BY THE ENGINEER.

CHANGES MAY BE REQUIRED WHEN PHYSICAL DIMENSIONS IN THE DETAIL DRAWINGS, STANDARD DETAILS, AND ROADWAY DETAILS ARE NOT ATTAINABLE TO MEET FIELD CONDITIONS OR RESULT IN DUPLICATE OR UNDESIRABLE OVERLAPPING OF DEVICES. MODIFICATION MAY INCLUDE: MOVING, SUPPLEMENTING, COVERING, OR REMOVAL OF DEVICES AS DIRECTED BY THE ENGINEER.

LANE AND SHOULDER CLOSURE REQUIREMENTS

- A) REMOVE LANE CLOSURE DEVICES FROM THE LANE WHEN WORK IS NOT BEING PERFORMED BEHIND THE LANE CLOSURE OR WHEN A LANE CLOSURE IS NO LONGER NEEDED OR AS DIRECTED BY THE ENGINEER.
- B) WHEN PERSONNEL AND/OR EQUIPMENT ARE WORKING WITHIN 15 FT OF AN OPEN TRAVEL LANE, CLOSE THE NEAREST OPEN SHOULDER USING ROADWAY STANDARD DRAWING NO. 1101.04 UNLESS THE WORK AREA IS PROTECTED BY BARRIER OR GUARDRAIL OR A LANE CLOSURE IS INSTALLED.
- C) WHEN PERSONNEL AND/OR EQUIPMENT ARE WORKING ON THE SHOULDER ADJACENT TO AN UNDIVIDED FACILITY AND WITHIN 5 FT OF AN OPEN TRAVEL LANE, CLOSE THE NEAREST OPEN TRAVEL LANE USING ROADWAY STANDARD DRAWING NO. 1101.02 UNLESS THE WORK AREA IS PROTECTED BY BARRIER OR GUARDRAIL.
- D) WHEN PERSONNEL AND/OR EQUIPMENT ARE WORKING WITHIN A LANE OF TRAVEL OF AN UNDIVIDED OR DIVIDED FACILITY, CLOSE THE LANE ACCORDING TO THE TRANSPORTATION MANAGEMENT PLANS, ROADWAY STANDARD DRAWINGS, OR AS DIRECTED BY THE ENGINEER. CONDUCT THE WORK SO THAT ALL PERSONNEL AND/OR EQUIPMENT REMAIN WITHIN THE CLOSED TRAVEL LANE.
- E) DO NOT WORK SIMULTANEOUSLY WITHIN 15 FT ON BOTH SIDES OF AN OPEN TRAVELWAY, RAMP, OR LOOP WITHIN THE SAME LOCATION UNLESS PROTECTED WITH GUARDRAIL OR BARRIER.

PAVEMENT EDGE DROP OFF REQUIREMENTS

- F) BACKFILL AT A 6:1 SLOPE UP TO THE EDGE AND ELEVATION OF EXISTING PAVEMENT IN AREAS ADJACENT TO AN OPEN TRAVEL LANE THAT HAS A DROP-OFF AS FOLLOWS:
 - BACKFILL DROP-OFFS THAT EXCEED 2 INCHES ON ROADWAYS WITH POSTED SPEED LIMITS OF 45 MPH OR GREATER.
 - BACKFILL DROP-OFFS THAT EXCEED 3 INCHES ON ROADWAYS WITH POSTED SPEED LIMITS LESS THAN 45 MPH.
 - BACKFILL WITH SUITABLE COMPACTED MATERIAL, AS APPROVED BY THE ENGINEER, AT NO EXPENSE TO THE DEPARTMENT.

TRAFFIC PATTERN ALTERATIONS

- G) NOTIFY THE ENGINEER TWENTY ONE (21) CALENDAR DAYS PRIOR TO ANY TRAFFIC PATTERN ALTERATION.

SIGNING

- H) INSTALL ADVANCE WORK ZONE WARNING SIGNS WHEN WORK IS WITHIN 40 FT FROM THE EDGE OF TRAVEL LANE AND NO MORE THAN THREE (3) DAYS PRIOR TO THE BEGINNING OF CONSTRUCTION.
- I) ENSURE ALL NECESSARY SIGNING IS IN PLACE PRIOR TO ALTERING ANY TRAFFIC PATTERN.
- J) INSTALL BLACK ON ORANGE "DIP" SIGNS (W8-2) AND/OR "BUMP" SIGNS (W8-1) 500 FT IN ADVANCE OF THE UNEVEN AREA, OR AS DIRECTED BY THE ENGINEER.

TEMPORARY SHORING

- K) FOR TEMPORARY SHORING, SEE TEMPORARY SHORING SPECIAL PROVISION.
- L) FOR CONTRACTOR DESIGNED SHORING, SURVEY THE SHORING LOCATION TO DETERMINE EXISTING ELEVATIONS AND ACTUAL DESIGN HEIGHTS BEFORE BEGINNING DESIGN.
- M) WHEN USING CONTRACTOR DESIGNED SHORING USE THE SOIL PARAMETERS SPECIFIED IN THE TEMPORARY SHORING SPECIAL PROVISION AND DETAILS.
- N) NO SUBSURFACE INFORMATION IS AVAILABLE IN THE VICINITY OF THE TEMPORARY SHORING. THE INFORMATION PROVIDED FOR DESIGN WAS ASSUMED AND MAY NOT BE APPLICABLE TO THE ACTUAL SITE CONDITIONS ENCOUNTERED DURING CONSTRUCTION.

TRAFFIC BARRIER

- O) INSTALL TEMPORARY BARRIER ACCORDING TO THE TRANSPORTATION MANAGEMENT PLANS A MAXIMUM OF TWO (2) WEEKS PRIOR TO BEGINNING WORK IN ANY LOCATION. ONCE TEMPORARY BARRIER IS INSTALLED AT ANY LOCATION PROCEED IN A CONTINUOUS MANNER TO COMPLETE THE PROPOSED WORK IN THAT LOCATION UNLESS OTHERWISE STATED IN THE TRANSPORTATION MANAGEMENT PLANS OR AS DIRECTED BY THE ENGINEER.

DO NOT PLACE BARRIER DIRECTLY ON ANY SURFACE OTHER THAN ASPHALT OR CONCRETE.

ONCE TEMPORARY BARRIER IS INSTALLED AT ANY LOCATION AND NO WORK IS PERFORMED BEHIND THE TEMPORARY BARRIER FOR A PERIOD LONGER THAN TWO (2) MONTHS, REMOVE/RESET TEMPORARY BARRIER AT NO COST TO THE DEPARTMENT UNLESS OTHERWISE STATED IN THE TRANSPORTATION MANAGEMENT PLANS, TEMPORARY BARRIER IS PROTECTING A HAZARD, OR AS DIRECTED BY THE ENGINEER.

INSTALL TEMPORARY BARRIER WITH THE TRAFFIC FLOW BEGINNING WITH THE UPSTREAM SIDE OF TRAFFIC. REMOVE TEMPORARY BARRIER AGAINST THE TRAFFIC FLOW BEGINNING WITH THE DOWNSTREAM SIDE OF TRAFFIC.

INSTALL AND SPACE DRUMS NO GREATER THAN TWICE THE POSTED SPEED LIMIT (MPH) TO CLOSE OR KEEP THE SECTION OF THE ROADWAY CLOSED UNTIL THE TEMPORARY BARRIER CAN BE PLACED OR AFTER THE TEMPORARY BARRIER IS REMOVED.

- P) PROTECT THE APPROACH END OF MOVABLE/PORTABLE CONCRETE BARRIER AT ALL TIMES DURING THE INSTALLATION AND REMOVAL OF THE BARRIER BY EITHER A TRUCK MOUNTED ATTENUATOR (MAXIMUM 72 HOURS) OR A TEMPORARY CRASH CUSHION.

PROTECT THE APPROACH END OF MOVABLE/PORTABLE CONCRETE BARRIER FROM ONCOMING TRAFFIC AT ALL TIMES BY A TEMPORARY CRASH CUSHION UNLESS THE APPROACH END OF MOVABLE/PORTABLE CONCRETE BARRIER IS OFFSET FROM ONCOMING TRAFFIC AS FOLLOWS OR AS SHOWN IN THE PLANS:

| POSTED SPEED LIMIT | MINIMUM OFFSET |
|--------------------|----------------|
| 40 OR LESS | 15 FT |
| 45-50 | 20 FT |
| 55 | 25 FT |
| 60 MPH or HIGHER | 30 FT |

PAVEMENT MARKINGS AND MARKERS

- Q) INSTALL TEMPORARY PAVEMENT MARKINGS AND TEMPORARY PAVEMENT MARKERS ON INTERIM LAYERS OF PAVEMENT AS FOLLOWS:




| ROAD NAME | MARKING | MARKER |
|---------------------------------|---------|--------|
| SR 1254 (EAST BUFFALO CREEK RD) | PAINT | NONE |

- R) PLACE ONE APPLICATION OF PAINT FOR TEMPORARY TRAFFIC PATTERNS. PLACE A SECOND APPLICATION OF PAINT SIX (6) MONTHS AFTER THE INITIAL APPLICATION AND EVERY SIX MONTHS AS DIRECTED BY THE ENGINEER.
- S) TIE PROPOSED PAVEMENT MARKING LINES TO EXISTING PAVEMENT MARKING LINES.
- T) REMOVE/REPLACE ANY CONFLICTING/DAMAGED PAVEMENT MARKINGS AND MARKERS BY THE END OF EACH DAY'S OPERATION.

MISCELLANEOUS

- U) IN THE EVENT A TIE-IN CANNOT BE MADE IN ONE DAY'S TIME, BRING THE TIE-IN AREA TO AN APPROPRIATE ROADWAY ELEVATION AS DETERMINED BY THE ENGINEER. PLACE BLACK ON ORANGE "LOOSE GRAVEL" SIGNS (W8-7) AND BLACK ON ORANGE "PAVEMENT ENDS" SIGNS (W8-3) (250 FT) AND (500 FT) RESPECTIVELY IN ADVANCE OF THE UNEVEN AREAS. USE DRUMS TO DELINEATE THE EDGE OF ROADWAY ALONG UNPAVED AREAS.
- V) MAINTAIN VEHICULAR ACCESS TO ALL DRIVEWAYS DURING THE LIFE OF THE CONTRACT, UNLESS OTHERWISE NOTED IN THE PHASING OR DIRECTED BY THE ENGINEER. USE INCIDENTAL STONE WHEN NECESSARY.

11/20/2013 10:41:02 AM U:\Graham\02_TrafficControl\TCP\Plan_Sheets\17BP.14.R.41_TC_TMP_02_GENERALNOTES.dgn

| | | | | |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------|---------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------|---------------|
|  <p>Stantec Consulting Services Inc. 801 Jones Franklin Road Suite 300 Raleigh, NC 27606 Tel. (919) 851-6866 Fax. (919) 851-7024 www.stantec.com License No. F-0672</p> | APPROVED <i>Betsy L. Watson</i> DATE: 11/20/13 |  |  | GENERAL NOTES |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------|---------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------|---------------|




FIGURE A

NOTES

- 1- REFER TO THE TRAFFIC CONTROL PLANS FOR TEMPORARY SHORING LOCATIONS AND NOTES.
- 2- REFER TO THE "TEMPORARY SHORING" PROJECT SPECIAL PROVISION FOR INFORMATION ABOUT TEMPORARY SHORING AND PORTABLE CONCRETE BARRIER (PCB).
- 3- PCB IS REQUIRED IF TEMPORARY SHORING IS LOCATED WITHIN THE CLEAR ZONE IN ACCORDANCE WITH THE AASHTO ROADSIDE DESIGN GUIDE. DO NOT PLACE BARRIER DIRECTLY ON ANY SURFACE OTHER THAN ASPHALT OR CONCRETE. (CONTACT NCDOT PAVEMENT MANAGEMENT UNIT FOR APPLICABLE PAVEMENT DESIGN).
- 4- BASED ON THE CLEAR DISTANCE, OFFSET, DESIGN SPEED AND PAVEMENT TYPE, CHOOSE AN UNANCHORED OR ANCHORED PCB FROM THE TABLE SHOWN IN FIGURE B. CLEAR DISTANCE IS DEFINED AS SHOWN IN FIGURE A AND OFFSET IS DEFINED AS SHOWN IN FIGURE B.
- 5- AT THE CONTRACTOR'S OPTION OR IF THE MINIMUM REQUIRED CLEAR DISTANCE IS NOT AVAILABLE, SET PCB NEXT TO AND UP AGAINST THE TRAFFIC SIDE OF THE TEMPORARY SHORING EXCEPT FOR BARRIER ABOVE TEMPORARY WALLS. PCB WITH THE MINIMUM REQUIRED CLEAR DISTANCE IS REQUIRED ABOVE TEMPORARY WALLS.
- 6- USE NCDOT PORTABLE CONCRETE BARRIER (PCB) IN ACCORDANCE WITH ROADWAY STANDARD DRAWING NO. 1170.01 AND SECTION 1170 OF THE STANDARD SPECIFICATIONS.
- 7- PCB REQUIREMENTS FOR TEMPORARY WALLS APPLY TO TEMPORARY MECHANICALLY STABILIZED EARTH (MSE) WALLS AND TEMPORARY SOIL NAIL WALLS.
- 8- SET PCB WITH A MINIMUM HORIZONTAL DISTANCE OF 2 FT BETWEEN THE FRONT FACE OF THE BARRIER AND THE EDGE OF THE NEAREST TRAFFIC LANE AS SHOWN IN FIGURE A UNLESS OTHERWISE SHOWN IN THE PLANS AND OR AS APPROVED BY THE ENGINEER.
- 9- FOR PCB ABOVE AND BEHIND TEMPORARY WALLS, PROVIDE A MINIMUM DISTANCE OF 3 FT BETWEEN THE EDGE OF PAVEMENT AND THE WALL FACE AS SHOWN IN FIGURE A. IF THESE MINIMUM REQUIRED DISTANCES ARE NOT AVAILABLE, CONTACT THE ENGINEER.
- 10- TABLE SHOWN IN FIGURE B IS BASED ON NCDOT RESEARCH PROJECT NO. 2005-010 WITH VEHICLE TYPE USED FOR NCHRP 350 CRASH TESTS. BARRIER DEFLECTIONS AND RESULTING MINIMUM REQUIRED CLEAR DISTANCES MIGHT VARY SIGNIFICANTLY FOR LARGER HEAVIER VEHICLES, RUNS OF BARRIER LESS THAN 200 FT IN LENGTH AND WET OR DRY PAVEMENT.

MINIMUM REQUIRED CLEAR DISTANCE, inches

| Barrier Type | Pavement Type | Offset * ft | Design Speed, mph | | | | | |
|----------------|--------------------------------------------|----------------|--------------------------|-------|-------|-------|-------|-------|
| | | | <30 | 31-40 | 41-50 | 51-60 | 61-70 | 71-80 |
| Unanchored PCB | Asphalt | <8 | 24 | 26 | 29 | 32 | 36 | 40 |
| | | 8-14 | 26 | 28 | 31 | 35 | 38 | 42 |
| | | 14-20 | 27 | 29 | 34 | 36 | 39 | 43 |
| | | 20-26 | 28 | 31 | 35 | 38 | 40 | 44 |
| | | 26-32 | 29 | 32 | 36 | 39 | 42 | 45 |
| | | 32-38 | 30 | 34 | 38 | 41 | 43 | 46 |
| | | 38-44 | 31 | 34 | 41 | 43 | 45 | 48 |
| | | 44-50 | 31 | 35 | 41 | 43 | 46 | 49 |
| | | 50-56 | 32 | 36 | 42 | 44 | 47 | 50 |
| | >56 | 32 | 36 | 42 | 45 | 47 | 51 | |
| | Concrete | <8 | 17 | 18 | 21 | 22 | 25 | 26 |
| | | 8-14 | 19 | 20 | 23 | 25 | 26 | 29 |
| | | 14-20 | 22 | 22 | 24 | 26 | 28 | 31 |
| | | 20-26 | 23 | 24 | 26 | 27 | 30 | 34 |
| | | 26-32 | 24 | 25 | 27 | 28 | 32 | 35 |
| | | 32-38 | 24 | 26 | 27 | 30 | 33 | 36 |
| | | 38-44 | 25 | 26 | 28 | 30 | 34 | 37 |
| | | 44-50 | 26 | 26 | 28 | 32 | 35 | 37 |
| 50-56 | | 26 | 26 | 28 | 32 | 35 | 38 | |
| >56 | 26 | 27 | 29 | 32 | 36 | 38 | | |
| Anchored PCB | Asphalt | All Offsets | 24 for All Design Speeds | | | | | |
| Anchored PCB | Concrete (including bridge approach slabs) | All Offsets | 12 for All Design Speeds | | | | | |

* See Figure Below





FIGURE B

DETAIL PROVIDED BY NCDOT



PORTABLE CONCRETE BARRIER AT TEMPORARY SHORING LOCATIONS

11/20/2013 11:56:41 AM C:\Users\m02\TrafficControl\TCP\Plan Sheets\17BP.14.R.41.TC_TMP_02A_PCB_AT_SHORING.dgn

PHASING

PHASE I

STEP 1:

INSTALL WORK ZONE ADVANCE WARNING SIGNS PER SHEET TMP-4 AND ROADWAY STANDARD DRAWING 1101.01 SHEET 3.

STEP 2:

USING A FLAGGING OPERATION PER ROADWAY STANDARD DRAWING 1101.02 SHEET 1, INSTALL ANCHORED TEMPORARY BARRIER AND CRASH CUSHIONS.

STEP 3:

CONSTRUCT CULVERT STAGE I AND APPROACHES UP TO BUT NOT INCLUDING THE FINAL LAYER OF SURFACE COURSE. SEE TMP-4.

PHASE II

STEP 1:

USING A FLAGGING OPERATION PER ROADWAY STANDARD DRAWING 1101.02 SHEET 1, REMOVE AND RESET PREVIOUSLY PLACED PORTABLE CONCRETE BARRIER AND CRASH CUSHIONS. PLACE MARKINGS, IMPLEMENT TEMPORARY TRAFFIC SIGNAL, AND SHIFT SR 1254 TRAFFIC ONTO THE PORTION OF THE COMPLETED CULVERT (STAGE I). SEE TMP-5.

STEP 2:

REMOVE EXISTING BRIDGE AND CONSTRUCT REMAINING CULVERT AND APPROACHES UP TO BUT NOT INCLUDING THE FINAL LAYER OF SURFACE COURSE (STAGE II) SEE TMP-5.

STEP 3:



USING A FLAGGING OPERATION PER ROADWAY STANDARD DRAWING 1101.02 SHEET 1, REMOVE TEMPORARY BARRIER AND PAVE THE FINAL LAYER OF SURFACE COURSE AND PLACE FINAL MARKINGS.

I:\2013\17BP.14.R.41\TrafficControl\Plan Sheets\17BP.14.R.41_TC_TMP_03_PHASING.dgn
 Diaton




Stantec

Stantec Consulting Services Inc.
 801 Jones Franklin Road
 Suite 300
 Raleigh, NC 27606
 Tel. (919) 851-6866
 Fax. (919) 851-7024
 www.stantec.com
 License No. F-0672

APPROVED: *Patsy L. Watson* DATE: 1/22/13





PHASING



11/20/2013
U:\Graham\02_Traffic\TrafficControl\TCP\Plan Sheets\17BP.14.R.41_TC_TMP_04_PHASE1.dgn
D:\ton

| | | | |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------|----------------|
| <p>Stantec</p> <p>Stantec Consulting Services Inc. 801 Jones Franklin Road Suite 300 Raleigh, NC 27806 Tel. (919) 851-6886 Fax. (919) 851-7024 www.stantec.com License No. F-0672</p> | <p>APPROVED: <i>Betsy L. Watson</i> DATE: 11/20/13</p> <p>SEAL</p> <p>PROFESSIONAL ENGINEER SEAL 29449 BETSY L. WATSON</p> | <p>DIVISION OF HIGHWAYS STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION WORK ZONE TRAFFIC CONTROL</p> | <p>PHASE I</p> |
| | <p>MATCHLINE - SEE BELOW</p> | | |



MATCHLINE - SEE ABOVE

MATCHLINE - SEE BELOW

11/20/2013
U:\Graham\02\TrafficControl\TCP\Plan_Sheets\17BP.14.R.41_TC_TMP_05_PHASE_II.dgn
B:\dton


| | | | | |
|--|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--|--|----------|
| | APPROVED: <i>Patsy L. Watson</i> DATE: 11/20/13 | | | PHASE II |
| | Stantec Consulting Services Inc. 801 Jones Franklin Road Suite 300 Raleigh, NC 27606 Tel. (919) 851-8866 Fax. (919) 851-7024 www.stantec.com License No. F-0672 | | | |

CONTRACT NO.: DN00164 PROJECT: 17BP.14.R.41

**STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION**

**PAVEMENT MARKING PLAN
 GRAHAM COUNTY**

**LOCATION: BRIDGE NO. 102 ON SR 1254 (EAST BUFFALO ROAD)
 OVER EAST BUFFALO CREEK**

| | |
|-------------------------------------------------------------------------------------|--------------------|
| PROJECT NO. 17BP.14.R.41 | SHEET NO. PMP-1 |
| APPROVED <i>Betsy L. Watson</i> | |
| DATE: 11/5/13 | |
|  | |

ROADWAY STANDARD DRAWINGS

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" - PROJECT SERVICES UNIT - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2012 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

| STD. NO. | TITLE |
|----------|-------------------------------------------------|
| 1205.01 | PAVEMENT MARKINGS - LINE TYPES & OFFSETS |
| 1205.02 | PAVEMENT MARKINGS - 2 LANE & MULTILANE ROADWAYS |
| 1205.12 | PAVEMENT MARKINGS - BRIDGES |

GENERAL NOTES

THE FOLLOWING GENERAL NOTES APPLY AT ALL TIMES FOR THE DURATION OF THE CONSTRUCTION PROJECT, EXCEPT WHEN OTHERWISE NOTED IN THE PLAN, OR DIRECTED BY THE ENGINEER.

A) INSTALL PAVEMENT MARKINGS AND PAVEMENT MARKERS ON THE FINAL SURFACE AS FOLLOWS:

| ROAD NAME | MARKING | MARKER |
|-----------------------|---------|--------|
| EAST BUFFALO CREEK RD | PAINT | NONE |

B) PLACE TWO APPLICATIONS OF PAINT PAVEMENT MARKINGS ON THE FINAL WEARING SURFACE. PLACE THE SECOND APPLICATION OF PAINT UPON SUFFICIENT DRYING TIME OF THE FIRST.

C) TIE PROPOSED PAVEMENT MARKING LINES TO EXISTING PAVEMENT MARKING LINES.

D) REMOVE/REPLACE ANY CONFLICTING/DAMAGED PAVEMENT MARKINGS AND MARKERS.


E) PASSING ZONES WILL BE DETERMINED IN THE FIELD AND MUST BE APPROVED BY THE ENGINEER.

F) REMOVE ALL RESIDUE AND SURFACE LAITANCE BY ACCEPTABLE METHODS OF THE BRIDGE DECK(S) PRIOR TO PLACING (PAINT) PAVEMENT MARKING.

FINAL PAVEMENT MARKING SCHEDULE

| SYMBOL | DESCRIPTION | PAY ITEM |
|--------|---------------------------|----------|
| PA | WHITE EDGELINE (4") | PAINT |
| PI | YELLOW DOUBLE CENTER (4") | PAINT |

PAVEMENT MARKING DETAIL



PLAN PREPARED BY:

BETSY L. WATSON, P.E. TRAFFIC ENGINEER
ROSI R. HENNEIN TRANSPORTATION TECHNICIAN



Stantec Consulting Services Inc.
 801 James Franklin Road
 Suite 300
 Raleigh, NC 27608
 Tel: (919) 851-4559
 Fax: (919) 851-3224
 www.stantec.com
 License No. F-0872

INDEX



| SHEET NO. | DESCRIPTION |
|-----------|--------------------------------------------------------------------------|
| PMP-1 | PAVEMENT MARKING PLAN TITLE, SCHEDULE SHEET, AND PAVEMENT MARKING DETAIL |

EROSION CONTROL PLAN

BEGIN CONSTRUCTION
BEGIN PROJECT 17BP.14.R.41
TIE TO PROJECT 17BP.14.R.34
-L- POT STA. 13+50.00

NOTES: ANY DEVIATION FROM OPTIONS GIVEN WILL REQUIRE PRIOR APPROVAL BY ENGINEER.

ADDITIONAL EROSION CONTROL DEVICES MAY NEED TO BE INSTALLED AS DIRECTED BY THE ENGINEER.



2012 STANDARD DRAWINGS

| | |
|------------------------------------------|----------------------------------------------|
| 1604.01 Railroad Erosion Control Detail | 1632.01 Rock Inlet Sediment Trap Type A |
| 1605.01 Temporary Silt Fence | 1632.02 Rock Inlet Sediment Trap Type B |
| 1606.01 Special Sediment Control Fence | 1632.03 Rock Inlet Sediment Trap Type C |
| 1607.01 Gravel Construction Entrance | 1633.01 Temporary Rock Silt Check Type A |
| 1622.01 Temporary Berms and Slope Drains | 1633.02 Temporary Rock Silt Check Type B |
| 1630.01 Riser Basin | 1634.01 Temporary Rock Sediment Dam Type A |
| 1630.02 Silt Basin Type B | 1634.02 Temporary Rock Sediment Dam Type B |
| 1630.03 Temporary Silt Ditch | 1635.01 Rock Pipe Inlet Sediment Trap Type A |
| 1630.04 Stilling Basin | 1635.02 Rock Pipe Inlet Sediment Trap Type B |
| 1630.05 Temporary Diversion | 1640.01 Coir Fiber Baffle |
| 1630.06 Special Stilling Basin | 1645.01 Temporary Stream Crossing |
| 1631.01 Matting Installation | |

EROSION AND SEDIMENT CONTROL MEASURES

| Std. # | Description | Symbol |
|---------|----------------------------------|--------|
| 1605.01 | Temporary Silt Fence | |
| 1606.01 | Special Sediment Control Fence | |
| 1633.01 | Temporary Rock Silt Check Type-A | XXXX |
| 1630.06 | Special Stilling Basin | □ |

INSTALL MATTING FOR EROSION CONTROL IN THE PROPOSED DITCH LINE.


PLAN ALONG -L-
 SCALE: 1" = 20'

CONSTRUCTION SEQUENCE

2 @ 9'x4' RCBC

- STAGE I TRAFFIC / PHASE 1 CONSTRUCTION**
- PLACE TEMP. IMPERVIOUS DIKE TO DEWATER THE AREA FOR PHASE 1 CONSTRUCTION.
 - CONSTRUCT LEFT FLOOD PLAIN CULVERT BARREL, SILL WALL AND DOWN-STREAM WING WALL UNDER EAST BOUND LANE.
 - DO NOT REMOVE TEMP. IMPERVIOUS DIKE.
- STAGE I TRAFFIC / PHASE 2 CONSTRUCTION**
- PLACE TEMPORARY DIVERSION PIPES THE ENTIRE LENGTH OF LOW FLOW BARREL (PHASE 2 & 3 CONST.).
 - ANCHOR BOTH ENDS BY TEMPORARY DIKES ACROSS EXISTING EAST BUFFALO CREEK.
 - DEWATER AREA FOR PHASE 2 CONSTRUCTION.
 - CONSTRUCT RIGHT LOW FLOW CULVERT BARREL, SILL WALL AND DOWN-STREAM WING WALL UNDER EAST BOUND LANE AROUND THE TEMPORARY PIPES.
 - SHIFT STAGE II TRAFFIC OVER PHASE 1 & 2 CONSTRUCTION BARREL SECTIONS.
- STAGE II TRAFFIC / PHASE 3 CONSTRUCTION**
- DECONSTRUCT EXISTING BRIDGE.
 - DEWATER THE AREA FOR PHASE 3 CONSTRUCTION AROUND THE TEMPORARY DIVERSION PIPES.
 - CONSTRUCT RIGHT LOW FLOW CULVERT BARREL, SILL WALL AND UPSTREAM WING WALL UNDER WEST BOUND LANE AROUND THE TEMPORARY PIPES.
 - REMOVE TEMPORARY DIVERSION PIPE UPON COMPLETION OF PHASE 3 CONSTRUCTION.
- STAGE II TRAFFIC / PHASE 4 CONSTRUCTION**
- PLACE TEMPORARY IMPERVIOUS DIKES TO DEWATER AREA FOR PHASE 4 CONSTRUCTION.
 - ROUTE FLOW THROUGH LOW FLOW BARREL IN AREA OF PHASE 2 & 3 CONSTRUCTION.
 - CONSTRUCT THE LEFT FLOOD PLAIN CULVERT BARREL, SILL WALL AND UPSTREAM WING WALL UNDER THE WEST BOUND LANE.
 - REMOVE TEMPORARY IMPERVIOUS DIKES AND DIVERSION PIPE.

2-24", 57' L
 TEMPORARY
 PIPE



ROADSIDE ENVIRONMENTAL UNIT
DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
 RALEIGH, N.C.

2012 STANDARD SPECIFICATIONS

THESE EROSION AND SEDIMENT CONTROL PLANS COMPLY WITH THE REGULATIONS SET FORTH BY THE NCG-010000 GENERAL CONSTRUCTION PERMIT EFFECTIVE AUGUST 3, 2011 ISSUED BY THE NORTH CAROLINA DEPARTMENT OF ENVIRONMENT AND NATURAL RESOURCES DIVISION OF WATER QUALITY.

WSP-SELLS
 Transportation & Infrastructure
 15401 Weston Parkway Suite 100
 Cary, NC 27513 - 919.678.0035
 www.wspells.com
 LICENSE NO. F-0891

RANA STANSELL
 LEVEL IIIA NAME

635
 LEVEL IIIA CERTIFICATION NO.

PROJECT NO. 17BP.14.R.41
 GRAHAM COUNTY
 STATION: 14+84.50 -L-

REPLACES BRIDGE No. 102

STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH

BRIDGE ON SR 1254
 OVER
 EAST BUFFALO CREEK

32' SHLD. POINT TO SHLD. POINT 97° SKEW

| REVISIONS | | | | | | SHEET NO. |
|-----------|-----|-------|-----|-----|-------|--------------|
| NO. | BY: | DATE: | NO. | BY: | DATE: | EC-1 |
| 1 | | | 3 | | | TOTAL SHEETS |
| 2 | | | 4 | | | 2 |

DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA

SOIL STABILIZATION TIMEFRAMES

| <i>SITE DESCRIPTION</i> | <i>STABILIZATION TIME</i> | <i>TIMEFRAME EXCEPTIONS</i> |
|----------------------------------------------|---------------------------|----------------------------------------------------------------------------------------|
| PERIMETER DIKES, SWALES, DITCHES AND SLOPES | 7 DAYS | NONE |
| HIGH QUALITY WATER (HQW) ZONES | 7 DAYS | NONE |
| SLOPES STEEPER THAN 3:1 | 7 DAYS | IF SLOPES ARE 10' OR LESS IN LENGTH AND ARE NOT STEEPER THAN 2:1, 14 DAYS ARE ALLOWED. |
| SLOPES 3:1 OR FLATTER | 14 DAYS | 7 DAYS FOR SLOPES GREATER THAN 50' IN LENGTH. |
| ALL OTHER AREAS WITH SLOPES FLATTER THAN 4:1 | 14 DAYS | NONE, EXCEPT FOR PERIMETERS AND HQW ZONES. |


CONTRACT NO.: DN00164 PROJECT: 17BP.14.R.41

11/4/2013
L:\Graham\02_Traffic\Signing\CADD\Signing_Layout_Plans\17BP.14.R.41_Sign_01.dgn
Rhennein

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

**SIGNING PLANS
GRAHAM COUNTY**

LOCATION: BRIDGE NO. 102 ON SR 1254 (EAST BUFFALO ROAD)
OVER EAST BUFFALO CREEK

| | |
|-------------------------------------------------------------------------------------|---------------------|
| PROJECT NO. 17BP.14.R.41 | SHEET NO. SIGN-1 |
| APPROVED <i>Betsy L. Watson</i> | |
| DATE: 11/5/13 | |
| SEAL | |
|  | |

GENERAL NOTES

- . SIGNS FURNISHED BY CONTRACTOR
- . IF REMOVAL OR RELOCATION OF SIGNS ON PRIVATE STREET (NON-STATE MAINTAINED) IS REQUIRED DUE TO CONSTRUCTION, THE CONTRACTOR SHALL INFORM THE ENGINEER. THE WORK WILL BE COMPLETED BY OTHERS.
- . SIGNING PLANS DO NOT INCLUDE TEMPORARY CONSTRUCTION SIGNING. SEE TRANSPORTATION MANAGEMENT PLANS.
- . WHEN NOT STATIONED OR DIMENSIONED ON PLANS, ALL 'E' SIGNS SHALL BE FIELD LOCATED BY THE ENGINEER
- . ALL EXISTING SIGNS ON "U" CHANNEL POST WITHIN THE PROJECT LIMITS SHALL BE REMOVED AND DISPOSED OF UNLESS OTHERWISE NOTED ON PLANS.
- . THE BACKGROUND FOR TYPE E SIGNS SHALL BE TYPE C REFLECTIVE SHEETING.

ROADWAY STANDARD DRAWINGS


THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" - PROJECT SERVICES UNIT - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2012 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

| STD. NO. | TITLE |
|----------|-------------------------------|
| 1264.01 | OBJECT MARKERS - TYPES |
| 1264.02 | OBJECT MARKERS - INSTALLATION |

SUMMARY OF QUANTITIES

| ITEM NO. | DESC. NO. | SECT. NO. | ITEM DESCRIPTION | QUANTITY | UNIT |
|------------|-----------|-----------|-----------------------------------------|----------|------|
| 4155000000 | 907 | | DISPOSAL OF SIGN SYSTEM, U-CHANNEL..... | 3 | EA. |
| 4915000000 | 1264 | | 7' U-CHANNEL POSTS..... | 4 | EA. |
| 4957000000 | 1264 | | OBJECT MARKERS (TYPE 3)..... | 4 | EA. |

SIGNING DETAIL



401 QUANTITY REQ'D 2



12 x 36
OM-3R

ONE "U" POST PER SIGN

402 QUANTITY REQ'D 2



12 x 36
OM-3L

ONE "U" POST PER SIGN

INDEX

| SHEET NO. | DESCRIPTION |
|-----------|-----------------------------|
| SIGN-1 | TITLE SHEET AND SIGN DETAIL |

PLAN PREPARED BY:

BETSY L. WATSON, P.E. TRAFFIC ENGINEER
ROSI R. HENNEIN TRANSPORTATION TECHNICIAN



Stantec Consulting Services Inc.
801 Jones Franklin Road
Suite 300
Raleigh, NC 27608
Tel: (919) 851-6868
Fax: (919) 851-7024
www.stantec.com
License No. F-0872

5/14/99

| | |
|-----------------------|-----------|
| PROJECT REFERENCE NO. | SHEET NO. |
| 17BP.14.R.41 | UO-1 |

UTILITIES BY OTHERS

NOTE:
ALL PROPOSED UTILITY WORK
SHOWN ON THIS SHEET WILL
BE DONE BY OTHERS

WETHERILL ENGINEERING
559 Jones Franklin Rd. Suite 164
Raleigh, N.C. 27606
License No. F-0377
Bus: 919 851 8077
Fax: 919 851 8107

TRANSPORTATION PLANNING/DESIGN - BRIDGE/STRUCTURE DESIGN
CIVIL/SITE DESIGN - GIS/GPS - CONSTRUCTION OBSERVATION


POWER: DUKE ENERGY CORPORATION
526 S. CHURCH STREET
P.O. BOX 1006, EC100
CHARLOTTE, N.C. 28202

TELEPHONE: FRONTIER COMMUNICATION
1000 SAINT ALBANS DRIVE, SUITE 300
RALEIGH, N.C. 27609

END CONSTRUCTION
-L- POT STA. 16+90

BEGIN CONSTRUCTION
BEGIN PROJECT 17BP.14.R.41
TIE TO PROJECT 17BP.14.R.34
-L- POT STA. 13+50.00

3/10/2014
U:\Roadway\17BP.14.R.41\GRAHAM102_ubo_psh.dgn



CROSS SECTION INDEX


| <u>ROADWAY</u> | <u>STATION</u> | <u>TO</u> | <u>STATION</u> | <u>SHEET NO.</u> |
|-----------------------|----------------|-----------|----------------|------------------|
| CROSS SECTION INDEX | | | | X-1 |
| CROSS SECTION SUMMARY | | | | X-1A |
| -EAST BUFFALO ROAD- | 13 + 50.00 | | 16 + 50.00 | X-2 - X-3 |

| STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS | | | | | |
|-------------------------------------------------|-------------------------|-------------------|-------------------------------|-------------------------|-------------------|
| CROSS-SECTION SUMMARY | | | | | |
| STATION -L- FINAL | Uncl. Exc. (cu. yd.) | Embt (cu. yd.) | STATION -L- TEMP. WIDENING | Uncl. Exc. (cu. yd.) | Embt (cu. yd.) |
| 13+50.00 | 0 | 0 | 13+50.00 | 0 | 0 |
| 14+00.00 | 0 | 0 | 14+00.00 | 3 | 33 |
| 14+50.00 | 11 | 0 | 14+50.00 | 3 | 39 |
| 15+00.00 | 26 | 0 | 15+00.00 | 11 | 56 |
| 15+50.00 | 23 | 0 | 15+50.00 | 21 | 57 |
| 16+00.00 | 0 | 0 | 16+00.00 | 23 | 41 |
| 16+50.00 | 0 | 0 | 16+50.00 | 13 | 24 |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |

Note: Earthwork Quantities are calculated by the Roadway Design Unit. These earthwork quantities are based in part on subsurface data provided by the Geotechnical Engineering Unit

Note: Approximate quantities only. Unclassified Excavation, Borrow Excavation, Shoulder Borrow, Fine Grading, Clearing and Grubbing, Breaking of Existing Asphalt Pavement, and Removal of Existing Pavement will be paid for at the contract lump sum price for "Grading"

Embankment quantity does not include backfill for undercut



150 140 130 120 110 100 90 80 70 60 50 40 30 20 10 0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150

1980

1980

1970

1970

1960

1960

1950

1950

16 + 50.00

1980

1980

1970

1970

1960


1960

1950

1950


16 + 00.00

—/—




LOCATION SKETCH

NO KNOWN UTILITY CONFLICTS



RIGHT ANGLE SECTION OF BARREL

THERE ARE 67 "C" BARS IN SECTION OF BARREL. NO CONSTRUCTION JOINT IS PERMITTED @ BOTTOM OF FILLET.



BAR TYPE

BAR DIMENSIONS ARE OUT TO OUT

SPLICE LENGTHS CHART

| BAR | SIZE | SPLICE LENGTH |
|------|------|---------------|
| B1 | 4 | 1'-9" |
| B3 | 4 | 1'-9" |
| C1 | 4 | * |
| A100 | 5 | 2'-2" |
| A200 | 4 | 1'-9" |
| A300 | 4 | 1'-9" |
| A400 | 5 | 2'-2" |
| G1 | 5 | 2'-2" |
| S2 | 8 | 2'-6" |

*MECHANICAL BUTT SPLICES REQUIRED FOR THESE BARS

OVERTOPPING FLOOD DATA

OVERTOPPING DISCHARGE ----- = 440 CFS±
 FREQUENCY OF OVERTOPPING ----- = 10 YR.±
 OVERTOPPING FLOOD ELEVATION ----- = 1958.7

HYDRAULIC DATA

DESIGN DISCHARGE ----- = 320 CFS
 FREQUENCY OF DESIGN FLOOD ----- = 5 YR.
 DESIGN HIGH WATER ELEVATION ----- = 1958.2
 BASIC DRAINAGE (Q100) ----- = 850 CFS
 BASIC HIGH WATER ELEVATION ----- = 1959.34
 DRAINAGE AREA ----- = 1.78 SQ. MI.

TOTAL STRUCTURE QUANTITIES

| CLASS A CONCRETE | |
|--------------------------------------------------------------|--------------------|
| BARREL @ 1.663 CY/FT | 75.7 C.Y. |
| SILL WALLS | 2.0 C.Y. |
| WING ETC. | 14.6 C.Y. |
| TOTAL | 92.3 C.Y. |
| REINFORCING STEEL | |
| BARREL | 10,684 LBS. |
| SILL WALLS | 192 LBS. |
| WINGS ETC. | 493 LBS. |
| TOTAL | 11,369 LBS. |
| FOUNDATION CONDITIONING MAT'L = 64 TONS | |
| RIP RAP, CLASS I = 60 TONS | |
| GEOTEXTILE FOR DRAINAGE = 72 SY | |
| REMOVAL OF EXISTING STRUCTURE @ STA. 14+84.50 -L- = LUMP SUM | |

NOTES

ASSUMED LIVE LOAD -----HS20-44 OR ALTERNATE LOADING.
 DESIGN FILL----- 2.22'
 FOR OTHER DESIGN DATA AND NOTES SEE STANDARD NOTE SHEET.
 3" Ø WEEP HOLES INDICATED TO BE IN ACCORDANCE WITH THE SPECIFICATIONS.
 CONCRETE IN CULVERTS TO BE POURED IN THE FOLLOWING ORDER:

1. WING FOOTINGS AND FLOOR SLAB INCLUDING 4" OF ALL VERTICAL WALLS.
2. THE REMAINING PORTIONS OF THE WALLS AND WINGS FULL HEIGHT FOLLOWED BY ROOF SLAB AND HEADWALLS.

THE RESIDENT ENGINEER SHALL CHECK THE LENGTH OF CULVERT BEFORE STAKING IT OUT TO MAKE CERTAIN THAT IT WILL PROPERLY TAKE CARE OF THE FILL.


DIMENSIONS FOR WING LAYOUT AS WELL AS ADDITIONAL REINFORCING STEEL EMBEDDED IN BARREL ARE SHOWN ON WING SHEET.

AT THE CONTRACTOR'S OPTION, HE MAY SPLICE THE VERTICAL REINFORCING STEEL IN THE INTERIOR FACE OF EXTERIOR WALL AND BOTH FACES OF INTERIOR WALLS ABOVE LOWER WALL CONSTRUCTION JOINT. THE SPLICE LENGTH SHALL BE AS PROVIDED IN THE SPLICE LENGTH CHART SHOWN ON THE PLANS. EXTRA WEIGHT OF STEEL DUE TO THE SPLICES SHALL BE PAID FOR BY THE CONTRACTOR.

AT THE CONTRACTOR'S OPTION HE MAY SUBMIT, TO THE ENGINEER FOR APPROVAL, DESIGN AND DETAIL DRAWINGS FOR A PRECAST REINFORCED CONCRETE BOX CULVERT IN LIEU OF THE CAST-IN-PLACE CULVERT SHOWN ON THE PLANS. THE DESIGN SHALL PROVIDE THE SAME SIZE AND NUMBER OF BARRELS AS USED ON THE CAST-IN-PLACE DESIGN. FOR OPTIONAL PRECAST REINFORCED CONCRETE BOX CULVERT, SEE SPECIAL PROVISIONS.

AFTER SERVING AS A TEMPORARY CROSSING, THE EXISTING STRUCTURE CONSISTING OF ONE 16'-6" SPAN WITH 17.3' OF CLEAR ROADWAY AND TIMBER FLOOR ON TIMBER JOISTS SUPPORTED BY TIMBER CAPS OVER TIMBER POSTS AND SILLS AT VARIABLE CENTERS AND LOCATED 6' UPSTREAM FROM THE PROPOSED CULVERT SHALL BE REMOVED. THE EXISTING BRIDGE IS PRESENTLY POSTED BELOW THE LEGAL LOAD LIMIT. SHOULD THE STRUCTURAL INTEGRITY OF THE BRIDGE FURTHER DETERIORATE, THIS LOAD LIMITATION MAY BE REDUCED AS FOUND NECESSARY DURING THE LIFE OF THE PROJECT.

FOR CULVERT DIVERSION DETAILS AND PAY ITEMS, SEE EROSION CONTROL PLANS.




PROFILE ALONG CULVERT

BILL OF MATERIAL STAGE I CONSTRUCTION

| BAR | NO. | SIZE | TYPE | LENGTH | WEIGHT |
|--------------------------|-----|------|------|---------|---------------------|
| A1 | 72 | #4 | 6 | 5'-10" | 281 |
| A2 | 72 | #4 | 6 | 5'-7" | 269 |
| A100 | 34 | #5 | STR. | 12'-11" | 458 |
| A101 | 34 | #5 | STR. | 9'-0" | 319 |
| A200 | 30 | #4 | STR. | 13'-2" | 264 |
| A201 | 30 | #4 | STR. | 8'-4" | 167 |
| A300 | 45 | #4 | STR. | 12'-6" | 376 |
| A301 | 45 | #4 | STR. | 9'-0" | 271 |
| A400 | 39 | #5 | STR. | 13'-7" | 553 |
| A401 | 39 | #5 | STR. | 8'-4" | 339 |
| B1 | 44 | #4 | STR. | 4'-6" | 132 |
| B3 | 68 | #4 | STR. | 5'-5" | 246 |
| C1 | 67 | #4 | STR. | 22'-7" | 1011 |
| G1 | 10 | #5 | STR. | 13'-7" | 142 |
| G2 | 10 | #5 | STR. | 8'-4" | 87 |
| S2 | 6 | #8 | STR. | 13'-11" | 223 |
| S3 | 6 | #8 | STR. | 8'-4" | 134 |
| REINFORCING STEEL | | | | | = 5,272 LBS. |

BILL OF MATERIAL STAGE II CONSTRUCTION

| BAR | NO. | SIZE | TYPE | LENGTH | WEIGHT |
|--------------------------|-----|------|------|---------|---------------------|
| A3 | 72 | #4 | 6 | 5'-10" | 281 |
| A4 | 72 | #4 | 6 | 5'-7" | 269 |
| A102 | 36 | #5 | STR. | 12'-11" | 485 |
| A103 | 36 | #5 | STR. | 9'-0" | 338 |
| A202 | 32 | #4 | STR. | 13'-2" | 281 |
| A203 | 32 | #4 | STR. | 8'-4" | 178 |
| A302 | 47 | #4 | STR. | 12'-6" | 392 |
| A303 | 47 | #4 | STR. | 9'-0" | 283 |
| A402 | 40 | #5 | STR. | 13'-7" | 567 |
| A403 | 40 | #5 | STR. | 8'-4" | 348 |
| B4 | 48 | #4 | STR. | 4'-6" | 144 |
| B6 | 70 | #4 | STR. | 5'-5" | 253 |
| C2 | 67 | #4 | STR. | 22'-6" | 1007 |
| G3 | 10 | #5 | STR. | 13'-7" | 142 |
| G4 | 10 | #5 | STR. | 8'-4" | 87 |
| S4 | 6 | #8 | STR. | 13'-11" | 223 |
| S5 | 6 | #8 | STR. | 8'-4" | 134 |
| REINFORCING STEEL | | | | | = 5,412 LBS. |



PROJECT NO. 17BP.14.R.41
 GRAHAM COUNTY
 STATION: 14+84.50

SHEET 1 OF 5 REPLACES BRIDGE 102


STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH

BARREL STANDARD
 DOUBLE 9 FT. X 4 FT.
 CONCRETE BOX CULVERT
 97°00'00" SKEW

| REVISIONS | | | SHEET NO. | | |
|-----------|-----|-------|-----------|-----|-------|
| NO. | BY: | DATE: | NO. | BY: | DATE: |
| 1 | | | 3 | | |
| 2 | | | 4 | | |


TOTAL SHEETS 5

ADDED NOV.1990




ASSEMBLED BY: C. B. BAKER DATE: 05/2012
 CHECKED BY: J. R. DUDECK DATE: 05/2012
 DRAWN BY: R.W. WRIGHT DATE: OCT. 1989
 CHECKED BY: C.R.K. DATE: OCT. 1989

SPECIAL
 STANDARD




STAGE I TRAFFIC/ PHASE 1 CONSTRUCTION

PLACE TEMP. IMPERVIOUS DIKE TO DEWATER THE AREA FOR PHASE 1 CONSTRUCTION. CONSTRUCT LEFT FLOOD PLAIN CULVERT BARREL, SILL WALL AND DOWN-STREAM WING WALL UNDER EAST BOUND LANE.




STAGE II TRAFFIC/ PHASE 3 CONSTRUCTION

DECONSTRUCT EXISTING BRIDGE. DEWATER THE AREA FOR PHASE 3 CONSTRUCTION AROUND THE TEMPORARY DIVERSION PIPE. CONSTRUCT RIGHT LOW FLOW CULVERT BARREL, SILL WALL AND UPSTREAM WING WALL UNDER WEST BOUND LANE AROUND THE TEMPORARY PIPE. REMOVE TEMPORARY DIVERSION PIPE UPON COMPLETION OF PHASE 3 CONSTRUCTION.




SECTION A-A

STAGE I TRAFFIC/ PHASE 1 & 2 CONSTRUCTION




SECTION B-B

STAGE II TRAFFIC/ PHASE 3 & 4 CONSTRUCTION



STAGE I TRAFFIC/ PHASE 2 CONSTRUCTION

PLACE TEMPORARY DIVERSION PIPE THROUGH THE ENTIRE LENGTH OF LOW FLOW BARREL (PHASE 2 & 3 CONSTRUCTION). ANCHOR BOTH ENDS BY TEMPORARY DIKES ACROSS EXISTING EAST BUFFALO CREEK. DEWATER AREA FOR PHASE 2 CONSTRUCTION. CONSTRUCT RIGHT LOW FLOW CULVERT BARREL, SILL WALL AND DOWN-STREAM WING WALL UNDER EAST BOUND LANE AROUND THE TEMPORARY PIPE. SHIFT STAGE II TRAFFIC OVER PHASE 1 & 2 CONSTRUCTION BARREL SECTIONS.



STAGE II TRAFFIC/ PHASE 4 CONSTRUCTION

PLACE TEMPORARY IMPERVIOUS DIKES TO DEWATER AREA FOR PHASE 4 CONSTRUCTION. ROUTE FLOW THROUGH LOW FLOW BARREL IN AREA OF PHASE 2 & 3 CONSTRUCTION. CONSTRUCT THE LEFT FLOOD PLAIN CULVERT BARREL, SILL WALL AND UPSTREAM WING WALL UNDER THE WEST BOUND LANE. REMOVE TEMPORARY IMPERVIOUS DIKES.

PROJECT NO. 17BP.14.R.41
GRAHAM COUNTY
 STATION: 14+84.50 -L-

SHEET 2 OF 5

STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH


STAGING DETAILS

| REVISIONS | | | | | | SHEET NO. |
|-----------|-----|-------|-----|-----|-------|--------------|
| NO. | BY: | DATE: | NO. | BY: | DATE: | C-2 |
| 1 | | | 3 | | | TOTAL SHEETS |
| 2 | | | 4 | | | 5 |




Stantec Consulting Services Inc.
 801 Jones Franklin Road
 Suite 300
 Raleigh, NC 27606
 Tel. (919) 851-6866
 Fax. (919) 851-7024
 www.stantec.com
 License No. F-0672


DRAWN BY: J. B. GEILE DATE: 10-17-12
 CHECKED BY: J. T. KELVINGTON DATE: 10-17-12




U:\Gr-dham02\Structures\Drawing\C-2.dgn 11/22/2013 11:01:20 AM belliot



CULVERT SECTION NORMAL TO ROADWAY




END ELEVATION NORMAL TO SKEW



PART PLAN - ROOF SLAB

PART PLAN - FLOOR SLAB




SKEW TRIANGLE

NOTE:
REINFORCING BAR COUPLERS REQUIRED FOR MECHANICAL BUTT SPLICES SHALL BE INCIDENTAL TO PROCUREMENT AND PLACEMENT OF REINFORCING STEEL

PROJECT NO. 17BP.14.R.41
GRAHAM COUNTY
STATION: 14+84.50

SHEET 3 OF 5


STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH
BARREL STANDARD
DOUBLE 9 FT. X 4 FT.
CONCRETE BOX CULVERT
97°00'00" SKEW




| REVISIONS | | | | | | SHEET NO. |
|-----------|-----|-------|-----|-----|-------|--------------|
| NO. | BY: | DATE: | NO. | BY: | DATE: | C-3 |
| 1 | | | 3 | | | TOTAL SHEETS |
| 2 | | | 4 | | | 5 |



| | | |
|-------------------------------|-----------------|----------|
| ASSEMBLED BY: C. B. BAKER | DATE: 05/2012 | SPECIAL |
| CHECKED BY: T. R. DUDECK | DATE: 05/2012 | |
| DRAWN BY: W. BRYAN STANLEY II | DATE: NOV. 1971 | STANDARD |
| CHECKED BY: JOEL A. JOHNSON | DATE: DEC. 1971 | |




PLAN W2




PLAN W1

BAR TYPES
ALL BAR DIMENSIONS ARE OUT TO OUT.




| BAR NO. | SIZE | TYPE | LENGTH | WEIGHT |
|---------|------|--------|----------|--------|
| H1 | 16 | #4 STR | 5'-2" | 55 |
| H2 | 8 | #4 STR | 4'-3" | 23 |
| H3 | 40 | #4 | 3'-3" | 87 |
| H4 | 8 | #4 STR | 5'-7" | 30 |
| N1 | 4 | #4 | 2 6'-4" | 17 |
| N2 | 8 | #4 | 2 5'-6" | 29 |
| N3 | 8 | #4 | 2 4'-8" | 25 |
| N4 | 8 | #4 | 2 3'-10" | 20 |
| T1 | 12 | #5 STR | 7'-0" | 88 |
| V1 | 4 | #4 STR | 4'-3" | 11 |
| V2 | 8 | #4 STR | 3'-6" | 19 |
| V3 | 8 | #4 STR | 2'-8" | 14 |
| V4 | 8 | #4 STR | 1'-10" | 10 |
| Z1 | 4 | #4 | 3 4'-6" | 12 |
| Z2 | 8 | #4 | 3 3'-11" | 21 |
| Z3 | 8 | #4 | 3 3'-4" | 18 |
| Z4 | 8 | #4 | 3 2'-7" | 14 |


| REINFORCING STEEL FOR 4 WINGS | | 493 LBS |
|-------------------------------|--|---------|
| CLASS A CONCRETE | | |
| 4 WINGS | | 8.3 CY |
| 2 HEADWALLS | | 1.9 CY |
| 2 EDGE BEAMS (TOP AND BOTTOM) | | 2.2 CY |
| END CURTAIN WALLS | | 2.2 CY |
| TOTAL | | 14.6 CY |



ELEVATION W2



ELEVATION W1



TYPICAL WING SECTION

NOTE:
A 3'-0" WIDE STRIP OF FILTER FABRIC SHALL BE ATTACHED TO THE FILL FACE OF THE WING COVERING THE ENTIRE LENGTH OF THE EXPANSION JOINT.

PROJECT NO. 17BP.14.R.41
GRAHAM COUNTY
STATION: 14+84.50
SHEET 4 OF 5


STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH
STANDARD WINGS
FOR
CONCRETE BOX CULVERT
H = 4'-0" SLOPE = 2:1
90° SKEW


| REVISIONS | | | | | | SHEET NO. | |
|-----------|-----|-------|-----|-----|-------|--------------|---|
| NO. | BY: | DATE: | NO. | BY: | DATE: | C-4 | |
| 1 | | | 3 | | | TOTAL SHEETS | 5 |
| 2 | | | 4 | | | | |



Stantec Consulting Services Inc.
801 Jones Franklin Road
Suite 300
Raleigh, NC 27606
Tel. (919) 851-8866
Fax. (919) 851-7024
www.stantec.com
License No. F-0672



ASSEMBLED BY : C. B. BAKER DATE : 05/2012
CHECKED BY : T. R. DUDECK DATE : 05/2012
DRAWN BY : CCJ 10/99
CHECKED BY : RWW 03/00






| BILL OF MATERIAL | | | | | |
|-------------------------|-----|------|------|--------|---------|
| BAR | NO. | SIZE | TYPE | LENGTH | WEIGHT |
| R1 | 20 | #4 | STR | 8'-8" | 116 |
| R2 | 40 | #4 | STR | 1'-8" | 45 |
| R3 | 40 | #4 | STR | 0'-8" | 18 |
| R4 | 20 | #4 | STR | 1'-0" | 13 |
| TOTAL REINFORCING STEEL | | | | | 192 LBS |
| CLASS A CONCRETE | | | | | 2.0 CY |

NOTE:
 BED MATERIAL PLACED BETWEEN SILLS IN THE CULVERT SHALL PROVIDE A CONTINUOUS LOW FLOW CHANNEL BETWEEN THE LOWER SILLS. THE MATERIAL SHALL BE AS SHOWN IN THE PLAN VIEW. STONES LARGER THAN 10" SHALL NOT BE PLACED WITHIN THE LOW FLOW CHANNEL. BED MATERIAL IS SUBJECT TO APPROVAL BY THE ENGINEER.
 FOR ADDITIONAL DETAILS, SEE CULVERT SURVEY REPORT.



SILL GEOMETRY



SILL REINFORCEMENT

2 LAYERS OF 30 LB. ROOFING FELT TO PREVENT BOND (TYP.)

SECTION A-A


PROJECT NO. 17BP.14.R.41
 GRAHAM COUNTY
 STATION: 14+84.50

SHEET 5 OF 5

STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH

SILL DETAILS

| REVISIONS | | | | | | SHEET NO. |
|-----------|-----|-------|-----|-----|-------|--------------|
| NO. | BY: | DATE: | NO. | BY: | DATE: | C-5 |
| 1 | | | 3 | | | TOTAL SHEETS |
| 2 | | | 4 | | | 5 |



U:\Graham02\Structures\Drawing\C-5.dgn 11/22/2013 11:05:00 AM belliot

Stantec Consulting Services Inc.
 801 Jones Franklin Road
 Suite 300
 Raleigh, NC 27606
 Tel. (919) 851-6866
 Fax. (919) 851-7024
 www.stantec.com
 License No. F-0672

DRAWN BY : T. R. DUDECK DATE : 10-17-12
 CHECKED BY : J. T. KELVINGTON DATE : 10-17-12

STANDARD NOTES

DESIGN DATA:

| | | |
|-------------------------------------------------|-------|----------------------------------|
| SPECIFICATIONS | ----- | A.A.S.H.T.O. (CURRENT) |
| LIVE LOAD | ----- | SEE PLANS |
| IMPACT ALLOWANCE | ----- | SEE A.A.S.H.T.O. |
| STRESS IN EXTREME FIBER OF | | |
| STRUCTURAL STEEL - AASHTO M270 GRADE 36 | - | 20,000 LBS. PER SQ. IN. |
| - AASHTO M270 GRADE 50W | - | 27,000 LBS. PER SQ. IN. |
| - AASHTO M270 GRADE 50 | - | 27,000 LBS. PER SQ. IN. |
| REINFORCING STEEL IN TENSION | | |
| GRADE 60 | -- | 24,000 LBS. PER SQ. IN. |
| CONCRETE IN COMPRESSION | ----- | 1,200 LBS. PER SQ. IN. |
| CONCRETE IN SHEAR | ----- | SEE A.A.S.H.T.O. |
| STRUCTURAL TIMBER - TREATED OR | | |
| UNTREATED - EXTREME FIBER STRESS | ----- | 1,800 LBS. PER SQ. IN. |
| COMPRESSION PERPENDICULAR TO GRAIN OF TIMBER | ----- | 375 LBS. PER SQ. IN. |
| EQUIVALENT FLUID PRESSURE OF EARTH | ----- | 30 LBS. PER CU. FT. (MINIMUM) |

MATERIAL AND WORKMANSHIP:

EXCEPT AS MAY OTHERWISE BE SPECIFIED ON PLANS OR IN THE SPECIAL PROVISIONS, ALL MATERIAL AND WORKMANSHIP SHALL BE IN ACCORDANCE WITH THE 2012 "STANDARD SPECIFICATIONS FOR ROADS AND STRUCTURES" OF THE N. C. DEPARTMENT OF TRANSPORTATION.

STEEL SHEET PILING FOR PERMANENT OR TEMPORARY APPLICATIONS SHALL BE HOT ROLLED.

CONCRETE:

UNLESS OTHERWISE REQUIRED ON PLANS, CLASS A CONCRETE SHALL BE USED FOR ALL PORTIONS OF ALL STRUCTURES WITH THE EXCEPTION THAT: CLASS AA CONCRETE SHALL BE USED IN BRIDGE SUPERSTRUCTURES, ABUTMENT BACKWALLS, AND APPROACH SLABS; AND CLASS B CONCRETE SHALL BE USED FOR SLOPE PROTECTION AND RIP RAP.

CONCRETE CHAMFERS:

UNLESS OTHERWISE NOTED ON THE PLANS, ALL EXPOSED CORNERS ON STRUCTURES SHALL BE CHAMFERED 3/4" WITH THE FOLLOWING EXCEPTIONS: TOP CORNERS OF CURBS MAY BE ROUNDED TO 1-1/2" RADIUS WHICH IS BUILT INTO CURB FORMS; CORNERS OF TRANSVERSE FLOOR EXPANSION JOINTS SHALL BE ROUNDED WITH A 1/4" FINISHING TOOL UNLESS OTHERWISE REQUIRED ON PLANS; AND CORNERS OF EXPANSION JOINTS IN THE ROADWAY FACES AND TOPS OF CURBS AND SIDEWALKS SHALL BE ROUNDED TO A 1/4" RADIUS WITH A FINISHING STONE OR TOOL UNLESS OTHERWISE REQUIRED ON PLANS.

DOWELS:

DOWELS WHEN INDICATED ON PLANS AS FOR CULVERT EXTENSIONS, SHALL BE EMBEDDED AT LEAST 12" INTO THE OLD CONCRETE AND GROUTED INTO PLACE WITH 1:2 CEMENT MORTAR.

ALLOWANCE FOR DEAD LOAD DEFLECTION, SETTLEMENT, ETC. IN CASTING SUPERSTRUCTURES:

BRIDGES SHALL BE BUILT ON THE GRADE OR VERTICAL CURVE SHOWN ON PLANS. SLABS, CURBS AND PARAPETS SHALL CONFORM TO THE GRADE OR CURVE.
ALL DIMENSIONS WHICH ARE GIVEN IN SECTION AND ARE AFFECTED BY DEAD LOAD DEFLECTIONS ARE DIMENSIONS AT CENTER LINE OF BEARING UNLESS OTHERWISE NOTED ON PLANS. IN SETTING FORMS FOR STEEL BEAM BRIDGES AND PRESTRESSED CONCRETE GIRDER BRIDGES, ADJUSTMENTS SHALL BE MADE DUE TO THE DEAD LOAD DEFLECTIONS FOR THE ELEVATIONS SHOWN. WHERE BLOCKS ARE SHOWN OVER BEAMS FOR BUILDING UP TO THE SLAB, THE VERTICAL DIMENSIONS OF THE BLOCKS SHALL BE ADJUSTED BETWEEN BEARINGS TO COMPENSATE FOR DEAD LOAD DEFLECTIONS, VERTICAL CURVE ORDINATE, AND ACTUAL BEAM CAMBER. WHERE BOTTOM OF SLAB IS IN LINE WITH BOTTOM OF TOP FLANGES, DEPTH OF SLAB BETWEEN BEARINGS SHALL BE ADJUSTED TO COMPENSATE FOR DEAD LOAD DEFLECTION, VERTICAL CURVE ORDINATE, AND ACTUAL BEAM CAMBER.
IN SETTING FALSEWORK AND FORMS FOR REINFORCED CONCRETE SPANS, AN ALLOWANCE SHALL BE MADE FOR DEAD LOAD DEFLECTIONS, SETTLEMENT OF FALSEWORK, AND PERMANENT CAMBER WHICH SHALL BE PROVIDED FOR IN ADDITION TO THE ELEVATIONS SHOWN. AFTER REMOVAL OF THE FALSEWORK, THE FINISHED STRUCTURES SHALL CONFORM TO THE PROFILE AND ELEVATIONS SHOWN ON THE PLANS AND CONSTRUCTION ELEVATIONS FURNISHED BY THE ENGINEER.
DETAILED DRAWINGS FOR FALSEWORK OR FORMS FOR BRIDGE SUPERSTRUCTURE AND ANY STRUCTURE OR PARTS OF A STRUCTURE AS NOTED ON THE PLANS SHALL BE SUBMITTED TO THE ENGINEER FOR APPROVAL BEFORE CONSTRUCTION OF THE FALSEWORK OR FORMS IS STARTED.

REINFORCING STEEL:

ALL REINFORCING STEEL SHALL BE DEFORMED. DIMENSIONS RELATIVE TO PLACEMENT OF REINFORCING ARE TO CENTERS OF BARS UNLESS OTHERWISE INDICATED IN THE PLANS. DIMENSIONS ON BAR DETAILS ARE TO CENTERS OF BARS OR ARE OUT TO OUT AS INDICATED ON PLANS.
WIRE BAR SUPPORTS SHALL BE PROVIDED FOR REINFORCING STEEL WHERE INDICATED ON THE PLANS. WHEN BAR SUPPORT PIECES ARE PLACED IN CONTINUOUS LINES, THEY SHALL BE SO PLACED THAT THE ENDS OF THE SUPPORTING WIRES SHALL BE LAPPED TO LOCK LEGS ON ADJOINING PIECES.

STRUCTURAL STEEL:

AT THE CONTRACTOR'S OPTION, HE MAY SUBSTITUTE 7/8" Ø SHEAR STUDS FOR THE 3/4" Ø STUDS SPECIFIED ON THE PLANS. THIS SUBSTITUTION SHALL BE MADE AT THE RATE OF 3 - 7/8" Ø STUDS FOR 4 - 3/4" Ø STUDS, AND STUD SPACING CHANGES SHALL BE MADE AS NECESSARY TO PROVIDE THE SAME EQUIVALENT NUMBER OF 7/8" Ø STUDS ALONG THE BEAM AS SHOWN FOR 3/4" Ø STUDS BASED ON THE RATIO OF 3 - 7/8" Ø STUDS FOR 4 - 3/4" Ø STUDS. STUDS OF THE LENGTH SPECIFIED ON THE PLANS MUST BE PROVIDED. THE MAXIMUM SPACING SHALL BE 2'-0".
EXCEPT AT THE INTERIOR SUPPORTS OF CONTINUOUS BEAMS WHERE THE COVER PLATE IS IN CONTACT WITH BEARING PLATE, THE CONTRACTOR MAY, AT HIS OPTION, SUBSTITUTE FOR THE COVER PLATES DESIGNATED ON THE PLANS COVER PLATES OF THE EQUIVALENT AREA PROVIDED THESE PLATES ARE AT LEAST 5/16" IN THICKNESS AND DO NOT EXCEED A WIDTH EQUAL TO THE FLANGE WIDTH LESS 2" OR A THICKNESS EQUAL TO 2 TIMES THE FLANGE THICKNESS. THE SIZE OF FILLET WELDS SHALL CONFORM TO THE REQUIREMENTS OF THE CURRENT ANSI/AASHTO/AWS "BRIDGE WELDING CODE". ELECTROSLAG WELDING WILL NOT BE PERMITTED.
WITH THE SOLE EXCEPTION OF EDGES AT SURFACES WHICH BEAR ON OTHER SURFACES, ALL SHARP EDGES AND ENDS OF SHAPES AND PLATES SHALL BE SLIGHTLY ROUNDED BY SUITABLE MEANS TO A RADIUS OF APPROXIMATELY 1/16 INCH OR EQUIVALENT FLAT SURFACE AT A SUITABLE ANGLE PRIOR TO PAINTING, GALVANIZING, OR METALLIZING.

HANDRAILS AND POSTS:

METAL STANDARDS AND FACES OF THE CONCRETE END POSTS FOR THE METAL RAIL SHALL BE SET NORMAL TO THE GRADE OF THE CURB, UNLESS OTHERWISE SHOWN ON PLANS. THE METAL RAIL AND TOPS OF CONCRETE POSTS USED WITH THE ALUMINUM RAIL SHALL BE BUILT PARALLEL TO THE GRADE OF THE CURB.
METAL HANDRAILS SHALL BE IN ACCORDANCE WITH THE PLANS. RAILS SHALL BE AS MANUFACTURED FOR BRIDGE RAILING. CASTINGS SHALL BE OF A UNIFORM APPEARANCE. FINIS AND OTHER DEFORMATIONS RESULTING FROM CASTING OR OTHERWISE SHALL BE REMOVED IN A MANNER SO THAT A UNIFORM COLORING OF THE COMPLETED CASTING SHALL BE OBTAINED. CASTINGS WITH DISCOLORATIONS OR OF NON-UNIFORM COLORING WILL NOT BE ACCEPTED. CERTIFIED MILL REPORTS ARE REQUIRED FOR METAL RAILS AND POSTS.

SPECIAL NOTES:

GENERALLY, IN CASE OF DISCREPANCY, THIS STANDARD SHEET OF NOTES SHALL GOVERN OVER THE SPECIFICATIONS, BUT THE REMAINDER OF THE PLANS SHALL GOVERN OVER NOTES HEREON, AND SPECIAL PROVISIONS SHALL GOVERN OVER ALL. SEE SPECIFICATIONS ARTICLE 105-4.

ENGLISH

JANUARY, 1990