




STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

ROY COOPER
GOVERNOR

JAMES H. TROGDON, III
SECRETARY

May 3, 2018

ADDENDUM # 1

To: Plan Holders
From: Wes Jamison, P.E. 
Division 14 Project Manager

RE: **Bid Item Additions**
Contract ID: DN00525
County: Henderson
Letting Date: May 22, 2018

The above contract has experienced the following bid item additions:

1. **6015000000-E 1615 ACR TEMPORARY MULCHING, quantity = 1**
2. **6018000000-E 1620 LB SEED FOR TEMPORARY SEEDING, quantity = 50**
3. **6021000000-E 1620 TON FERTILIZER FOR TEMPORARY SEEDING, quantity = 0.2**
4. **6084000000-E 1660 ACR SEEDING & MULCHING, quantity = 2**
5. **6108000000-E 1665 TON FERTILIZER TOPDRESSING, quantity = 0.75**

Please see the attached revised Itemized Proposal For Contract No. DN00525 pages, that reflect the bid item additions for Addendum # 1.

Please access ebs addenda files on Bid Express®.

Thank you for your attention to this matter.

May 03, 2018 4:02 pm

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0106000000-E	230	BORROW EXCAVATION	1,710 CY		
0003	0335300000-E	305	18" DRAINAGE PIPE	680 LF		
0004	0576000000-E	310	*** CS PIPE CULVERTS, ***** THICK (36) (0.079)	25 LF		
0005	0576000000-E	310	*** CS PIPE CULVERTS, ***** THICK (48) (0.109)	100 LF		
0006	0588000000-E	310	18" CS PIPE CULVERTS, 0.064" THICK	285 LF		
0007	0594000000-E	310	24" CS PIPE CULVERTS, 0.064" THICK	30 LF		
0008	1121000000-E	520	AGGREGATE BASE COURSE	5,251 TON		
0009	1146000000-E	535	CONDITIONING EXISTING BASE	12 MSY		
0010	1245000000-E	SP	SHOULDER RECONSTRUCTION	0.96 SMI		
0011	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	1,890 TON		
0012	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	91 TON		
0013	1803500000-E	660	ASPHALT SURFACE TREATMENT, DOUBLE SEAL	12,432 SY		
0014	1820000000-E	SP	ASPHALT SURFACE TREATMENT, FOG SEAL	12,432 SY		
0015	1838000000-E	660	EMULSION FOR ASPHALT SURFACE TREATMENT	6,714 GAL		
0016	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	5 EA		
0017	2830000000-N	858	ADJUSTMENT OF MANHOLES	1 EA		
0018	4413000000-E	SP	WORK ZONE ADVANCE/GENERAL WARNING SIGNING	48 SF		

May 03, 2018 4:02 pm

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	4457000000-N	SP	TEMPORARY TRAFFIC CONTROL	Lump Sum	L.S.	
0020	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	40,712 LF		
0021	5325000000-E	1510	*** WATER LINE (1)	535 LF		
0022	5835000000-E	1540	*** ENCASEMENT PIPE (2)	160 LF		
0023	6000000000-E	1605	TEMPORARY SILT FENCE	1,164 LF		
0024	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	8 TON		
0025	6012000000-E	1610	SEDIMENT CONTROL STONE	30 TON		
0026	6030000000-E	1630	SILT EXCAVATION	16 CY		
0027	6036000000-E	1631	MATTING FOR EROSION CONTROL	10,245 SY		
0028	6042000000-E	1632	1/4" HARDWARE CLOTH	180 LF		
0029	6071010000-E	SP	WATTLE	60 LF		
0030	6071020000-E	SP	POLYACRYLAMIDE (PAM)	3 LB		
0031	6071030000-E	1640	COIR FIBER BAFFLE	12 LF		
0032	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	100 LB		
0033	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	3 EA		
0034	6015000000-E	1615	TEMPORARY MULCHING	1 ACR		
0035	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0036	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.2 TON		
0037	6084000000-E	1660	SEEDING & MULCHING	2 ACR		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	6108000000-E	1665	FERTILIZER TOPDRESSING	0.75		
				TON		

1602/May03/Q94990.91/D141583960000/E38

Total Amount Of Bid For Entire Project :
