PROJECT NO.	SHEET NO.	TOTAL NO.
14CR.20871.13	5	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	1½" MILLING SY	3" MILLING SY	INCIDENTAL MILLING SY	INTERMEDIATE COURSE, I19.0B TONS	SURFACE COURSE, S9.5B TONS	ASPHALT BINDER FOR PLANT MIX TONS	CURB RAMPS EA	ADJ. OF METER OR VALVE BOX EA
14CR.20871.13	Swain	1	SR-1361	FROM CHG PVT WEST OF US441 TO PVT CHG WEST OF SR-1390	1	2	2WU	NO	NO	0.37	21	900				506	30		
TOTAL FOR MAP NO. 1										**0.37**		**900**				**506**	**30**		
14CR.20871.13	Swain	2	SR-1390	FROM SR-1361 TO US 19	2	2	2WU	NO	NO	0.56	28		2,816	100	530	1,968	143	10	1
TOTAL FOR MAP NO. 2										**0.56**			**2,816**	**100**	**530**	**1,968**	**143**	**10**	**1**
14CR.20871.13	Swain	3	SR-1198	FROM SR-1158 TO END OF MAINT	3	2	2WU	NO	NO	0.13	18					125			
TOTAL FOR MAP NO. 3										**0.13**						**125**			
14CR.20871.13	Swain	4	SR-1391	FROM PVT CHG AT US-19 TO PVT CHG AT US 441	3	2	2WU	NO	NO	0.68	21					765	46		
TOTAL FOR MAP NO. 4										**0.68**						**765**	**46**		
TOTAL FOR PROJ NO. 14CR.20871.13										**1.74**		**900**	**2,816**	**100**	**530**	**3,364**	**219**	**10**	**1**
GRAND TOTAL										**1.74**		**900**	**2,816**	**100**	**530**	**3,364**	**219**	**10**	**1**

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	4400000000-E STATIONARY WORK ZONE SIGN SF	4457000000-N TEMPORY TRAFFIC CONTROL LS
14CR.20871.13	Swain	1	SR-1361	FROM CHG PVT WEST OF US441 TO PVT CHG WEST OF SR-1390	1	2	2WU	0.37	21	42.0	1
TOTAL FOR MAP NO. 1								**0.37**		**42.0**	**1**
14CR.20871.13	Swain	2	SR-1390	FROM SR-1361 TO US 19	2	2	2WU	0.56	28	63.0	
TOTAL FOR MAP NO. 2								**0.56**		**63.0**	
14CR.20871.13	Swain	3	SR-1198	FROM SR-1158 TO END OF MAINT	3	2	2WU	0.13	18	15.0	
TOTAL FOR MAP NO. 3								**0.13**		**15.0**	
14CR.20871.13	Swain	4	SR-1391	FROM PVT CHG AT US-19 TO PVT CHG AT US 441	3	2	2WU	0.68	21	76.0	
TOTAL FOR MAP NO. 4								**0.68**		**76**	
TOTAL FOR PROJ NO. 14CR.20871.13								**1.74**		**196**	**1**
GRAND TOTAL								**1.74**		**196**	**1**