PROJECT NO.	SHEET NO.	TOTAL NO.
14CR.10441.12, 14CR.20441.13	7	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	1½" MILLING SY	2 ½" MILLING SY	INTERMEDIATE COURSE, I19.0B TONS	SURFACE COURSE, S9.5B TONS	SURFACE COURSE, SF9.5A TONS	SURFACE COURSE, (LEVELING), SF9.5A TN	ASPHALT BINDER FOR PLANT MIX TONS	2'-6" CURB & GUTTER LF	4" CONCRETE SIDEWALK SY	CURB RAMPS EA	PORTABLE LIGHTING EA	INDUCTIVE LOOP LF	LEAD-IN CABLE LF
14CR.10441.12	Haywood	1	US 19/23	FROM WEST CANTON CITY LIMITS TO EAST /WEST SPLIT	1	5	MU	NO	NO	1.05	50	35,700	10,500	1,650	3,009						2	1.0	2,000	500
TOTAL FOR MAP NO. 1										**1.05**		**35,700**	**10,500**	**1,650**	**3,009**						**2**	**1.0**	**2,000**	**500**
14CR.10441.12	Haywood	2	US 19/23 (EAST BOUND ONLY)	FROM EAST/WEST SPLIT TO THE EAST/WEST SPLIT	2	2	MU	NO	NO	0.47	30	9,100	4,550	650	768			46	50	35.00	30		500	50
TOTAL FOR MAP NO. 2										**0.47**		**9,100**	**4,550**	**650**	**768**			**46**	**50**	**35.00**	**30**		**500**	**50**
14CR.10441.12	Haywood	3	US 19/23	FROM EAST/WEST SPLIT TO EAST CANTON CITY LIMITS	3	2		NO	NO	0.9	36	20,900	2,090	300	1,762				50	35.00			200	50
TOTAL FOR MAP NO. 3										**0.9**		**20,900**	**2,090**	**300**	**1,762**				**50**	**35.00**			**200**	**50**
TOTAL FOR PROJ NO. 14CR.10441.12										**2.42**		**65,700**	**17,140**	**2,600**	**5,539**			**46**	**100**	**70.00**	**32**	**1.0**	**2,700**	**600**
14CR.20441.13	Haywood	4	SR-1111 LAKE LOGAN RD	FROM US 276 TO NC 215	4	2	2WU	NO	NO	2.26	20					2,201	1,117							
TOTAL FOR MAP NO. 4										**2.26**						**2,201**	**1,117**							
14CR.20441.13	Haywood	5	SR-1116 EDWARDS COVE RD	FROM US 276 TO SR-1111	4	2	2WU	NO	NO	1.6	21					1,636	830							
TOTAL FOR MAP NO. 5										**1.6**						**1,636**	**830**							
TOTAL FOR PROJ NO. 14CR.20441.13										**3.86**						**3,837**	**1,947**							
GRAND TOTAL										**6.28**		**65,700**	**17,140**	**2,600**	**5,539**	**3,837**	**1,947**	**46**	**100**	**70.00**	**32**	**1.0**	**2,700**	**600**