STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

PAT MCCRORY
GOVERNOR

ANTHONY J. TATA
SECRETARY

June 21, 2013

ADDENDUM #1

To: Plan Holders

From: Wanda H. Austin, PE Wanda H Austin
Proposals Engineer

RE:
Contract ID: DN00143
County: Haywood
Letting Date: June 25, 2013

The following questions have been asked regarding the above project. Answers are provided in italics.

1. Date of Availability - The proposal lists the Date of Availability as April 14, 2014, yet we are bidding on it June 25, 2013 which is 10 months after the bid date. Is the April 14th date correct or would we be able to begin the project in July or August of 2013? *April 14, 2014, is correct. The contract time is scheduled as such due to a trout moratoria that is in place between October 15 and April 15.*
2. Bid Sheet – On the Summary of Quantities Sheet 3 in the plans, there are four items listed that do not appear on the bid sheet. The items missing are Line Items 7-10 between Line Item 6 Grading and Line Item 11 Select Granular Material.
   The bid sheet lists Select Granular Material as Line Item 7 which means it moved up four lines since the other four items are missing. All the following items have moved up four lines as well. The total of line items should be 76 instead of 72 that appear on the bid sheet.
   - The missing Items include:

A.	Line Item 7	Clearing and Grubbing(0.5 Acres)	1	LS
B.	Line Item 8	Unclassified Excavation	230	CY
C.	Line Item 9	Borrow Excavation	65	CY
D.	Line Item 10	Fine Grading (990 SY)	1	LS

   The items were Clearing and Grubbing, Unclassified Excavation, Borrow, and Fine Grading. These items shall be covered under the contract lump sum price for Grading and should be bid as such. The reason that they are included on the Summary of Quantities on Sheet 3 of the Plan Set is to help aid in the bidding process.
3. Bid Sheet –The quantity for Line Item 15 on the bid sheet, Aggregate Base Course, is listed as 49.088 Ton instead of 49 Ton. Also note on Sheet 3, Aggregate Base Course is Line Item 19 instead of 15 because of the four missing items. *The quantity on the bid*

Fourteenth Division Office
Phone: (828)586-2141 *253 Webster Road, Sylva, North Carolina 28779* *Fax: (828)586-4043*

item sheet has been adjusted. Use the attached bid sheet or the posted addendum file when submitting a bid.

Please insert this letter into the addendum section of the proposal and sign the verification. Thank you for your attention to this matter.

Fourteenth Division Office
Phone: (828)586-2141 *253 Webster Road, Sylva, North Carolina 28779* *Fax: (828)586-4043*

County : Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
			ROADWAY ITEMS			
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUBBING	1 ACR		
0004	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ******* (12+16)	Lump Sum	L.S.	
0005	0036000000-E	225	UNDERCUT EXCAVATION	50 CY		
0006	0043000000-N	226	GRADING	Lump Sum	L.S.	
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	50 CY		
0008	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	50 SY		
0009	0199000000-E	SP	TEMPORARY SHORING	600 SF		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	10 TON		
0011	0320000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	20 SY		
0012	0343000000-E	310	15" SIDE DRAIN PIPE	22 LF		
0013	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	12 LF		
0014	1099700000-E	505	CLASS IV SUBGRADE STABILIZATION	50 TON		
0015	1121000000-E	520	AGGREGATE BASE COURSE	49 TON		
0016	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		
0017	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	210 TON		
0018	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	140 TON		

County : Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	20 TON		
0020	2000000000-N	806	RIGHT OF WAY MARKERS	13 EA		
0021	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1 EA		
0022	2407000000-N	840	STEEL FRAME WITH TWO GRATES, STD 840.37	1 EA		
0023	2556000000-E	846	SHOULDER BERM GUTTER	10 LF		
0024	3030000000-E	862	STEEL BM GUARDRAIL	6.25 LF		
0025	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	12.5 LF		
0026	3165000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE ********** (350, TL-2)	1 EA		
0027	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	3 EA		
0028	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0029	3628000000-E	876	RIP RAP, CLASS I	2 TON		
0030	3649000000-E	876	RIP RAP, CLASS B	15 TON		
0031	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	40 SY		
0032	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	144 SF		
0033	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	20 SF		
0034	4430000000-N	1130	DRUMS	30 EA		
0035	4445000000-E	1145	BARRICADES (TYPE III)	16 LF		
0036	4450000000-N	1150	FLAGGER	32 HR		
0037	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	2 EA		

County : Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	4490000000-E	1170	PORTABLE CONCRETE BARRIER (ANCHORED)	30 LF		
0039	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	1,860 LF		
0040	6000000000-E	1605	TEMPORARY SILT FENCE	500 LF		
0041	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	30 TON		
0042	6012000000-E	1610	SEDIMENT CONTROL STONE	20 TON		
0043	6015000000-E	1615	TEMPORARY MULCHING	0.6 ACR		
0044	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0045	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED-ING	0.25 TON		
0046	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0047	6029000000-E	SP	SAFETY FENCE	100 LF		
0048	6030000000-E	1630	SILT EXCAVATION	20 CY		
0049	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,420 SY		
0050	6042000000-E	1632	1/4" HARDWARE CLOTH	55 LF		
0051	6071020000-E	SP	POLYACRYLAMIDE (PAM)	10 LB		
0052	6084000000-E	1660	SEEDING & MULCHING	0.6 ACR		
0053	6087000000-E	1660	MOWING	0.6 ACR		
0054	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0055	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0056	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0057	6108000000-E	1665	FERTILIZER TOPDRESSING	0.5 TON		

County : Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0058	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0059	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	9 EA		
			STRUCTURE ITEMS			
0060	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ********** (12+16)	Lump Sum	L.S.	
0061	8077000000-E	410	FOUNDATION EXCAVATION (RETAINING WALL)	15 CY		
0062	8084000000-N	410	FOUNDATION EXCAVATION FOR END BENT ** AT STATION ********** (12+16)	Lump Sum	L.S.	
0063	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ******** (12+16)	Lump Sum	L.S.	
0064	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	112.2 CY		
0065	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ********** (12+16)	Lump Sum	L.S.	
0066	8217000000-E	425	REINFORCING STEEL (BRIDGE)	12,201 LB		
0067	8505000000-E	460	VERTICAL CONCRETE BARRIER RAIL	60.29 LF		
0068	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	71 TON		
0069	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	15 SY		
0070	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0071	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	300 LF		

County : Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	8847000000-E	SP	GENERIC RETAINING WALL ITEM (CIP GRAVITY RETAINING WALL)	170 SF		

0811/Jun21/Q20057.04/D311833720000/E72 Total Amount Of Bid For Entire Project :