PROJECT NO.	SHEET NO.	TOTAL NO.
2016CPT.14.02.10871.1.1	6	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	3" MILLING SY	1½" MILLING SY	INCIDENTAL MILLING SY	INTERMEDIATE COURSE, I19.0B TONS	SURFACE COURSE, S9.5B TONS	ASPHALT BINDER FOR PLANT MIX TONS	MILLED RUMBLE STRIPS (ASPHALT CEMENT CONCRETE) LF
14CR.10871.7	Swain	1	US 74 WEST	FROM PVT CHG UNDER SR-1140 TO END DIV HWY	1	2	MD	NO	NO	2.57	28	27,138	4,156		5,105	4,208	497	27,139
TOTAL FOR MAP NO. 1										**2.57**		**27,138**	**4,156**		**5,105**	**4,208**	**497**	**27,139**
14CR.10871.7	Swain	2	US 74 EAST	FROM BEG DIV HWY TO PVT CHG UNDER SR-1140	1	2	MD	NO	NO	2.57	28	27,138	3,620		5,105	4,156	494	27,139
TOTAL FOR MAP NO. 2										**2.57**		**27,138**	**3,620**		**5,105**	**4,156**	**494**	**27,139**
14CR.10871.7	Swain	3	US 74	FROM BEGIN DIV HWY TO PVT CHG .01 MILES WEST OF SR-1123	2	5	MU	NO	NO	0.6	75	10,138		500	1,906	1,821	109	
TOTAL FOR MAP NO. 3										**0.6**		**10,138**		**500**	**1,906**	**1,821**	**109**	
14CR.10871.7	Swain	4	EXIT RAMP 64 TO US19 & SR-1140	FROM US 19/74 EAST TO SR-1140	3	1		NO	NO	0.37	24		5,210			484		
TOTAL FOR MAP NO. 4										**0.37**			**5,210**			**484**		
14CR.10871.7	Swain	5	ACCESS RAMP TO US 19/74 WEST	FROM US 19 TO US 19/74 WEST	4	1		NO	NO	0.43	24		6,054			552	33	
TOTAL FOR MAP NO. 5										**0.43**			**6,054**			**552**	**33**	
14CR.10871.7	Swain	6	ACCESS RAMP TO US 74 EAST	FROM US 19 TO US 74 EAST	4	1		NO	NO	0.27	24		3,802			347		
TOTAL FOR MAP NO. 6										**0.27**			**3,802**			**347**		
TOTAL FOR PROJ NO. 14CR.10871.7										**6.81**		**64,414**	**22,842**	**500**	**12,116**	**11,568**	**1,133**	**54,278**
GRAND TOTAL										**6.81**		**64,414**	**22,842**	**500**	**12,116**	**11,568**	**1,133**	**54,278**

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	4400000000-E STATIONARY WORK ZONE SIGN SF	4457000000-E TEMPORY TRAFFIC CONTROL LS	4697000000-E 8" X 120 M WHITE THERMO LF	4710000000-E 24" X 120 M WHITE THERMO LF	4721000000-E THERMO MSG SCHOOL 120 M EA	4725000000-E THERMO LT ARROW 90 M EA	4725000000-E THERMO RT ARROW 90 M EA	4810000000-E 4" WHITE PAINT LF	4891000000-E GENERIC PAVE MARK ITEM(50 MIL 4" YELLOW THERMO) LF	4891000000-E GENERIC PAVE MARK ITEM(50 MIL 4"WHITE THERMO) LF	4905000000-N SNOW PLOWABLE MARKERS EA
14CR.10871.7	Swain	1	US 74 WEST	FROM PVT CHG UNDER SR-1140 TO END DIV HWY	1	2	MD	2.57	28	292.0	1	1,028	250	6	13	6	6,785	14,084	20,568	245
TOTAL FOR MAP NO. 1								**2.57**		**292.0**	**1**	**1,028**	**250**	**6**	**13**	**6**	**6,785**	**14,084**	**20,568**	**245**
14CR.10871.7	Swain	2	US 74 EAST	FROM BEG DIV HWY TO PVT CHG UNDER SR-1140	1	2	MD	2.57	28	292.0		1,028	250	6	15	2	6,785	14,084	20,568	245
TOTAL FOR MAP NO. 2								**2.57**		**292.0**		**1,028**	**250**	**6**	**15**	**2**	**6,785**	**14,084**	**20,568**	**245**
14CR.10871.7	Swain	3	US 74	FROM BEGIN DIV HWY TO PVT CHG .01 MILES WEST OF SR-1123	2	5	MU	0.6	75	67.0			80		2		3,168	7,920	8,160	
TOTAL FOR MAP NO. 3								**0.6**		**67**			**80**		**2**		**3,168**	**7,920**	**8,160**	
14CR.10871.7	Swain	4	EXIT RAMP 64 TO US19 & SR-1140	FROM US 19/74 EAST TO SR-1140	3	1		0.37	24									2,442	3,981	
TOTAL FOR MAP NO. 4								**0.37**										**2,442**	**3,981**	
14CR.10871.7	Swain	5	ACCESS RAMP TO US 19/74 WEST	FROM US 19 TO US 19/74 WEST	4	1		0.43	24									2,838	4,627	
TOTAL FOR MAP NO. 5								**0.43**										**2,838**	**4,627**	
14CR.10871.7	Swain	6	ACCESS RAMP TO US 74 EAST	FROM US 19 TO US 74 EAST	4	1		0.27	24									1,785	2,905	
TOTAL FOR MAP NO. 6								**0.27**										**1,785**	**2,905**	
TOTAL FOR PROJ NO. 14CR.10871.7								**6.81**		**651**	**1**	**2,056**	**580**	**12**	**30**	**8**	**16,738**	**43,153**	**60,809**	**490**
															38			**103,962**		
GRAND TOTAL								**6.81**		**651**	**1**	**2,056**	**580**	**12**	**30**	**8**	**16,738**	**43,153**	**60,809**	**490**
															38			**103,962**		