




STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

ROY COOPER
GOVERNOR

JAMES H. TROGDON, III
SECRETARY

November 21, 2018

ADDENDUM # 1

To: Plan Holders
From: Wes Jamsion 
Division Project Manager

RE: **Special Provision Addition & Pay Item Addition**
Contract ID: DN006007
County: Haywood
Letting Date: December 11, 2018

The above contract has experienced the following revisions:

I. Special Provision Addition

1. On page **G-2 Table of Contents**, before line Utility Construction.....UC, add the following line:

GEOENVIRONMENTAL.....GV

2. After page **G-67** and before page **UC-1**, add the following section and Project Special Provision:

(See attachment on the next page of this Addendum)

**PROJECT SPECIAL PROVISIONS
GEOENVIRONMENTAL**

CONTAMINATED SOIL (11/20/2018)

The Contractor's attention is directed to the fact that soil contaminated with petroleum hydrocarbon compounds may exist within the project area. The potential areas of contamination are indicated on corresponding plans sheets. Information relating to these contaminated areas, sample locations, and investigation reports will be available at the following web address by navigating to the correct letting year and month then selecting, "Plans and Proposals", "U-6055", "GeoEnv Postings":

<http://dotw-xfer01.dot.state.nc.us/dsplan/>

Petroleum contaminated soil may be encountered during any earthwork activities on the project. The Contractor shall only excavate those soils that the Engineer designates necessary to complete a particular task. The Engineer shall determine if soil is contaminated based on petroleum odors and unusual soil staining. Contaminated soil not required to be excavated is to remain in place and undisturbed. Undisturbed soil shall remain in place, whether contaminated or not. The Contractor shall transport all contaminated soil excavated from the project to a facility licensed to accept contaminated soil.

In the event that a stockpile is needed, the stockpile shall be created within the property boundaries of the source material and in accordance with the Diagram for Temporary Containment and Treatment of Petroleum-Contaminated Soil per North Carolina Department of Environmental Quality's Division of Waste Management UST Section GUIDELINES FOR EX SITU PETROLEUM CONTAMINATED SOIL REMEDIATION. If the volume of contaminated material exceeds available space on site, the Contractor shall obtain a permit from the NCDEQ UST Section's Regional Office for off-site temporary storage. Stockpiling contaminated soil will be incidental to the project. The Contractor shall provide disposal manifests and weigh tickets to the Engineer for review and approval.

Measurement and Payment:

The quantity of contaminated soil hauled, and disposed of shall be the actual number of tons of material, which has been acceptably transported and weighed with certified scales as documented by disposal manifests and weigh tickets. The quantity of contaminated soil, measured as provided above, shall be paid for at the contract unit price per ton for "Hauling and Disposal of Petroleum Contaminated Soil".

The above price and payment shall be full compensation for all work covered by this section, including, but not limited to stockpiling, loading, transportation, weighing, laboratory testing, disposal, equipment, decontamination of equipment, labor, and personal protective equipment.

Payment shall be made under:

Pay Item

Hauling and Disposal of Petroleum Contaminated Soil

Pay Unit

Ton

DocuSigned by:

Cyrus Parker

C96492AF5E824DF...
11/20/2018



II. Pay Item Addition

1. On page T-7 after line item # **0128 6132000000-N Generic Erosion Control Item (Concrete Washout Structure)**, add the following item:

0129 0255000000-E Generic Grading Item (Hauling and Disposal of Petroleum Contaminated Soil) 50 Ton

See attached pay item sheet T-7 on the next page of this addendum showing this revision.

Please access ebs addenda files on Bid Express®.

Thank you for your attention to this matter.

County : Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0111	6012000000-E	1610	SEDIMENT CONTROL STONE	145		TON
0112	6015000000-E	1615	TEMPORARY MULCHING	0.5		ACR
0113	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100		LB
0114	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.5		TON
0115	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200		LF
0116	6030000000-E	1630	SILT EXCAVATION	60		CY
0117	6036000000-E	1631	MATTING FOR EROSION CONTROL	5,000		SY
0118	6037000000-E	SP	COIR FIBER MAT	850		SY
0119	6042000000-E	1632	1/4" HARDWARE CLOTH	675		LF
0120	6084000000-E	1660	SEEDING & MULCHING	0.5		ACR
0121	6087000000-E	1660	MOWING	0.5		ACR
0122	6090000000-E	1661	SEED FOR REPAIR SEEDING	50		LB
0123	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25		TON
0124	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50		LB
0125	6108000000-E	1665	FERTILIZER TOPDRESSING	0.25		TON
0126	6114500000-N	1667	SPECIALIZED HAND MOWING	10		MHR
0127	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	20		EA
0128	6132000000-N	SP	GENERIC EROSION CONTROL ITEM (CONCRETE WASHOUT STRUCTURE)	1		EA
0129	0255000000-E	SP	GENERIC GRADING ITEM (HAULING AND DISPOSAL OF PETROLEUM CONTAMINATED SOIL)	50		TON