




STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION

ROY COOPER  
GOVERNOR

JAMES H. TROGDON, III  
SECRETARY

November 28, 2018

**ADDENDUM # 1**

To: Plan Holders  
From: Wes Jamison   
Division Project Manager

RE: **Pay Item Quantity Revision and Plan Sheet Revision**  
Contract ID: DN00664  
County: Haywood; Jackson  
Letting Date: December 11, 2018

The above contract has experienced the following revisions:

**I. Pay Item Quantity Revision**

On page T-1, revise Line Item # **0005 1519000000-E Asphalt Conc Surface Course, Type S9.5B 7,174 Ton** to the following :

**0005 1519000000-E Asphalt Conc Surface Course, Type S9.5B 6,558 Ton**

On page T-1, revise Line Item # **0007 1523000000-E Asphalt Conc Surface Course, Type S9.5C 735 Ton** to the following:

**0007 1523000000-E Asphalt Conc Surface Course, Type S9.5C 1,422 Ton**

See attached bid item sheet T-1 on the following page of this addendum showing these revisions.

County : Haywood, Jackson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	1245000000-E	SP	SHOULDER RECONSTRUCTION	26.2	SMI	
0003	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1.5)	8,245	SY	
0004	1330000000-E	607	INCIDENTAL MILLING	444	SY	
0005	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	6,558	TON	
0006	1520000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE S9.5B (LEVELING COURSE)	771	TON	
0007	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	1,422	TON	
0008	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	576	TON	
0009	1704000000-E	SP	PATCHING EXISTING PAVEMENT	326	TON	
0010	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	3	EA	
0011	4413000000-E	SP	WORK ZONE ADVANCE/GENERAL WARNING SIGNING	1,017	SF	
0012	4457000000-N	SP	TEMPORARY TRAFFIC CONTROL	Lump Sum	L.S.	
0013	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	390,804	LF	
0014	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	140	LF	
<b>0911/Nov28/Q410334.2/D33073100000/E14</b>				<b>Total Amount Of Bid For Entire Project :</b>		

## II. Plan Sheet Revision

Replace **Plan Sheet No. 5, Summary of Quantities**, with the attached sheet on the following page of this addendum showing revisions to Surface Course, S9.5B and Surface Course, S9.5C quantities.

Please access ebs addenda files on Bid Express®.

Thank you for your attention to this matter.

PROJECT NO.	SHEET NO.	TOTAL NO.
2020CPT.14.04.20441, Ect.	5	

### SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	1245000000-E	1297000000-E	1330000000-E	1519000000-E	1520000000-E	1523000000-E	1575000000-E	1704000000-E	2845000000-N	
												SHOULDER RECONSTRUCTION	1 1/2" MILLING	INCIDENTAL MILLING	SURFACE COURSE, \$9.5B	LEVELING COURSE, \$9.5B	SURFACE COURSE, \$9.5C	ASPHALT BINDER FOR PLANT MIX	PATCHING EXISTING PAVEMENT	ADJ. OF METER OR VALVE BOX	
											MI	FT	SMI	SY	SY	TONS	TONS	TONS	TONS	TONS	EA
2020CPT.14.04.20441	Haywood	1	SR-1513 (HYDER MOUNTAIN RD)	FROM SR-1533 TO SR-1642	2	2	2WU	NO	NO	1.99	20	3.96		111	1,629	31		111	12	1	
<b>TOTAL FOR MAP NO. 1</b>											<b>1.99</b>		<b>3.96</b>		<b>111</b>	<b>1,629</b>	<b>31</b>		<b>111</b>	<b>12</b>	<b>1</b>
2020CPT.14.04.20441	Haywood	2	SR-1519 (RICHLAND CREEK RD)	FROM SR-1523 TO NC-209	1	2	2WU	NO	NO	1.63	20	2.66		111	1,364			91	25	2	
<b>TOTAL FOR MAP NO. 2</b>											<b>1.63</b>		<b>2.66</b>		<b>111</b>	<b>1,364</b>			<b>91</b>	<b>25</b>	<b>2</b>
<b>TOTAL FOR PROJ NO. 2020CPT.14.04.20441</b>											<b>3.62</b>		<b>6.62</b>		<b>222</b>	<b>2,993</b>	<b>31</b>		<b>202</b>	<b>37</b>	<b>3</b>
2020CPT.14.04.20501	Jackson	3	SR-1145 (NORTH NORTON RD)	FROM PVMT CHNG .3MI EAST OF SR-1153 TO PVMT CHNG .3MI EAST OF SR-1144	1	2	2WU	NO	NO	4.25	20	18.06		111	3,565			239	289		
<b>TOTAL FOR MAP NO. 3</b>											<b>4.25</b>		<b>18.06</b>		<b>111</b>	<b>3,565</b>			<b>239</b>	<b>289</b>	
2020CPT.14.04.20501	Jackson	4	SR-1330 (FOREST HILLS RD)	FROM SR-1325 TO PVMT CHNG AT NC-107	3	2	2WU	NO	NO	0.45	30		8,245				668	40			
<b>TOTAL FOR MAP NO. 4</b>											<b>0.45</b>			<b>8,245</b>				<b>668</b>	<b>40</b>		
2020CPT.14.04.20501	Jackson	5	SR-1330 (NORTH COUNTRY CLUB DR/COX FARM RD)	FROM PVMT CHNG AT NC-107 TO END OF LOOP	4	2	2WU	NO	NO	0.76	20	1.52		111		740	754	95			
<b>TOTAL FOR MAP NO. 5</b>											<b>0.76</b>		<b>1.52</b>		<b>111</b>		<b>740</b>	<b>754</b>	<b>95</b>		
<b>TOTAL FOR PROJ NO. 2020CPT.14.04.20501</b>											<b>5.46</b>		<b>19.58</b>	<b>8,245</b>	<b>222</b>	<b>3,565</b>	<b>740</b>	<b>1,422</b>	<b>374</b>	<b>289</b>	
<b>GRAND TOTAL</b>											<b>9.08</b>		<b>26.20</b>	<b>8,245</b>	<b>444</b>	<b>6,558</b>	<b>771</b>	<b>1,422</b>	<b>576</b>	<b>326</b>	<b>3</b>

### THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	4413000000-E	4457000000-N	4810000000-E		4835000000-E		
										WORK ZONE ADVANCE/GENERAL WARNING SIGNING	TEMPORARY TRAFFIC CONTROL	4" WHITE PAINT	4" YELLOW PAINT	24" WHITE PAINT		
										SF	LS	LF	LF	LF		
2020CPT.14.04.20441	Haywood	1	SR-1513 (HYDER MOUNTAIN RD)	FROM SR-1533 TO SR-1642	2	2	2WU	1.99	20	223	1.00	42,825	42,825			
<b>TOTAL FOR MAP NO. 1</b>											<b>1.99</b>	<b>223</b>	<b>42,825</b>	<b>42,825</b>		
2020CPT.14.04.20441	Haywood	2	SR-1519 (RICHLAND CREEK RD)	FROM SR-1523 TO NC-209	1	2	2WU	1.63	20	183		35,078	35,078			
<b>TOTAL FOR MAP NO. 2</b>											<b>1.63</b>	<b>183</b>	<b>35,078</b>	<b>35,078</b>		
<b>TOTAL FOR PROJ NO. 2020CPT.14.04.20441</b>											<b>3.62</b>	<b>406</b>	<b>77,903</b>	<b>77,903</b>		
													<b>155,806</b>			
2020CPT.14.04.20501	Jackson	3	SR-1145 (NORTH NORTON RD)	FROM PVMT CHNG .3MI EAST OF SR-1153 TO PVMT CHNG .3MI EAST OF SR-1144	1	2	2WU	4.25	20	476		91,460	91,460			
<b>TOTAL FOR MAP NO. 3</b>											<b>4.25</b>	<b>476</b>	<b>91,460</b>	<b>91,460</b>		
2020CPT.14.04.20501	Jackson	4	SR-1330 (FOREST HILLS RD)	FROM SR-1325 TO PVMT CHNG AT NC-107	3	2	2WU	0.45	30	50		9,684	9,684	140		
<b>TOTAL FOR MAP NO. 4</b>											<b>0.45</b>	<b>50</b>	<b>9,684</b>	<b>9,684</b>	<b>140</b>	
2020CPT.14.04.20501	Jackson	5	SR-1330 (NORTH COUNTRY CLUB DR/COX FARM RD)	FROM PVMT CHNG AT NC-107 TO END OF LOOP	4	2	2WU	0.76	20	85		16,355	16,355			
<b>TOTAL FOR MAP NO. 5</b>											<b>0.76</b>	<b>85</b>	<b>16,355</b>	<b>16,355</b>		
<b>TOTAL FOR PROJ NO. 2020CPT.14.04.20501</b>											<b>5.46</b>	<b>611</b>	<b>117,499</b>	<b>117,499</b>	<b>140</b>	
													<b>234,998</b>			
<b>GRAND TOTAL</b>											<b>9.08</b>	<b>1,017</b>	<b>1</b>	<b>195,402</b>	<b>195,402</b>	<b>140</b>
													<b>390,804</b>			