



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

PAT MCCRORY
GOVERNOR

ANTHONY J. TATA
SECRETARY

December 31, 2014

CONTRACT: DB00208
WBS ELEMENT: 42287.3.FR2
FEDERAL-AID NO: BRZ-0304(4)
COUNTY: Pamlico
ROUTE: NC 304
DESCRIPTION: Replace Bridge #24 on NC 304 over North Prong of Bay River

ADDENDUM NUMBER 2

TO: Prospective Bidders

Please note the following revision to the contract proposal for the above-referenced project.

- The correction of Line Item 43 from "GENERIC UTILITY ITEM RELOCATE 8" WATER MAIN" to "GENERIC UTILITY ITEM RELOCATE 10" SANITARY SEWER MAIN"

Please see the attached updated proposal items and the Addendum EBS file on our letting website.

Sincerely,

A handwritten signature in black ink, appearing to read "Sarah Lentine".

Sarah Lentine
Division Contract Officer

cc: Mr. Ed Eatmon, PE
Mr. Bill Kincannon, PE

MAILING ADDRESS:
DIVISION TWO - OPERATIONS
P.O. BOX 1587
GREENVILLE, NC 27835

TELEPHONE: (252) 439-2800
FAX: (252) 830-3341
WEBSITE: WWW.NCDOT.GOV

LOCATION:
1704 N GREENE ST
GREENVILLE, NC

County : Pamlico

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (1+00)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0006	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	60 TON		
0007	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	190 SY		
0008	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	556 LF		
0009	0995000000-E	340	PIPE REMOVAL	36 LF		
0010	1220000000-E	545	INCIDENTAL STONE BASE	20 TON		
0011	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH 1.5" (BRIDGE)	300 SY		
0012	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH 3"	13,638 SY		
0013	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	575 TON		
0014	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	1,672 TON		
0015	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	4,466 TON		
0016	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	375 TON		
0017	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	11 EA		

County : Pamlico

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** 1	11 EA		
0019	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	1,100 LF		
0020	2591000000-E	848	4" CONCRETE SIDEWALK	280 SY		
0021	2605000000-N	848	CONCRETE CURB RAMP	8 EA		
0022	2800000000-N	858	ADJUSTMENT OF CATCH BASINS	1 EA		
0023	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	15 LF		
0024	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0025	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	4 EA		
0026	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	1 EA		
0027	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0028	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	2 EA		
0029	3628000000-E	876	RIP RAP, CLASS I	5 TON		
0030	3649000000-E	876	RIP RAP, CLASS B	5 TON		
0031	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	50 SY		
0032	4399000000-N	1105	TEMPORARY TRAFFIC CONTROL	Lump Sum	L.S.	
0033	4413000000-E	SP	WORK ZONE ADVANCE/GENERAL WARNING SIGNING	224 SF		
0034	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	34,051 LF		
0035	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	300 LF		

County : Pamlico

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	60 LF		
0037	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	6 EA		
0038	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	34,051 LF		
0039	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	300 LF		
0040	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	60 LF		
0041	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	6 EA		
0042	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	117 EA		
0043	5912000000-N	SP	GENERIC UTILITY ITEM RELOCATE 10" SANITARY SEWER MAIN	Lump Sum	L.S.	
0044	6000000000-E	1605	TEMPORARY SILT FENCE	1,300 LF		
0045	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	5 TON		
0046	6012000000-E	1610	SEDIMENT CONTROL STONE	15 TON		
0047	6015000000-E	1615	TEMPORARY MULCHING	1 ACR		
0048	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0049	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.2 TON		
0050	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0051	6029000000-E	SP	SAFETY FENCE	300 LF		
0052	6030000000-E	1630	SILT EXCAVATION	15 CY		
0053	6036000000-E	1631	MATTING FOR EROSION CONTROL	700 SY		

County : Pamlico

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	6042000000-E	1632	1/4" HARDWARE CLOTH	440	LF	
0055	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	300	SY	
0056	6071010000-E	SP	WATTLE	200	LF	
0057	6084000000-E	1660	SEEDING & MULCHING	1	ACR	
0058	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
0059	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.2	TON	

STRUCTURE ITEMS

0060	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** 1	Lump Sum	L.S.	
0061	8112730000-N	450	PDA TESTING	2	EA	
0062	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** 1	Lump Sum	L.S.	
0063	8156000000-E	SP	CONCRETE WEARING SURFACE	3,139	SF	
0064	8161000000-E	420	GROOVING BRIDGE FLOORS	4,039	SF	
0065	8175000000-E	420	CLASS AA CONCRETE (BRIDGE)	129.3	CY	
0066	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** 1	Lump Sum	L.S.	
0067	8224000000-E	425	EPOXY COATED REINFORCING STEEL (BRIDGE)	11,806	LB	
0068	8333000000-E	450	16" PRESTRESSED CONCRETE PILES	960	LF	
0069	8350000000-E	450	24" PRESTRESSED CONCRETE PILES	640	LF	

County : Pamlico

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0070	8392500000-E	450	PREDRILLING FOR PILES	320		
				LF		
0071	8393000000-N	450	PILE REDRIVES	10		
				EA		
0072	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	124		
				TON		
0073	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	138		
				SY		
0074	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0075	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,540		
				LF		
0076	8860000000-N	SP	GENERIC STRUCTURE ITEM AESTHETIC LIGHTING	Lump Sum	L.S.	
0077	8867000000-E	SP	GENERIC STRUCTURE ITEM DECORATIVE METAL RAIL & CONCRE TE PARAPET	307.67		
				LF		
1609/Dec31/Q119508.37/D362746940000/E77				Total Amount Of Bid For Entire Project :		