



ROY COOPER
Governor

MICHAEL L. HOLDER
Acting Secretary

January 6, 2017

CONTRACT: DB00327
WBS ELEMENT: DF15002.2040801
COUNTY: Greene
ROUTE: SR1247
DESCRIPTION: Emergency Repair Hurricane Matthew Related

ADDENDUM 1

TO: PROSPECTIVE BIDDERS

Please note the following revision to the proposal for the above referenced project.

- **ADD** Line Item 32... 1121000000-E Aggregate Base Course 848 TONS. Please see attached revised list of bid items.
- **Proposal Page 70 “Dewatering” Special Provision** delete the following sentence from the description “The contractor may elect to dewater using sheet pile or aqua barriers”. And replace with “The contractor will be required to dewater using aqua barrier”.
- **Proposal Page 71 “Installation of state supplied 13’-1” x 8’-2” Aluminum Structural Plate Pipe with Headwalls” Special Provision** Add the following sentence to the description “The assembly of the 13’-1” x 8’-2” aluminum structural pipe will be required to be done within the excavation”.

If electing to use the Computer Bid Preparation process, the Expedite File has been updated to reflect these revisions. Please download the Expedite Addendum File and follow the instructions for applying the addendum.

The Contractor’s bid must be based on these revised pay item quantities. The contract will be prepared accordingly.



Sincerely,

A handwritten signature in black ink, appearing to read "Rich Godley". The signature is fluid and cursive, with the first name "Rich" being more prominent than the last name "Godley".

Rich Godley
Assistant DDC Engineer

cc: Mr. Ed Eatmon, PE
Mr. Arron Bullard, PE
Mr. William Kincannon, PE
Mrs. Heather Lane, PE
Ms. Claudia Wainwright
Mr. Jim Evans

County : Greene

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0022000000-E	225	UNCLASSIFIED EXCAVATION	85 CY		
0004	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	300 SY		
0005	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	190 SY		
0006	1077000000-E	SP	#57 STONE	485 TON		
0007	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	100 TON		
0008	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	65 TON		
0009	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	45 TON		
0010	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	15 TON		
0011	3030000000-E	862	STEEL BM GUARDRAIL	250 LF		
0012	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0013	6000000000-E	1605	TEMPORARY SILT FENCE	285 LF		
0014	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	5 TON		
0015	6012000000-E	1610	SEDIMENT CONTROL STONE	10 TON		
0016	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0017	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.2 TON		
0018	6029000000-E	SP	SAFETY FENCE	200 LF		
0019	6036000000-E	1631	MATTING FOR EROSION CONTROL	100 SY		

County : Greene

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	6042000000-E	1632	1/4" HARDWARE CLOTH	70 LF		
0021	6071012000-E	SP	COIR FIBER WATTLE	50 LF		
0022	6071020000-E	SP	POLYACRYLAMIDE (PAM)	2 LB		
0023	6084000000-E	1660	SEEDING & MULCHING	1 ACR		
0024	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0025	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.2 TON		
0026	6111000000-E	SP	IMPERVIOUS DIKE	85 LF		
0027	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	3 EA		
0028	6133000000-N	SP	GENERIC EROSION CONTROL ITEM DEWATERING	Lump Sum	L.S.	
0029	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** -L-12+88.36	Lump Sum	L.S.	
0030	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** -L-12+88.36	Lump Sum	L.S.	
0031	8804000000-N	SP	GENERIC CULVERT ITEM -L-12+88.36 NCDOT SUPPLIED 13'-1" x 8'-2" ASPP W/ HEADWAL LS	Lump Sum	L.S.	
0032	1121000000-E	520	AGGREGATE BASE COURSE	848 TON		

1149/Jan06/Q3304.4/D136842532000/E32

Total Amount Of Bid For Entire Project :