



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

ROY COOPER
GOVERNOR

J. ERIC BOYETTE
SECRETARY

January 19, 2023

CONTRACT: DB00554
TIP NUMBER: H-2002E
WBS ELEMENT: 49300.3.6
COUNTY: PITT
ROUTE: US 264A AT SR 1534
DESCRIPTION: CONSTRUCTION OF TURN LANES WITH BULB-OUTS AND
CONCRETE CHANNELIZATION ISLANDS AT US 264A AT
SR 1534 IN PITT COUNTY

ADDENDUM 1

TO: PROSPECTIVE BIDDERS

Please note the following revisions to the proposal.

- Revision of Item Number 9 to Asphalt Conc Surface Course, Type S9.5C.
- Please see attached page A1-A2.
- A revised electronic file has been uploaded to bid express named DB00554.001.

Please make sure to sign the addendum page in the proposal to acknowledge this addendum.

Sincerely,

DocuSigned by:
Mary Voelker Moore
714C11DCC4C6...

Mary Voelker Moore, PE
Division Contract Engineer

cc: Ms. Heather C. Lane, PE
Ms. Sarah Lentine, PE
Mr. Cadmus Capehart, PE
Mr. Steve Hamilton, PE
Mr. Jordan Scott, PE
Mr. Rich Godley
Mr. Jim Evans

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	10 TON		
0005	0320000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	10 SY		
0006	0448300000-E	310	18" RC PIPE CULVERTS, CLASS IV	10 LF		
0007	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	770 TON		
0008	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	470 TON		
0009	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	230 TON		
0010	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	75 TON		
0011	2253000000-E	840	PIPE COLLARS	0.45 CY		
0012	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1 EA		
0013	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	1 EA		
0014	2647000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED)	484.5 SY		
0015	4413000000-E	SP	WORK ZONE ADVANCE/GENERAL WARNING SIGNING	96 SF		
0016	4457000000-N	SP	TEMPORARY TRAFFIC CONTROL	Lump Sum	L.S.	
0017	4688000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)	4,700 LF		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	1,500 LF		
0019	4709000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 90 MILS)	100 LF		
0020	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	6 EA		
0021	4855000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (6")	600 LF		
0022	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	5 EA		
0023	6000000000-E	1605	TEMPORARY SILT FENCE	700 LF		
0024	6012000000-E	1610	SEDIMENT CONTROL STONE	10 TON		
0025	6036000000-E	1631	MATTING FOR EROSION CONTROL	50 SY		
0026	6042000000-E	1632	1/4" HARDWARE CLOTH	25 LF		
0027	6071012000-E	SP	COIR FIBER WATTLE	50 LF		
0028	6071020000-E	SP	POLYACRYLAMIDE (PAM)	1 LB		
0029	6084000000-E	1660	SEEDING & MULCHING	1 ACR		
0030	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0031	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.2 TON		
0032	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	3 EA		
0033	6117500000-N	SP	CONCRETE WASHOUT STRUCTURE	1 EA		