PROJECT NO.	SHEET NO.	TOTAL NO.
2CR.10741.22, 2CR.20541.9	5	5
2CR.20741.11,		

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	1½" MILLING THROUGH C&G SY	1½" MILLING SY	SURFACE COURSE, S9.5B TONS	SURFACE COURSE, SF9.5A TONS	ASPHALT BINDER FOR PLANT MIX TONS	ADJ. OF MANHOLES EA	ADJ. OF METER OR VALVE BOX EA
2CR.10741.22	Pitt	1	NC 118, QUEEN STREET	1.5" MILL AND RESURFACE FROM NC 118 / SR 1939 INTERSECTION TO SR 1907	1	2	2WU	NO	NO	0.38	44.27	9,869		831		50	14	9
TOTAL FOR MAP NO. 1										**0.38**		**9,869**		**831**		**50**	**14**	**9**
TOTAL FOR PROJ NO. 2CR.10741.22										**0.38**		**9,869**		**831**		**50**	**14**	**9**
2CR.20541.9	Lenoir	2	SR 1800, CONTENTNEA DR / TICK BITE RD	1.5" RESURFACING FROM NC 118 TO 0.8 MILE SE (NEAR BRANDON RD)	2	2	2WU	NO	NO	0.8	19			769		46		
TOTAL FOR MAP NO. 2										**0.8**				**769**		**46**		
TOTAL FOR PROJ NO. 2CR.20541.9										**0.8**				**769**		**46**		
2CR.20741.11	Pitt	3	SR 1907, CHURCH ST / MARVIN TAYLOR RD	1.5" MILLING AND RESURFACING FROM NC 118 TO END C&G (ST. DAVID ST.)	1	2	2WU	NO	NO	0.48	32	10,124		783		47	14	17
		3	SR 1907, MARVIN TAYLOR RD	1.5" RESURFACING, END OF C&G (ST. DAVID ST.) TO SR 1902	2	2	2WU	NO	NO	4.8	20			4,760		286		
TOTAL FOR MAP NO. 3										**5.28**		**10,124**		**5,543**		**333**	**14**	**17**
2CR.20741.11	Pitt	4	SR 1909, DAWSON RD	1.5" RESURFACING FROM SR 1907 TO NC 118	3	2	2WU	NO	NO	1.04	18				966	58		
TOTAL FOR MAP NO. 4										**1.04**					**966**	**58**		
2CR.20741.11	Pitt	5	SR 1910, MLK DR	1.5" MILLING AND RESURFACING FROM NC 118 TO 75' SOUTH OF CREEK SHORE DR.	4	2	2WU	NO	NO	0.14	36		5,491		254	15	3	4
		5	SR 1910, CREEK SHORE DR	1.5" MILLING AND RESURFACING FROM MLK DR. TO END OF C&G	4	2	2WU	NO	NO	0.1	36				187	11		
		5	SR 1910, CREEK SHORE DR / WILEY GASKINS RD	1.5" RESURFACING FROM END OF C&G TO SR 1914	3	2	2WU	NO	NO	1.6	20				1,619	97		
TOTAL FOR MAP NO. 5										**1.84**			**5,491**		**2,060**	**123**	**3**	**4**
2CR.20741.11	Pitt	6	SR 1911, WALL STREET	1.5" RESURFACING FROM SR 1909 TO PAVEMENT JOINT @ NCL GRIFTON	3	2	2WU	NO	NO	0.65	20				658	39		
TOTAL FOR MAP NO. 6										**0.65**					**658**	**39**		
2CR.20741.11	Pitt	7	SR 1940, DUDLEY RD	1.5" RESURFACING FROM SR 1939 TO SR 1110	3	2	2WU	NO	NO	0.47	20				480	29		
TOTAL FOR MAP NO. 7										**0.47**					**480**	**29**		
TOTAL FOR PROJ NO. 2CR.20741.11										**9.28**		**10,124**	**5,491**	**5,543**	**4,164**	**582**	**17**	**21**
GRAND TOTAL										**10.46**		**19,993**	**5,491**	**7,143**	**4,164**	**678**	**31**	**30**