PROJECT NO.	SHEET NO.	TOTAL NO.
2CR.20521.10	4	5

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	SHOULDER RECONSTRUCTION SMI	INCIDENTAL MILLING SY	SURFACE COURSE, SF9.5A TONS	ASPHALT BINDER FOR PLANT MIX TON	SEED & MULCHING AC
2CR.20521.10	Jones	1	SR 1321	FROM SR 1002 TO DEAD END	1	2		NO	NO	0.743	19	1.49	222	895	60	0.36
TOTAL FOR MAP NO. 1										**0.743**		**1.49**	**222**	**895**	**60**	**0.36**
2CR.20521.10	Jones	2	SR 1329	FROM SR 1002 TO DEAD END	1	2		NO	NO	0.532	20	1.06	222	654	44	0.26
TOTAL FOR MAP NO. 2										**0.532**		**1.06**	**222**	**654**	**44**	**0.26**
2CR.20521.10	Jones	3	SR 1332	FROM SR 1121 TO SR 1002	1	2		NO	NO	1.402	18	2.80	222	1,551	104	0.68
TOTAL FOR MAP NO. 3										**1.402**		**2.80**	**222**	**1,551**	**104**	**0.68**
2CR.20521.10	Jones	4	SR 1333	FROM SR 1121 TO SR 1002	1	2		NO	NO	1.097	20	2.19	222	1,348	90	0.53
TOTAL FOR MAP NO. 4										**1.097**		**2.19**	**222**	**1,348**	**90**	**0.53**
2CR.20521.10	Jones	5	SR 1123	FROM SR 1124 TO END OF PVMNT	1	2		NO	NO	0.643	20	1.29	222	805	54	0.31
TOTAL FOR MAP NO. 5										**0.643**		**1.29**	**222**	**805**	**54**	**0.31**
TOTAL FOR PROJ NO. 2CR.20521.10										**4.417**		**8.83**	**1,110**	**5,253**	**352**	**2.14**
GRAND TOTAL										**4.417**		**8.83**	**1,110**	**5,253**	**352**	**2.14**