



STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION

ROY COOPER  
GOVERNOR

JAMES H. TROGDON, III  
SECRETARY

April 6, 2018

CONTRACT: DB00414  
WBS ELEMENT: 2018CPT.02.54.10071  
COUNTY: Beaufort  
ROUTE: NC 32  
DESCRIPTION: Patching, Strengthening, Resurfacing, Pavement Markings, and Pavement Markers on NC 32 from Bridge #21 to the Washington County Line in Beaufort County

**ADDENDUM 1**

TO: PROSPECTIVE BIDDERS

Please note the following revisions to the proposal.

- Revised the Price Adjustment – Asphalt Binder for Plant Mix to \$429.00. A revised page 26 Add 1 is attached.
- A revised electronic file has been uploaded to bid express named DB00414.001.

**Please make sure to sign the addendum page in the proposal to acknowledge this addendum.**

Sincerely,

DocuSigned by:  
*Mary Voelker Moore*  
714C11DCCEBC4C6...

Mary Voelker Moore, PE  
Division Contract Engineer

cc: Mr. Jeremy Stroud, PE  
Ms. Sarah F. Lentine, PE  
Mr. William Kincannon, PE  
Ms. Claudia Wainwright

*Mailing Address:*  
NC DEPARTMENT OF TRANSPORTATION  
DIVISION 2  
PROJECT DEVELOPMENT GROUP  
PO BOX 1587  
GREENVILLE, NC 27835-1587

*Telephone:* (252) 439-2828  
*Customer Service:* 1-877-368-4968

*Website:* www.ncdot.gov

*Location:*  
1037 W.H. SMITH BLVD.  
GREENVILLE, NC 27835

included to address drop off issues identified by the Engineer after paving is completed. Shoulder Reconstruction shall not be performed unless directed by the Engineer. Excessive material generated from the existing pavement prior to paving shall be removed by the Contractor and is considered incidental to the asphalt pavement line items as stated in the Note to Contractor on page DIV2-1.

*Hauling NCDOT Supplied Shoulder Material* will be measured and paid as the actual number of loads of material delivered to the project.

*Incidental Stone Base* will be measured and paid as provided in Article 545-6 of the *2018 Standard Specifications*.

*Seeding and Mulching* will be measured and paid as shown elsewhere in the contract documents.

Payment will be made under:

<b>Pay Item</b>	<b>Pay Unit</b>
Shoulder Reconstruction	Shoulder Mile
Hauling NCDOT Supplied Material	Each

**SHOULDER RECONSTRUCTION PROCEDURE:**

(7-1-95) (Rev. 10-15-13)

560

SP1 R10BR

Perform shoulder reconstruction immediately following paving operations and in no case allow paving operations to exceed shoulder operations by more than two weeks without written permission of the Engineer. Failure to meet this requirement shall be cause to cease paving operations until it can be met. Place final pavement marking after shoulder reconstruction.

Upon completion of shoulder reconstruction, remove construction signs and use on other projects or store at the county maintenance installation or as directed by the Engineer.

**PRICE ADJUSTMENT - ASPHALT BINDER FOR PLANT MIX:**

(11-21-00)

620

SP6 R25

Price adjustments for asphalt binder for plant mix will be made in accordance with Section 620 of the *2018 Standard Specifications*.

The base price index for asphalt binder for plant mix is **\$429.00** per ton.

This base price index represents an average of F.O.B. selling prices of asphalt binder at supplier's terminals on **March 1, 2018**.

**FINAL SURFACE TESTING NOT REQUIRED:**

(5-18-04) (Rev. 2-16-16)

610

SP6 R45

Final surface testing is not required on this project in accordance with Section 610-13, *Final Surface Testing and Acceptance*.