



STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION

ROY COOPER  
GOVERNOR

J. ERIC BOYETTE  
SECRETARY

April 4, 2023

CONTRACT: DB00427  
TIP NUMBER: W-5702V  
WBS ELEMENT: 44848.3.22  
COUNTY: CRAVEN  
ROUTE: SR 1400 at SR 1450  
DESCRIPTION: CONSTRUCTION OF A ROUND-A-BOUT ON A NEW  
LOCATION AT SR 1400 AT SR 1450 IN CRAVEN COUNTY

**ADDENDUM 1**


TO: PROSPECTIVE BIDDERS

Please note the following revisions to the proposal.

- Addition of Line Number 52, Portable Changeable Message Sign, and Line Number 53, Flagger.
- Please see attached page A1-A4.
- A revised electronic file has been uploaded to bid express named DB00427.001.

**Please make sure to sign the addendum page in the proposal to acknowledge this addendum.**

Sincerely,

DocuSigned by:  
  
714C11DCCEBC4C6...

Mary Voelker Moore, PE  
Division Contract Engineer

cc: Ms. Heather C. Lane, PE  
Mr. Aaron Bullard, PE  
Mr. Cadmus Capehart, PE

Mailing Address:  
NC DEPARTMENT OF TRANSPORTATION  
DIVISION 2  
PROJECT DEVELOPMENT GROUP  
GREENVILLE, NC 27834

Telephone: (252) 439-2828  
Customer Service: 1-877-368-4968

Website: [www.ncdot.gov](http://www.ncdot.gov)

Location:  
1037 W.H. SMITH BLVD.  
GREENVILLE, NC 27834

Mr. Steve Hamilton, PE  
Mr. Jordan Scott, PE  
Mr. Lang Jones  
Mr. Jim Evans

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0057000000-E	226	UNDERCUT EXCAVATION	300 CY		
0005	0195000000-E	265	SELECT GRANULAR MATERIAL	300 CY		
0006	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	300 SY		
0007	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	20 TON		
0008	0320000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	50 SY		
0009	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	48 LF		
0010	0995000000-E	340	PIPE REMOVAL	32 LF		
0011	1121000000-E	520	AGGREGATE BASE COURSE	178 TON		
0012	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		
0013	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** (0 TO 3")	1,000 SY		
0014	1330000000-E	607	INCIDENTAL MILLING	100 SY		
0015	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	1,685 TON		
0016	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	1,260 TON		
0017	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	1,055 TON		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	175 TON		
0019	2542000000-E	846	1'-6" CONCRETE CURB & GUTTER	320 LF		
0020	2627000000-E	852	4" CONCRETE ISLAND COVER	358 SY		
0021	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	172 SY		
0022	2738000000-E	SP	GENERIC PAVING ITEM (12" CONCRETE TRUCK APRON)	498 SY		
0023	4102000000-N	904	SIGN ERECTION, TYPE E	32 EA		
0024	4237000000-N	907	STOCKPILE SIGN, D, E OR F	6 EA		
0025	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	288 SF		
0026	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	160 SF		
0027	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	32 SF		
0028	4430000000-N	1130	DRUMS	25 EA		
0029	4445000000-E	1145	BARRICADES (TYPE III)	32 LF		
0030	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	4,726 LF		
0031	4700000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (12", 90 MILS)	300 LF		
0032	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	48 EA		
0033	5325600000-E	1510	6" WATER LINE	460 LF		
0034	5329000000-E	1510	DUCTILE IRON WATER PIPE FITTINGS	1,000 LB		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	5540000000-E	1515	6" VALVE	3 EA		
0036	5800000000-E	1530	ABANDON 6" UTILITY PIPE	460 LF		
0037	5835000000-E	1540	*** ENCASEMENT PIPE (10")	70 LF		
0038	6000000000-E	1605	TEMPORARY SILT FENCE	1,800 LF		
0039	6012000000-E	1610	SEDIMENT CONTROL STONE	10 TON		
0040	6015000000-E	1615	TEMPORARY MULCHING	1 ACR		
0041	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0042	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.5 TON		
0043	6029000000-E	SP	SAFETY FENCE	250 LF		
0044	6036000000-E	1631	MATTING FOR EROSION CONTROL	200 SY		
0045	6071012000-E	SP	COIR FIBER WATTLE	100 LF		
0046	6071020000-E	SP	POLYACRYLAMIDE (PAM)	1 LB		
0047	6084000000-E	1660	SEEDING & MULCHING	1 ACR		
0048	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0049	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.5 TON		
0050	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	5 EA		
0051	6117500000-N	SP	CONCRETE WASHOUT STRUCTURE	1 EA		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0052	4420000000-N	1120	PORTABLE CHANGEABLE MESSAGE SIGN	4 EA		
0053	4455000000-N	1150	FLAGGER	20 DAY		

1032/Apr04/Q18040/D190149632000/E53

Total Amount Of Bid For Entire Project :