# STATE OF NORTH CAROLINA
# DIVISION OF HIGHWAYS
# SUMMARY OF QUANTITIES

| ITEM | SECT | QUANTITY | UNIT | ITEM DESCRIPTION |
|---|---|---|---|---|
| 1 | 800 | 1 | LS | MOBILIZATION |
| 2 | 801 | 1 | LS | CONSTRUCTION SURVEYING |
| 3 | 226 | 1 | LS | GRADING |
| 4 | 300 | 160 | TON | FOUNDATION CONDITIONING MATERIAL,MINOR STRUCTURES |
| 5 | 300 | 490 | SY | FOUNDATION CONDITIONING GEOTEXTILE |
| 6 | 305 | 272 | LF | 18" DRAINAGE PIPE |
| 7 | 305 | 116 | LF | 24" DRAINAGE PIPE |
| 8 | 310 | 36 | LF | 30" R.C.PIPE CULVERTS,CLASS III |
| 9 | 310 | 865 | LF | 36" R.C.PIPE CULVERTS,CLASS III |
| 10 | 310 | 8 | LF | 15" R.C.PIPE CULVERTS,CLASS IV |
| 11 | 310 | 48 | LF | 30" R.C.PIPE CULVERTS,CLASS IV |
| 12 | 310 | 96 | LF | 48" C.A.A.PIPE CULVERT,0.109" THICK |
| 13 | 340 | 428 | LF | PIPE REMOVAL |
| 14 | 545 | 200 | TON | INCIDENTAL STONE BASE |
| 15 | SP | 12.02 | SMI | SHOULDER RECONSTRUCTION |
| 16 | 607 | 1306 | SY | MILLING ASPHALT PAVEMENT, 0" TO 4" |
| 17 | 607 | 200 | SY | INCIDENTAL MILLING |
| 18 | 610 | 8,185 | TON | ASPHALT CONCRETE BASE COURSE,TYPE B25.0B |
| 19 | 610 | 4,645 | TON | ASPHALT CONCRETE INTERMEDIATE COURSE,TYPE I19.0B |
| 20 | 610 | 9,165 | TON | ASPHALT CONCRETE SURFACE COURSE,TYPE S9.5B |
| 21 | 620 | 1,145 | TON | ASPHALT BINDER FOR PLANT MIX |
| 22 | 654 | 130 | TON | ASPHALT PLANT MIX,PAVEMENT REPAIR |
| 23 | 838 | 17.5 | CY | ENDWALLS |
| 24 | 840 | 4 | EA | MASONRY DRAINAGE STRUCTURES |
| 25 | 840 | 3 | LF | MASONRY DRAINAGE STRUCTURES |
| 26 | 840 | 4 | EA | FRAME WITH TWO GRATES,STD 840.22 |
| 27 | 848 | 200 | SY | 6" CONCRETE DRIVEWAY |
| 28 | 876 | 10 | TON | RIP RAP,CLASS I |
| 29 | 876 | 5 | TON | RIP RAP,CLASS B |
| 30 | 876 | 50 | SY | GEOTEXTILE FOR DRAINAGE |
| 31 | 1105 | 1 | LS | TEMPORARY TRAFFIC CONTROL |
| 32 | SP | 224 | SF | WORK ZONE ADVANCE/ GENERAL WARNING SIGNING |
| 33 | 1205 | 64,721 | LF | THERMOPLASTIC PAVEMENT MARKING LINES (6",90 MILS) |
| 34 | 1205 | 17,820 | LF | THERMOPLASTIC PAVEMENT MARKING LINES (6",120 MILS) |
| 35 | 1205 | 40 | LF | THERMOPLASTIC PAVEMENT MARKING LINES (24",120 MILS) |
| 36 | 1253 | 400 | EA | SNOWPLOWABLE PAVEMENT MARKER |
| 37 | 1605 | 20,000 | LF | TEMPORARY SILT FENCE |
| 38 | 1610 | 5 | TON | STONE FOR EROSION CONTROL,CLASS B |
| 39 | 1610 | 5 | TON | SEDIMENT CONTROL STONE |
| 40 | 1630 | 5 | CY | SILT EXCAVATION |
| 41 | 1631 | 1,850 | SY | MATTING FOR EROSION CONTROL |
| 42 | 1632 | 140 | LF | 1/4" HARDWARE CLOTH |
| 43 | SP | 600 | LF | WATTLE |
| 44 | SP | 100 | LB | POLYACRYLAMIDE (PAM) |
| 45 | 1660 | 30.08 | ACRE | SEEDING AND MULCHING |
| 46 | SP | 3 | EA | RESPONSE FOR EROSION CONTROL |

REVISIONS

8/17/99

29-DEC-2014 11:23
S:\PROJECTS\CONES\NC41_70 toTrenton\NC41.dgn2_psh3.dgn
$$$$USERNAME$$$$