PROJECT NO.	SHEET NO.	TOTAL NO.
2SP.20745.1	3	4

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	ASPHALT SURFACE TREATMENT, DOUBLE SEAL SY	EMULSION FOR ASPHALT SURFACE TREATMENT GAL
2SP.20745.1	Pitt	1	SR 1200	FROM SR 1218 TO NC 121	1	2	2WU	NO	NO	2.888	22	37,300	18,650
TOTAL FOR MAP NO. 1										**2.888**		**37,300**	**18,650**
2SP.20745.1	Pitt	2	SR 1202	FROM NC 43 TO NC 43	1	2	2WU	NO	NO	3.994	20	46,900	23,450
TOTAL FOR MAP NO. 2										**3.994**		**46,900**	**23,450**
2SP.20745.1	Pitt	3	SR 1212	FROM SR 1200 TO NC 43	1	2	2WU	NO	NO	4.333	16	40,700	20,350
TOTAL FOR MAP NO. 3										**4.333**		**40,700**	**20,350**
2SP.20745.1	Pitt	4	SR 1217	FROM SR 1218 TO SR 1138	1	2	2WU	NO	NO	2.64	20	31,000	15,500
TOTAL FOR MAP NO. 4										**2.64**		**31,000**	**15,500**
2SP.20745.1	Pitt	5	SR 1218	FROM SR 1139 TO SR 1200	1	2	2WU	NO	NO	2.39	18	25,200	12,600
TOTAL FOR MAP NO. 5										**2.39**		**25,200**	**12,600**
2SP.20745.1	Pitt	6	SR 1220	FROM NC 121 TO SR 1200	1	2	2WU	NO	NO	1.87	20	22,000	11,000
TOTAL FOR MAP NO. 6										**1.87**		**22,000**	**11,000**
2SP.20745.1	Pitt	7	SR 1226	FROM SR 1304 TO NC 121	1	2	2WU	NO	NO	0.45	18	7,100	3,550
TOTAL FOR MAP NO. 7										**0.45**		**7,100**	**3,550**
2SP.20745.1	Pitt	8	SR 1232	FROM SR 1240 TO WILSON COUNTY LINE	1	2	2WU	NO	NO	4.25	20	50,400	25,200
TOTAL FOR MAP NO. 8										**4.25**		**50,400**	**25,200**
2SP.20745.1	Pitt	9	SR 1235	FROM NC 222 TO WILSON COUNTY LINE	1	2	2WU	NO	NO	0.3	20	3,600	1,800
TOTAL FOR MAP NO. 9										**0.3**		**3,600**	**1,800**
2SP.20745.1	Pitt	10	SR 1236	FROM SR 1232 TO SR 1231	1	2	2WU	NO	NO	1.25	20	14,700	7,350
TOTAL FOR MAP NO. 10										**1.25**		**14,700**	**7,350**
2SP.20745.1	Pitt	11	SR 1240	FROM SR 1241 TO SR 1232	1	2	2WU	NO	NO	1.47	20	16,500	8,250
TOTAL FOR MAP NO. 11										**1.47**		**16,500**	**8,250**
2SP.20745.1	Pitt	12	SR 1241	FROM SR 1200 TO SR 1232	1	2	2WU	NO	NO	3.29	20	36,100	18,050
TOTAL FOR MAP NO. 12										**3.29**		**36,100**	**18,050**
2SP.20745.1	Pitt	13	SR 1243	FROM SR 1240 TO SR 1200	1	2	2WU	NO	NO	3.83	20	43,900	21,950
TOTAL FOR MAP NO. 13										**3.83**		**43,900**	**21,950**
TOTAL FOR PROJ NO. 2SP.20745.1										**32.955**		**375,400**	**187,700**
GRAND TOTAL										**32.955**		**375,400**	**187,700**