PROJECT NO.	SHEET NO.	TOTAL NO.
2CR.10071.12	5	6

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	INCIDENTAL STONE BASE TONS	SHOULDER RECONSTRUCTION SMI	1 3/4 " MILLING SY	INCIDENTAL MILLING SY	BASE COURSE, B25.0B TONS	SURFACE COURSE, S9.5B TONS	ASPHALT BINDER FOR PLANT MIX TON	TEMPORARY SILT FENCE LF	COIR FIBER WATTLE LF	SEED & MULCHING AC
2CR.10071.12	Beaufort	1	NC 92	RESURFACING FROM END C&G EAST OF BATH TO BACK CREEK BRIDGE	1	2		NO	NO	0.3	27	150	0.60		222		482	29	200	100	0.219
		"	"	BACK CREEK BRIDGE	2	2	2WU	NO	NO	0.133	28			2,178			222	13			
		"	"	WIDEN 0'-2' LT, 0'-2' RT AS DIRECTED BY ENGINEER FROM BACK CREEK BRIDGE TO SR 1757	3	2	2WU	NO	NO	1.2	24		2.40			882	1,716	142			0.876
		"	"	RESURFACING FROM SR 1757 TO SR 1746	1	2	2WU	NO	NO	0.8	24		1.60				1,144	69			0.584
		"	"	WIDEN 0'-3' LT, 0'-3' RT AS DIRECTED BY ENGINEER FROM SR 1746 TO NC 306	3	2	2WU	NO	NO	2.8	24		5.60			4,372	4,004	433			2.040
		"	"	WIDEN 0'-3' LT, 0'-3' RT AS DIRECTED BY ENGINEER FROM NC 306 TO SR 1722	3	2	2WU	NO	NO	3.5	24		7.00		135	5,465	5,005	541			2.550
TOTAL FOR MAP NO. 1										**8.733**		**150**	**17.20**	**2,178**	**357**	**10,719**	**12,573**	**1,227**	**200**	**100**	**6.269**
2CR.10071.12	Beaufort	2	NC 99	RESURFACE BATH COMMUNITY EMS PARKING LOT	N/A	N/A	N/A	NO	NO								25	2			
TOTAL FOR MAP NO. 2																	**25**	**2**			
TOTAL FOR PROJ NO. 2CR.10071.12										**8.733**		**150**	**17.2**	**2178**	**357**	**10719**	**12598**	**1229**	**200**	**100**	**6.269**
GRAND TOTAL										**8.733**		**150**	**17.20**	**2,178**	**357**	**10,719**	**12,598**	**1,229**	**200**	**100**	**6.269**