STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
SUMMARY OF QUANTITIES

SECT	QUANTITY	UNIT	ITEM DESCRIPTION
800	1	LS	MOBILIZATION
801	1	LS	CONSTRUCTION SURVEYING
226	1	LS	GRADING
226	100	CY	UNDERCUT EXCAVATION (CONTINGENCY)
300	20	TON	FOUNDATION CONDITIONING MATERIAL,MINOR STRUCTURES
300	60	SY	FOUNDATION CONDITIONING GEOTEXTILE
310	180	LF	15" RC PIPE CULVERTS,CLASS IV
340	62	LF	PIPE REMOVAL
545	50	TON	INCIDENTAL STONE BASE
610	640	TON	ASPHALT CONCRETE BASE COURSE,TYPE B25.0B
610	1200	TON	ASPHALT CONCRETE INTERMEDIATE COURSE,TYPE I19.0B
610	730	TON	ASPHALT CONCRETE SURFACE COURSE,TYPE S9.5B
620	140	TON	ASPHALT BINDER FOR PLANT MIX,GRADE PG64-22
840	2	EA	BRICK DROP INLET
840	2	EA	DROP INLET FRAME AND GRATES
846	380	LF	8" X 12" CONCRETE CURB
852	50	SY	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)
1205	3750	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4",90 MILS)
1205	4500	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4",120 MILS)
1205	225	LF	THERMOPLASTIC PAVEMENT MARKING LINES (12",90 MILS)
1205	125	LF	THERMOPLASTIC PAVEMENT MARKING LINES (24",120 MILS)
1205	5	EA	THERMOPLASTIC PAVEMENT MARKING SYMBOLS (90 MILS)
1605	2150	LF	TEMPORARY SILT FENCE
1620	50	LB	SEED FOR TEMPORARY SEEDING
1620	0.2	TON	FERTILIZER FOR TEMPORARY SEEDING
SP	1	LB	POLYACRYLAMIDE (PAM)
SP	30	LF	WATTLE
1660	1	ACRE	SEEDING AND MULCHING
1661	50	LB	SEED FOR REPAIR SEEDING
1661	.2	TON	FERTILIZER FOR REPAIR SEEDING
SP	4	EA	RESPONSE FOR EROSION CONTROL

REVISIONS

8/17/99

31-MAR-2015 11:41
C:\WINDOWS\TEMP\RAVEN\4317Er-nul\4301?\W5601L_psh3.DGN
$$$$USERNAME$$$$