

North Carolina Department of Transportation

Highway Stormwater Program STORMWATER MANAGEMENT PLAN



(Version 2.07; Released October 2016)

FOR NCDOT PROJECTS

(Version 2.07; Released (T PROJECTS							
WBS Element:	45575.1.1	TIP No.:	3-5620	County(ies	: Beaufort				Page	1	of	2
				General Proje	ct Information							
WBS Element:		45575.1.1		TIP Number: B-5620		Projec	t Type:	Bridge Replacement	D	ate:	10/25/20	017
NCDOT Contact:		Robert T. Turnbull,	Environmental	Services, Inc.	Contractor / Design			h Carolina, P.C. / Jame	s A. Byrd,	PE		
Address:		4901 Trademark Dr				Address	343 E. Six I	Forks Road				
		Raleigh, NC 27610					Suite 200					
		•					Raleigh, NC 27609					
	Phone:	(919) 212-1760		Phone	none: (919) 424-0437							
		rturnbull@esinc.cc					ail: jabyrd@hntb.com					
City/Town:			Au	rora	County(ies):		eaufort					
River Basin(s):		Tar-Pam	CAMA County?		Yes							
Wetlands within Pro	ect Limits?	Yes			or and a country :			<u> </u>	ļ			
,				Project D	escription							
Project Length (lin. r	niles or feet).	0.18		Surrounding Land Use:	Rural Residential a	nd Agriculture						
		0.10	Proposed Project				Existing Sit	te				
Project Built-Upon A	rea (ac.)		0.6	ac.			0.5	ac.				
Typical Cross Section		2 - 11' asphalt pave		paved shoulders, 3' grass shou	ders.	2 - 9' asphalt		with grass shoulders.	Wetlands a	nd tributar	es to Car	mpbell
,,				, , , , , , , , , , , , , , , , , , , ,				our quadrants. CAMA w				
						wetlands.				_		
Annual Avg Daily Tra	affic (veh/hr/day):	Design/Future:		480 Ye	ar: 2033	Existing	:	240		Year	201	13
General Project Nari						C 33 over Campbell Creek. The existing bridge consists of 1 @ 25' - 6", 1 @ 24' - 11",						
(Description of Minir	nization of Water	@ 25' - 1", and 1 @	25'- 5" reinfor	ced concrete floor and continuo	us I-beams on reinforce	ed concrete ca	ps and timbe	er piles. It is to be replace	ced with a 1	1 @ 45' - 0'	', 1 @ 50'	' - 0"
Quality Impacts)		and 1 @ 45' - 0", 21	" cored slab (1	40' total length, 33' total width)	13' downstream of the	existing crossi	ng.					
				er Buffer Regulations, the propo								
					drainage system will outlet outside of the buffer limits in the west quadrant at -L- station 16+75 RT was specified at the outlet due to low velocity and agency's desire to minimize impacts.						with the	outlet
		pipe set at 0.3% to i	educe velocity	into the wetlands. No rip rap pa	outlet due to i	t due to low velocity and agency's desire to minimize impacts.						
				Waterbody	Information							
Surface Water Body	(1):		Campbe	ell Creek	NCDWR Stream Ir	ndex No.:	29-33-2-(2)					
_			34	Primary Classification:	Class				= \=/			
NCDWR Surface Wa	ter Classification for	r Water Body		Supplemental Classification:	High Quality Wa		(NSW)					
Other Stream Classification:			ouppioniental olassilication.	riigii Quality VVa	(11017)	(11011)			1		
Impairments:	iloution.										1	
Aquatic T&E Species? Comments:												
NRTR Stream ID:) i		Comments.				Buffer Bul	ne in Effect:		Ton	Damline	
	las Cooppins Mate	Podu?	/oo	Dook Draina Dischaus Com	Duffor?	No	Buffer Rules in Effect: Tar-Pamlic Dissipator Pads Provided in Buffer? N/A					
, , , ,				Deck Drains Discharge Over	justification in the General Project Narrative)			escribe in the General		rative: if no		n the
	•	/ ·		(ii yes, provide justilication	in the General Project	ivalialive)	(ii yes, d	escribe in the General Pro			, justily if	ıı uıe
(if yes, provid	le justification in the (senerai Project Narr	auve)	l				Ochoral I II	o _j oot r i uita			



North Carolina Department of Transportation

Highway Stormwater Program



(Version 2.07; Released October 2016)

STORMWATER MANAGEMENT PLAN
FOR NCDOT PROJECTS

WBS Element:			TIP No.: B-5620 County(ies): Beaufort						Page 2	of 2
Preformed Scour Holes and Energy Dissipators										
Sheet No.	Station & Coordinates (Road and Non Road Projects)	Surface Water Body	Energy Dissipator Type	Riprap Type	Drainage Area (ac)	Conveyance Structure	Pipe/Structure Dimensions (in)	Q10 (cfs)	V10 (fps)	BMP Associated w/ Buffer Rules?
4	-L- 16+44.78 RT 35.287275,-76.686840	(1)Campbell Creek	Riprap Energy Dissipator Basin	Class 'B'	0.1	Pipe	18	0.8	0.5	N/A
				Additional Co						

Additional Comments

STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS

BEAUFORT COUNTY

LOCATION: REPLACE BRIDGE NO. 30 OVER CAMPBELL CREEK ON NC 33 PERMIT DRAWING SHEET 1 OF 9


SHEET TOTAL NO. SHEETS

1

DESCRIPTION

TYPE OF WORK: GRADING, DRAINAGE, PAVING, AND STRUCTURE

PERMIT DRAWINGS: WETLAND & STREAM IMPACTS





NOTES:

PROFILE (VERTICAL)

- 1. CLEARING ON THIS PROJECT SHALL BE PERFORMED TO THE LIMITS ESTABLISHED BY METHOD II.
- 2. THIS PROJECT IS NOT WITHIN ANY MUNICIPAL BOUNDARIES.

FUNC CLASS =

REGIONAL TIER

MAJOR COLLECTOR

INCOMPLETE PLANS
DO NOT USE FOR R/W ACQUISITION

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

ONTRAC

GRAPHIC SCALES DESIGN DATA

ADT 2013 = 240
ADT 2033 = 480

K = 10 %
D = 60 %
T = 7 % *
V = 55 MPH

* TTST = 2% DUAL 5%

PROJECT LENGTH

LENGTH OF ROADWAY TIP PROJECT B-5620 = 0.155 MILES LENGTH OF STRUCTURE TIP PROJECT B-5620 = 0.026 MILES

TOTAL LENGTH OF TIP PROJECT B-5620 = 0.181 MILES

Prepared In the Office of: HNTB NORTH CAROLINA, P.C. 343 E. Six Forks Road, Suite 200 Raleigh, North Carolina 27609 NC License No: C-1554 2012 STANDARD SPECIFICATIONS RIGHT OF WAY DATE: PROJECT ENGINEER

DAVID W. BASS, PE
PROJECT ENGINEER

APRIL 10, 2017

MONICA J. DUVAL
PROJECT DESIGN ENGINEER

LETTING DATE:
OCTOBER 4, 2017

HON F. YEUNG, PE

HYDRAULICS ENGINEER

P.E.

NATURE:


ROADWAY DESIGN
ENGINEER


N.C.


45575.1.1

B-5620









STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS

BEAUFORT COUNTY


LOCATION: REPLACE BRIDGE NO. 30 OVER CAMPBELL CREEK **ON NC 33**

TYPE OF WORK: GRADING, DRAINAGE, PAVING, AND STRUCTURE

STATE	5"	TATE PROJECT REFE	SHEET NO.	TOTAL SHEETS				
N.C.		B-56	B-5620					
STAT	E PROJ. NO.	F. A. F	ROJ. NO.		ION			
45	575.1.1				PE			
			DEDAA	т	DD 7 ///	INIC		

PERMIT DRAWING SHEET 5 OF 9

PERMIT DRAWINGS: BUFFER IMPACTS





- 1. CLEARING ON THIS PROJECT SHALL BE PERFORMED TO THE LIMITS ESTABLISHED BY METHOD II.
- 2. THIS PROJECT IS NOT WITHIN ANY MUNICIPAL BOUNDARIES.

INCOMPLETE PLANS DO NOT USE FOR R/W ACQUISITION DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

PROFILE (VERTICAL)

GRAPHIC SCALES

DESIGN DATA

ADT 2013 = 240ADT 2033 = 480 K = 10 %

V = 55 MPH

* TTST = 2% DUAL 5% FUNC CLASS = MAJOR COLLECTOR **REGIONAL TIER**

PROJECT LENGTH

LENGTH OF ROADWAY TIP PROJECT B-5620 = 0.155 MILES LENGTH OF STRUCTURE TIP PROJECT B-5620 = 0.026 MILES

TOTAL LENGTH OF TIP PROJECT B-5620 = 0.181 MILES

Prepared in the Office of: HNTB NORTH CAROLINA, P.C. 343 E. Six Forks Road, Suite 200 Raleigh, North Carolina 27609 NC License No: C-1554 2012 STANDARD SPECIFICATIONS

RIGHT OF WAY DATE: APRIL 10, 2017

LETTING DATE: OCTOBER 4, 2017


DAVID W. BASS, PE PROJECT ENGINEER MONICA J. DUVAL

HON F. YEUNG, PE

ROADWAY DESIGN **ENGINEER**

HYDRAULICS ENGINEER





	WETLAND PERMIT IMPACT SUMMARY											
			WETLAND IMPACTS SURFACE WATER IN						E WATER IMP	ACTS		
Site No.	Station (From/To)	Structure Size / Type	Permanent Fill In Wetlands (ac)	Temp. Fill In Wetlands (ac)	Excavation in Wetlands (ac)	Mechanized Clearing in Wetlands (ac)	Hand Clearing in Wetlands (ac)	Permanent SW impacts (ac)	Temp. SW impacts (ac)	Existing Channel Impacts Permanent (ft)	Existing Channel Impacts Temp. (ft)	Natural Stream Design (ft)
1	-L- STA. 12+20 TO STA. 21+75	21" CORED SLAB BRIDGE (404)	0.07	0.00	0.02	0.04	0.00	0	0	0	0	0
1	-L- STA. 12+20 TO STA. 21+75	21" CORED SLAB BRIDGE (CAMA)	0.21	0.00	<0.01	0.08	0.00	0	0	0	0	0
1	-L- STA. 12+20 TO STA. 21+75	21" CORED SLAB BRIDGE	0.00	0.00	0.00	0.00	0.00	<0.01	<0.01	0	0	0
TOTALS:			0.28	0.00	0.02	0.12	0.00	<0.01	<0.01	0	0	0

Notes: Total Surface Water Impacts (include removal of existing piles and proposed piles) = 46.6 sq ft.

Temporary Impacts result from removal of existing piles and Permanent Impacts result from installation of proposed piles.

33 exitsing piles at 0.8 sq $\,$ ft per pile = 26.4 sq $\,$ ft.

14 proposed piles at 1.4 sq ft per pile = 20.2 sq ft.

NC DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS

BEAUFORT COUNTY BRIDGE NO. 030 B-5620

SHEET 7 OF 9 10/25/2017

RIPARIAN BUFFER IMPACTS SUMMARY **IMPACT** BUFFER REPLACEMENT **TYPE MITIGABLE** ALLOWABLE ZONE 2 TOTAL ZONE 1 ZONE 2 TOTAL ZONE 1 ZONE 1 ZONE 2 PARALLEL ROAD STATION CROSSING BRIDGE IMPACT (ft^2) (ft^2) (ft^2) (ft^2) (ft^2) SITE NO. STRUCTURE SIZE / TYPE (FROM/TO) 21" CORED SLAB BRIDGE -L- 15+02 TO 18+70 Χ 4746 4407 9153 TOTAL: 4746 4407 9153 0 0 0 0

N.C. DEPT. OF TRANSPORTATION DIVISION OF HIGHWAYS

BEAUFORT COUNTY BRIDGE NO. 030 PROJECT: B-5620

> DATE 10/25/2017 SHEET 8 OF 9

WETLANDS IN BUFFER IMPACTS SUMMARY WETLANDS IN **BUFFERS** ZONE 1 ZONE 2 STATION (ft^2) (ft^2) SITE NO. (FROM/TO) -L- 15+02-17+30LT 3153 3403 -L- 16+78 - 17+10RT 108 10 -L- 17+91 - 18+70LT 1069 795 -L- 18+02 - 18+37RT 49 113 TOTAL: 4443 4257

NOTE: THERE ARE NO IMPACTS TO BUFFERS OUTSIDE OF THE WETLANDS ALONG THE TRIB TO CAMPBELLS CREEK IN THE NORTHWEST QUADRENT OF THE PROJECT, THEREFORE BUFFER MITIGATION IS NOT REQUIRED.

N.C. DEPT. OF TRANSPORTATION DIVISION OF HIGHWAYS

BEAUFORT COUNTY BRIDGE NO. 030 PROJECT: B-5620

> DATE 10/25/2017 SHEET 9 OF