PROJECT REFERENCE NO.	SHEET NO.
W-5329	3

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
SUMMARY OF QUANTITIES

SECT	QUANTITY	UNIT	ITEM DESCRIPTION
800	1	LS	MOBILIZATION
801	1	LS	CONSTRUCTION SURVEYING
226	1	LS	GRADING
300	170	TON	FOUNDATION CONDITIONING MATERIAL,MINOR STRUCTURES
300	510	SY	FOUNDATION CONDITIONING GEOTEXTILE
305	202	LF	15" DRAINAGE PIPE
305	446	LF	18" DRAINAGE PIPE
305	216	LF	24" DRAINAGE PIPE
310	107	LF	15" RC PIPE CULVERTS,CLASS IV
310	33	LF	18" RC PIPE CULVERTS,CLASS IV
310	274	LF	24" RC PIPE CULVERTS,CLASS IV
310	79	LF	30" RC PIPE CULVERTS,CLASS IV
310	95	LF	54" RC PIPE CULVERTS,CLASS IV
310	75	LF	60" RC PIPE CULVERTS,CLASS IV
340	1065	LF	PIPE REMOVAL
610	1705	TON	ASPHALT CONCRETE BASE COURSE,TYPE B25.0B
610	1365	TON	ASPHALT CONCRETE INTERMEDIATE COURSE,TYPE I19.0B
610	2090	TON	ASPHALT CONCRETE SURFACE COURSE,TYPE S9.5B
620	270	TON	ASPHALT BINDER FOR PLANT MIX,GRADE PG64-22
838	16	CY	REINFORCED ENDWALLS
876	22	TON	RIP RAP,CLASS I
876	10	TON	RIP RAP,CLASS B
1205	9800	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4",90 MILS)
1205	70	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4",120 MILS)
1205	13100	LF	THERMOPLASTIC PAVEMENT MARKING LINES (6",120 MILS)
1205	190	LF	THERMOPLASTIC PAVEMENT MARKING LINES (12",90 MILS)
1205	110	LF	THERMOPLASTIC PAVEMENT MARKING LINES (24",120 MILS)
1205	25	EA	THERMOPLASTIC PAVEMENT MARKING SYMBOLS (90 MILS)
1605	4200	LF	TEMPORARY SILT FENCE
1620	50	LB	SEED FOR TEMPORARY SEEDING
1620	0.2	TON	FERTILIZER FOR TEMPORARY SEEDING
1660	1	ACRE	SEEDING AND MULCHING
1661	50	LB	SEED FOR REPAIR SEEDING
1661	.2	TON	FERTILIZER FOR REPAIR SEEDING
SP	350	LF	WATTLE
SP	24	LB	POLYACRYLAMIDE (PAM)
SP	4	EA	RESPONSE FOR EROSION CONTROL

SECT	QUANTITY	UNIT	ITEM DESCRIPTION
1510	4435	LF	8" WATER LINE
1510	175	LF	6" WATER LINE
1515	16	EA	RECONNECT WATER METER
1515	6	EA	RELOCATE WATER METER
1515	10	EA	8" VALVE
1515	2	EA	6" VALVE
1530	5000	LF	ABANDON 8" UTILITY PIPE
1540	106	LF	16" ENCASEMENT PIPE
1540	50	LF	12" ENCASEMENT PIPE
1550	580	LF	TRENCHLESS INSTALLATION OF 10" IN SOIL
1550	580	LF	TRENCHLESS INSTALLATION OF 10" NOT IN SOIL

REVISIONS

8/17/99

22-MAY-2015 10:11
C:\APPS\CONFIGNE\BROWN258\258Brown\brown258_psh3.dgn
$$$$USERNAME$$$$