# STATE OF NORTH CAROLINA
# DIVISION OF HIGHWAYS
# SUMMARY OF QUANTITIES

| SECT | QUANTITY | UNIT | ITEM DESCRIPTION |
| --- | --- | --- | --- |
| 800 | 1 | LS | MOBILIZATION |
| 801 | 1 | LS | CONSTRUCTION SURVEYING |
| 226 | 1 | LS | GRADING |
| 300 | 20 | TON | FOUNDATION CONDITIONING MATERIAL,MINOR STRUCTURES |
| 300 | 60 | SY | FOUNDATION CONDITIONING GEOTEXTILE |
| 310 | 120 | LF | 15" RC PIPE CULVERTS,CLASS IV |
| 310 | 32 | LF | 24" RC PIPE CULVERTS,CLASS IV |
| 340 | 194 | LF | PIPE REMOVAL |
| 610 | 1070 | TON | ASPHALT CONCRETE BASE COURSE,TYPE B25.0B |
| 610 | 1170 | TON | ASPHALT CONCRETE INTERMEDIATE COURSE,TYPE I19.0B |
| 610 | 530 | TON | ASPHALT CONCRETE SURFACE COURSE,TYPE S9.5B |
| 620 | 140 | TON | ASPHALT BINDER FOR PLANT MIX,GRADE PG64-22 |
| 838 | 3.5 | CY | REINFORCED ENDWALLS |
| 840 | 1.5 | CY | PIPE COLLAR |
| 848 | 10 | SY | 6" CONCRETE DRIVEWAY |
| 1205 | 3000 | LF | THERMOPLASTIC PAVEMENT MARKING LINES (6",90 MILS) |
| 1205 | 9900 | LF | THERMOPLASTIC PAVEMENT MARKING LINES (4",120 MILS) |
| 1205 | 100 | LF | THERMOPLASTIC PAVEMENT MARKING LINES (12",90 MILS) |
| 1205 | 45 | LF | THERMOPLASTIC PAVEMENT MARKING LINES (24",120 MILS) |
| 1205 | 6 | EA | THERMOPLASTIC PAVEMENT MARKING SYMBOLS (90 MILS) |
| 1620 | 50 | LB | SEED FOR TEMPORARY SEEDING |
| 1620 | 0.2 | TON | FERTILIZER FOR TEMPORARY SEEDING |
| SP | 3 | LB | POLYACRYLAMIDE (PAM) |
| SP | 170 | LF | WATTLE |
| 1660 | 1 | ACRE | SEEDING AND MULCHING |
| 1661 | 50 | LB | SEED FOR REPAIR SEEDING |
| 1661 | .2 | TON | FERTILIZER FOR REPAIR SEEDING |
| SP | 4 | EA | RESPONSE FOR EROSION CONTROL |

REVISIONS


8/17/99

08-MAY-2015 11:15
C:\APPS\PWWORK\TT\WC33.W5601K\Jethro33\33_jethro_psh3.dgn
$$$$USERNAME$$$$