DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA

# CROSS-SECTION SUMMARY

## IN CUBIC YARDS

| LOCATION (-L-) | UNCLASSIFIED EXCAVATION | UNDERCUT | EMBANKMENT |
|---|---|---|---|
| 14+00.00 | 0 | | 0 |
| 14+50.00 | 28 | | 10 |
| 15+00.00 | 33 | | 9 |
| 15+50.00 | 36 | | 11 |
| 15+83.00 | 15 | | 6 |
| 16+33.00 | 9 | | 13 |
| 16+67.00 | 8 | | 20 |
| 17+00.00 | 23 | | 47 |
| 17+33.00 | 35 | | 34 |
| 17+50.00 | 12 | | 3 |
| 18+00.00 | 16 | | 28 |
| 18+50.00 | 15 | | 43 |
| 19+00.00 | 20 | | 53 |
| 19+50.00 | 19 | | 60 |
| 20+00.00 | 12 | | 43 |
| 20+50.00 | 7 | | 31 |
| 21+00.00 | 6 | | 41 |
| 21+50.00 | 9 | | 50 |
| 22+00.00 | 11 | | 58 |
| 22+50.00 | 11 | | 65 |
| 23+00.00 | 24 | | 63 |
| 23+50.00 | 41 | | 69 |
| 23+78.15 | 25 | | 43 |
| 24+11.15 | 25 | | 41 |
| 24+44.15 | 18 | | 34 |
| 24+77.15 | 10 | | 28 |
| 25+27.15 | 11 | | 27 |
| 25+50.00 | 4 | | 8 |
| 26+03.68 | 5 | | 11 |
| | | | |

| LOCATION (-Y-) | UNCLASSIFIED EXCAVATION | UNDERCUT | EMBANKMENT |
|---|---|---|---|
| 10+00.00 | 0 | | 0 |
| 10+25.00 | 0 | | 4 |
| 10+50.00 | 6 | | 7 |
| 10+75.00 | 10 | | 10 |
| 11+00.00 | 7 | | 13 |
| 11+25.00 | 10 | | 14 |
| 11+50.00 | 6 | | 12 |
| | | | |

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT.

NOTE:

APPROXIMATE QUANTITIES ONLY. UNCLASSIFIED EXCAVATION, BORROW EXCAVATION, FINE GRADING, CLEARING AND GRUBBING AND REMOVAL OF EXISTING PAVEMENT WILL BE PAID FOR AT THE CONTRACT LUMP SUM PRICE FOR "GRADING."


Rev. 3/6/01
08-MAY-2015 11:15
S:\PROJECTS\DOT\NC33_W5601K\Jethro33\33_jethro_x1a.dgn
$$$$USERNAME$$$$